LiftAll PRODUCTS FOR BETTER LIFTING

Help

TABLE OF CONTENTS

Help
Introduction 3
Why *Lift-All* 4
Sling Inspections 4
Sling Selection 5
General OSHA & Manufacturer Requirements 6
Inspection 9
Physical Factor Affecting Sling Strength 9
Effect of Angle of Lift 10
Lift Evaluation and Operating Practices 11
Quality and Engineering Services 12
Safety in Lifting - Video / Seminar 12

Web Slings
Why *Lift-All* Web Slings 14
Environmental Considerations 14
Web Selector-Quick Comparisons 15
Inspection Criteria 16
Standard Web Sling Types 18
Web Sling Eye Treatments 19
Web Sling Information 20
How To Order Web Slings 21
Web Sling Hardware 22
Tuff-Edge II and *Webmaster 1600* 24
Dura-Web Nylon Slings 29
Webmaster 1200 30
Reverse Eye Slings 31
Tuff-Edge II Hardware / Bridle Slings 32
Wide Lift Slings 34
Drum Handling Slings 35
Stone Handling Slings 36
Gas Bottle Slings 37
Web Sling Weights 38

***Tuflex* Roundslings**
What is *Tuflex* 42
How to Order *Tuflex* Roundslings 43
Inspection Criteria 44
Endless 46
Eye and Eye 47
Braided 48
Keyflex 50
Wide Lift *Tuflex* 52
Stage Slings / *Steelflex* 52
Tuflex Hardware / Bridle Slings 54

***Hull Saver* Boat Slings** 56

Wire Rope and Slings
Wire Rope and Sling Basics, Environment 60
Inspection 61
How to Order Wire Rope Slings 62
Permaloc Wire Rope Slings 63
Permaloc Bridle Slings 64
Grommets and Endless Slings 65
E - Z Flex Cable Laid Slings 66
E - Z Flex Two Leg Bridles 67
E - Z Flex Endless 68
Hidden Tuck Hand Spliced Slings 69
Multi-Part Cabled Slings 70
Multi-Part Braided Slings 71
Swaged Threaded Studs 72
Swaged Socket Assemblies 73
Winch Lines, Hoist Line and Buttons 74
Wire Rope 75
Sling Attachments, Hooks, Etc. 76
Cable & Components 78
Wire Rope Sling Weights 80

***LiftAlloy* Chain Slings**
Chain Sling Basics, Features 84
How to Order 84
Capacity Chart 85
Inspection Criteria 86
Single and Double Slings 88
Triple, Quad and Basket 89
Adjustable and Endless 90
Adjust-A-Link 91
Hooks, Master Links, Etc. 92

***Roughneck* Mesh Slings**
Wire Mesh Slings 98
Chain Mesh Slings 100
Inspection Criteria 98, 100, 102

***Load Hugger* Cargo Control**
Load Hugger Basics 104
Web Selector 105
Ratchet Assemblies 106
Corner and Ratchet Protectors 109
Winch Strap Assembiles and Winches 110
E-Track and Van Interior Assemblies 111
Tie Down Chain and Binders 111

Lifting Beams and Custom Engineered Lifting Devices
Basics, How to Order 113
Custom Spreader Beams 114
Custom Alloy S and J Hooks 115
Standard Alloy J Hooks 116
Custom Coil and Pallet Lifters 117

***Tow All* Vehicle Strap** 118

Hoists
Manual Chain Hoists 119
Lever Pullers 120
Mini Lever Hoists 121

Accessories
Lodelok Hooks 122
Wear Pads 123
Hoist Rings 127
Lifting Application Worksheet 130
Conversion and Weight Tables 131

DEFINITION

⚠ WARNING as used throughout this catalog, serves to alert users to potentially hazardous situations which often occur in the use of these products. Failure to read, understand and follow the accompanying instructions on how to avoid these situations could result in death or serious injury.

HOW TO USE THIS CATALOG

If this is your first venture into slings, we suggest you read "Help" pages 3 through 12 to learn about the different types of slings and general safety rules. When you move on to the section containing your sling type, specific information regarding that type is located there.

If you know the type of sling you need, locate the section by looking for the colored page tab.

Specific ordering instructions are shown in each section of the catalog.

Note: All Dimensions and Specifications are Subject to Change Without Notice. Hardware dimensions are nominal and may vary depending on source. If dimensions are critical to your application, please specify your requirements.

INTRODUCING *LIFT-ALL*®

Company Profile

Started in 1964, *Lift-All* has grown to be the largest sling manufacturer in North America with over 250 employees working in five manufacturing locations around the United States. Corporate headquarters and the largest facility are located in Landisville, Pennsylvania. Manufacturing facilities and warehouses are strategically located throughout the U.S. Sales representatives cover the entire U.S., Canada and Mexico.

Sound engineering principles, and a serious concern for safety have been the standard by which innovative lifting products have been produced by *Lift-All* for over 40 years.

Lift-All's Mission Statement

Our mission is to be the trusted name in quality lifting and securement products and services by dedicating ourselves to customer satisfaction while providing exceptional value. Our long term success will be accomplished by a skilled workforce, committed to the principles of teamwork, integrity and performance.

Disclaimer of Warranties and Limitation of Liability

Seller warrants that its goods are free from defects in materials and workmanship. Accordingly, Seller's liability is limited to replacing without charge or refunding the purchase price, or making fair allowance for any noncompliance with any specifications or any defects in materials or workmanship in its products existing at the time of delivery. Seller requires written notice and the return of the product to establish any claim. SELLER MAKES NO OTHER WARRANTY OF ANY KIND WHATEVER, EXPRESS OR IMPLIED, AND ALL IMPLIED WARRANTIES OR MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE WHICH EXCEED THE ABOVE OBLIGATION ARE HEREBY DISCLAIMED BY SELLER AND EXCLUDED. Seller will not be liable for any consequential damages, loss or expense arising in connection with the use or inability whatever, regardless of whether damage, loss, or expense results from any act or failure to act by Seller, whether negligent or willful, or from any other reason.

Throughout this catalog trade names are shown in italic type.
All trade names are the property of *Lift-All* unless specifically identified by footnote as the property of another company.

© 2009 *Lift-All*
This publication may not be copied, in any form, without express written permission from *Lift-All*.

Why *Lift-All*?

Lift-All Promotes User Safety

- Safety Seminars and Sling Inspections are available to all sling users.
- *Lift-All* quality assurance procedures produce consistently superior products.
- Warning, inspection and operating practices information is supplied with every order.
- By manufacturing all types of slings, *Lift-All* will, without prejudice, recommend the best sling for the application.
- Traceability of all slings through serial numbers.

Lift-All Saves You Time

- *Lift-All* is the only source that can manufacture all of your sling needs.
- Our engineering staff can design the slings or lifting devices needed for special lifting applications.
- Local manufacturing and warehousing from five U.S. locations assures prompt delivery.
- *Lift-All* trained distributors are well qualified to assist the user in sling selection and application decisions.

Lift-All Saves You Money

- Our combination of uncompromising product quality, service and technology makes *Lift-All* your best choice in long term value.

SLING INSPECTIONS

Sling Inspection Services

OSHA regulations require that all chain slings receive a thorough inspection at least once per year by a competent person. You now have the opportunity to have a thorough, documented inspection performed by a factory trained *Lift-All* representative. Chain slings, wire rope slings, web slings, roundslings and wire mesh slings all can be inspected in one survey by a representative from the only company that makes them all - *Lift-All*.

The Inspection Procedure

Each sling is individually recorded and reported by location, serial number (if available), size, type, reach and condition.

If desired, we will affix a warning to those slings found to be damaged.

A Sling Survey Report will be printed and submitted to you for your records, showing the above information along with any recommendations we may have for improving your sling life and lifting safety.

If you wish to repair or replace any of the damaged slings, we will provide cost estimates to do so.







Sling Inspections not only help to insure safe lifting equipment but also increase employee awareness of sling safety, creating a safer workplace for all.

To inquire about or arrange for your Sling Inspection, please call our directed toll free phone number (800) 909-1964.

SLING SELECTION

Which Type of Sling Should I Choose?

General Use of Different Types of Slings

Synthetic Slings - Both Web Slings and Roundslings are used where loads must be protected from damage. The weight and flexibility of synthetic slings reduce fatigue and strain on riggers. *Tuflex* Roundslings, with their color coded capacities, and ease of use and inspection, are rapidly gaining in popularity.

Wire Rope Slings - The most common and lowest cost per ton of lift of all slings. Used in the construction industry and other industries where heavy loads and rugged conditions exist.

Chain Slings - Alloy chain slings combine superior strength, ease of handling and durability. The combination of heavy loads, elevated working temperatures and severe lift conditions usually dictate that an alloy chain sling be used. Typical chain sling applications are found in steel mills, foundries, and heavy machining operations requiring repetitive lifts.

Mesh Slings: Wire and Chain - These slings excel in lifting objects that are hot or have sharp edges, such as bar stock or plate steel. Mesh slings greatly enhance load balancing due to their wide load bearing surface. Machine shops and steel warehouses typically have good applications for mesh slings.

GENERAL OSHA AND MANUFACTURER REQUIREMENTS FOR ALL SLINGS

⚠ WARNING Read Definition on page 3

Safe Operating Practices

- Inspect slings prior to each use and do not use if damaged. (See specific sling type for inspection criteria.)



- Slings shall not be loaded in excess of their rated capacities. Rated capacities (Working Load Limits) must be shown by markings or tags attached to all slings.



- Angle of lift must be considered in all lifts. See page 10.





- Slings shall be padded or protected from the sharp edges of their loads.

- Slings shall be securely attached to their loads

- Loads must be rigged to prevent slippage.



- Lift must be stable with respect to the center of gravity - balanced.



Help

GENERAL OSHA AND MANUFACTURER REQUIREMENTS FOR ALL SLINGS

⚠ WARNING Read Definition on page 3

- Do not point load hooks - center load in base of hook.





- Suspended loads shall be kept clear of all obstructions.
- All persons shall be kept clear of loads to be lifted, and suspended load.

- Hands and fingers shall not be placed between the sling and load while the sling is being tightened around the load. After lifting, the load should not be pushed or guided by employees hands directly on the load. Ropes or "tag lines" should be attached for this purpose.





- Do not shock load. Jerking the load could overload the sling and cause it to fail.

GENERAL OSHA AND MANUFACTURER REQUIREMENTS FOR ALL

⚠ WARNING Read Definition on page 3

- A sling shall not be pulled from under a load when the load is resting on the sling. Before a load is lifted, a place should be prepared where it is to be put down. Lumber can be used to allow space to remove the sling and prevent shifting of the load.



- Sling legs shall not be kinked or twisted.

- Slings shall not be dragged on floor.

- Temperature and chemical environment must be considered (see specific sling types for data).





- Slings shall be stored in cool, dark, dry areas, preferably on racks.



- Slings shall not be shortened with knots, bolts, or makeshift devices.

Help

INSPECTION

⚠ WARNING Read Definition on page 3

Daily Inspection

Each day before using, the sling, all fastenings and attachments shall be inspected for damage or defects by a competent person designated by the employer. Additional inspections shall be performed prior to each use where severe conditions warrant. Damaged or defective slings shall be immediately removed from service.

Periodic Inspection

OSHA specifies that alloy steel chain slings shall have a thorough periodic inspection by a competent person at least once every 12 months. *Lift-All* recommends that all slings have a thorough inspection by a competent person at least once every 12 months. These inspections must be recorded and maintained for each individual sling. See the following pages for specific inspection recommendations: Web Slings: 16 & 17, *Tuflex* Roundslings: 44 & 45, Wire Rope Slings: 61, *LiftAlloy* Chain Slings: 86 & 87, Roughneck Mesh Slings: 98, 100 & 102, Lifting Beams and Custom Devices: 113. The warning sheets that accompany each order must be read and understood by all sling users. See sling abuse illustrations in their respective section of this catalog.

In some instances, it is possible to repair slings, proof test and return them to service. Damaged components and sections of chain or wire mesh can be replaced. Hooks, links and other components that are in good condition can be salvaged from a damaged web or round sling, rewebbed, proof tested by *Lift-All* and returned to service.

Repair

Lift-All strongly advises that damaged slings be repaired only by the manufacturer.

PHYSICAL FACTORS

⚠ WARNING Read Definition on page 3

Physical Factors Affecting Strength of Slings

Your care in the use and handling will prolong sling life significantly. The following physical factors should be considered when using any of the slings in this catalog:

1. Cutting of synthetic slings, Nicking or Gouging of steel slings. Probably the number one cause of sling failure. Usually caused by a sharp or small diameter load edge against the sling. It can be prevented with proper padding.
2. Improper Loading - Shock Loading, unbalanced loading, over loading and inadequate consideration for the effect of angle factors can adversely affect safety. Make sure the load weight is within the rated capacity of the sling(s) being used for both type of hitch and angle of lift. See "Effect of Angle of Lift" diagrams on page 10.
3. Temperature - Avoid loads and environments where temperatures exceed the limits of the slings being used. All slings can be damaged by excessive heat. See page 14 for Web Slings and *Tuflex* Roundslings, *Keyflex* Roundslings page 51, Wire Rope Slings page 60, *Lift-Alloy* Chain Slings page 84, Roughneck Mesh Slings page 98 & 100.
4. Punctures & Abrasions seriously degrade sling strength. Rough load surfaces and dragging slings on the ground will damage all slings, steel or synthetic. Use proper padding between slings and rough loads. Never drag slings on ground or concrete floors.
5. Foreign Matter - Material such as metal chips and heavy grit can damage web slings, both internally and externally. Both synthetic and steel slings can be damaged by weld spatter and heat from a welding torch. Avoid contact with foreign matter whenever possible.
6. Ultraviolet Light - Nylon and polyester web slings are adversely affected by prolonged exposure to UV light, i.e. sunlight or arc welding. Inspect and remove if slings appear bleached and stiff. Store slings properly when not in use (see No. 7 below).
7. Improper Storage - Even in storage, synthetic and steel slings can degrade if not kept in clean, dry conditions. *Lift-All* recommends hanging slings on a rack. Web sling should be stored in a dark area to avoid unnecessary sunlight/UV degradation.
8. Chemical Environment - Slings exposed to certain chemicals or the vapors of these chemicals can lose some or all of their strength. When using slings in a chemical environment, contact *Lift-All* to assure sling compatibility. See the following pages for specific information: Web Slings: 14, *Tuflex* Roundslings: 14, Wire Rope Slings: 60, *LiftAlloy* Chain Slings: 84, Roughneck Mesh Slings: 98 & 100.

Effect of Angle of Lift on a Sling's Rated Capacity

⚠ WARNING Read Definition on page 3

Using slings at an angle **can become deadly** if that angle is not taken into consideration when selecting the sling to be used. The tension on each leg of the sling is increased as the angle of lift, from horizontal, decreases. It is most desirable for a sling to have a larger angle of lift, approaching 90°. Lifts with angles of less than 30° from horizontal are not recommended. If you can measure the angle of lift or the length and height of the sling as rigged, you can determine the properly rated sling for your lift.

What would be the rating of each sling rigged at this angle?

1. Calculate the Reduction Factor [RF].
   a. Using the angle from horizontal, read across the Angle Chart to the corresponding number of the Reduction Factor column.
   - OR -
   b. Divide sling height* [H] by sling length* [L].
2. Reduction Factor [RF] x the sling's rated capacity for the type hitch that will be used = Sling's Reduced Rating.

* Measured from a common horizontal plane to the hoisting hook.





What capacity sling do I need?

1. Determine the weight that the sling will be lifting [LW].
2. Calculate the Tension Factor [TF].
   a. Using the angle from horizontal, read across the angle chart to the corresponding number of Tension Factor column.
   - OR -
   b. Divide sling length* [L] by sling height* [H].
3. Lifting Weight [LW] x the Tension Factor [TF] = Minimum Sling Rating for the type of hitch that will be used.

* Measured from a common horizontal plane to the hoisting hook.

Reduced Capacity



Example:
Vertical Choker rating of each sling = 6,000 lbs.
Measured Length (L) = 6 ft.
Measured Height (H) = 4 ft.
Reduction Factor (RF) = 4 (H) ÷ 6 (L) = .667
Reduced sling rating in this configuration = .667 (RF) x 6,000 lbs. = 4,000 lbs. of lifting capacity per sling

Effect of Angle Chart

Reduction Factor (RF)	Angle From Horizontal	Tension Factor (TF)
1.000	90˚	1.000
0.996	85˚	1.004
0.985	80˚	1.015
0.966	75˚	1.035
0.940	70˚	1.064
0.906	65˚	1.104
0.866	60˚	1.155
0.819	55˚	1.221
0.766	50˚	1.305
0.707	45˚	1.414
0.643	40˚	1.555
0.574	35˚	1.742
0.500	30˚	2.000

Sling capacity decreases as the angle from horizontal decreases. Sling angles of less than 30° are not recommended.

Increasing Tension



Example:
Load weight = 1,000 lbs.
Rigging - 2 slings in vertical hitch
Lifting Weight (LW) per sling = 500 lbs.
Measured Length (L) = 10 ft.
Measured Height (H) = 5 ft.
Tension Factor (TF) = 10 (L) ÷ 5 (H) = 2.0
Minimum Vertical Rated Capacity required for this lift = 500 (LW) x 2.0 (TF) = 1000 lbs. per sling

Help

Lift Evaluation and Operating Practices

⚠ WARNING Read Definition on page 3

Important Considerations - Before buying or using a sling, know as much as possible about the lift you will make to minimize the potential dangers to personnel, product and property. All of the following items should be evaluated.

Environment

- Crane and load foundation
- Obstruction in path of travel and for head height
- Power lines or other hazards
- Chemical conditions
- Temperature of load and surroundings
- Location of people - away from danger
- Inspect all equipment

Load

- Weight of load
- Center of gravity (drain liquids)
- Pick-up point integrity, including location and number
- Edges that may damage sling
- Abrasive areas that may damage sling
- Secure or remove loose parts
- Structural integrity (bending and crushing)

Rigging

- Type of sling required, including number of legs
- Type of hitch required
- Balance of load and stability, including flexing
- Prevention of load shift and movement against sling
- Angle of lift
- Tag line and spotter requirements
- Plan and procedures

See page 130 for our Lifting Application Worksheet.

Choker Hitch Angles



⚠ WARNING

Read Definition on page 3

When lifting and turning a load using a choker hitch, it is not uncommon to bend the body of the sling around the choker loop and have a severe bend occur around the body at this point.

For choker angles of 120° or less, the choker rating must be reduced by multiplying the corresponding factor times the slings standard choker rating.

Angle of Choke	Factor
Over 120°	1.00
90° - 120°	.87
60° - 89°	.74
30° - 59°	.62
0° - 29°	.49

Sling capacity decreases as choke angle decreases.

Effect of Anchor Shackle Pin or Crane Hook on Sling Eye



⚠ WARNING Read Definition on page 3

Damage to slings can occur if the wrong size pin or hook is used. The width of the pin or hook should never exceed the natural inside width of the eye.

The eye dimension for each type and size of sling are shown in the capacity tables of this catalog. If your pin or hook is large, request an oversized eye for the sling.

Lift-All is dedicated to manufacturing and developing products for material handling that meet or exceed current industry and government requirements (OSHA and ASME B30.9). Ultimately, the life and strength of any sling depends on those who inspect, use and maintain it.

The ASME B30.9 Sling Safety Standard can be obtained from:
ASME Customer Service
Phone: 800-843-2763
www.asme.org

Occupational Safety and Health Administration (OSHA) "Industrial Slings" Regulations are published by the Office of the Federal Register, National Archives and Records Administration - Part 29 1910.184
www.osha.gov

QUALITY AND ENGINEERING SERVICES

Quality Standards

Lift-All insures top quality products through a Quality Program, based predominately on Military Specification MIL-I-45208, which includes:

1. Detailed specifications for each product.
2. Testing of raw material prior to product manufacturing.
3. Random testing of finished products.
4. Proof testing as required (certificates available).
5. Final inspection of products prior to shipment.

Lift-All is dedicated to manufacturing and developing products for material handling that meet or exceed current industry and government requirements, including OSHA and ASME B30.9 for lifting slings. *Lift-All* products conform to the following:

Product Type	Standard /Specification
Cargo Securement	US DOT, FMCSA 393.102, WSTDA
Chain Slings	OSHA 1910.184, ASME B30.9, NACM
Hoists	ASME B30.16, B30.21
Roundslings	ASME B30.9, WSTDA
Webbing Slings	OSHA 1910.184, ASME B30.9, WSTDA
Wire Mesh Slings	OSHA 1910.184, ASME B30.9
Wire Rope Slings	OSHA 1910.184, ASME B30.9

Engineering Services

Fee based engineering services are available for lifting applications or custom product design and review. Contact *Lift-All* for details on this program.

SAFETY IN LIFTING

Safety Video Available

"Safety In Lifting", a 22 minute presentation is available in VCR and DVD format in both English and Spanish. It covers all types of slings: Web, Roundslings, Wire Rope, Chain and Wire Mesh. The Video suggests the best type of sling for common lifting applications, shows safe lifting procedures (in accordance with OSHA and ASME B30.9 guidelines), the proper inspection, care and maintenance of the various sling types, and more. Your in-plant training and safety program may be just a bit easier with some help from *Lift-All.*

Safety Seminar

Lift-All representatives are available to present a "Safety in Lifting" seminar at your location, improving your employees knowledge of slings in general and answering specific questions about your applications.

For details about the Video and/or "Safety in Lifting" Seminars call: *Lift-All* at 1-800-909-1964.

Web Slings

WHY *LIFT-ALL* WEB SLINGS?

Lift-All web slings meet or exceed OSHA, ASME B30.9 and WSTDA standards and regulations.

All of the sling webbing contained in this catalog is recommended for general purpose lifting. Military webbing, sometimes designated as "Mil-Spec", has not been designed for, nor do we recommend it for general lifting applications.

What is the Difference?

Refer to Mil-Spec Webbing Diagram

- Mil-Spec webbing does not have red core yarn warning system.
- Mil-Spec webbing supports the entire load with exposed surface yarns. *Lift-All* sling webbing uses a combination of internal protected yarns and surface yarns.
- Damage to the surface of Mil-Spec webbing causes greater strength reduction of the webbing.



Mil-Spec Webbing

- Combination binder/surface yarns cover each side and carry virtually all of the load.
- Transverse pick yarns inter-relate with binder/surface yarns.

Refer to *Lift-All* Sling Webbing Diagram

- Sling webbing, as shown, has its surface yarns connected from side to side, which not only protect the core yarns, but positions all surface and tensile yarns to work together to support the load.
- Wear or damage to Sling Webbing face yarns cause an immediate strength loss. This is why Sling Webbing has red core yarns to visually reveal damage and act as a basis for sling rejection.



***Lift-All* Sling Webbing**

- Transverse pick yarns inter-relate with binder/surface yarns.
- Woven surface yarns cover each side and carry a portion of the load.
- Strip of longitudinal core yarns bears majority of load.
- Binder yarns secure the surface yarns to web core yarns.
- Red core warning yarns.

ENVIRONMENTAL CONSIDERATIONS

⚠ WARNING Read Definition on page 3

- Nylon and polyester are seriously degraded at temperatures above 200°F.
- Prolonged exposure to ultraviolet light adversely affects nylon and polyester. Slings become bleached and stiff when exposed to sunlight or arc welding.
- Many chemicals have an adverse effect on nylon and polyester. See Chemical chart (this page).

Chemical Environment Data

General guide only. For specific temperature, concentration and time factors, please consult *Lift-All* prior to purchasing or use.

CHEMICAL \ OK / NO	NYLON	POLYESTER
Acids		*
Alcohols		
Aldehydes		
Strong Alkalis		**
Bleaching Agents		
Dry Cleaning Solvents		
Ethers		
Halogenated Hydro-Carbons		
Hydro-Carbons		
Ketones		
Oils Crude		
Oils Lubricating		
Soap & Detergents		
Water & Seawater		
Weak Alkalis		

* Disintegrated by concentrated sulfuric acid.
** Degraded by strong alkalis at elevated temperatures.

LIFT-ALL WEB SELECTOR - QUICK COMPARISONS

	Approx. Thickness	Single Ply Rated Capacity Per In. of Width	Available Material	Identify by:	Choose from:
	3/16"	1600 Lbs.	Polyester	Blue edge Blue center stripe Silver surface	Daily use under good to rugged lifting conditions. Superior edge cut resistance. Our best seller.*
	3/16"	1600 Lbs.	Polyester	Blue center stripe	Daily use under good to moderate lifting conditions. Polyester stretches less for better load control, reduced abrasion.*
	3/16"	1600 Lbs.	Nylon	No center stripe	Daily use under good to moderate lifting conditions. Nylon stretches more to help avoid shock loading.*
	1/8"	1200 Lbs.	Polyester	Blue center stripe Black yarn one edge	Less frequent use under good lifting conditions. Polyester stretches less for better load control, reduced abrasion.*
	1/8"	1200 Lbs.	Nylon	No center stripe- Black yarn one edge	Less frequent use under good lifting conditions. Nylon stretches more to help avoid shock loading.*
	5/16"	2000 Lbs.	Nylon	Two black center stripes	Heavy use under moderate to rugged lifting conditions. Abrasion resistant yarns cover entire surface.*
	3/16"	1000 Lbs.	Nylon	One black center stripe	Daily use under moderate lifting conditions. Abrasion resistant yarns cover entire surface.*

* **⚠ WARNING** Always use Wear Pads to protect synthetic slings from being cut by load edges.(See Page 123 for Wear Pad information)

INSPECTION CRITERIA FOR WEB SLINGS

All slings should be inspected for damage prior to each use to assure that their strength has not been compromised. The following photos illustrate some of the common damage that occurs to indicate that the sling should be taken out of service.

THE DAMAGE: **Surface and Edge Cuts** - It is important to realize that all of the fibers in web slings contribute to the strength of that sling. When there have been a significant number of fibers broken in a web sling, as shown here, that sling should be taken out of service.
WHAT TO LOOK FOR: **Broken fibers** of equal length indicate that the sling has been cut by an edge. **Red core warning yarns may or may not be visible with cuts and are not required to show before removing slings from service.**
TO PREVENT: Use **wear pads** (see page 123) between the sling and all edges that come in contact with the sling.







THE DAMAGE: **Holes/Snags/Pulls**
WHAT TO LOOK FOR: **Punctures or areas** where fibers stand out from the rest of the sling surface.
TO PREVENT: Avoid sling contact with protrusions, both during lifts and while transporting or storing.



THE DAMAGE: **Abrasion**
WHAT TO LOOK FOR: Areas of the sling that look and feel **fuzzy** indicate that the fibers have been broken by being subject to contact and movement against a rough surface. Affected areas are usually stained.
TO PREVENT: Never drag slings along the ground. Never pull slings from under loads that are resting on the sling. Use wear pads between slings and rough surface loads.



INSPECTION CRITERIA FOR WEB SLINGS

THE DAMAGE: **Heat/Chemical**

WHAT TO LOOK FOR: **Melted or charred fibers** anywhere along the sling. Heat and chemical damage can look similar and they both have the effect of damaging sling fibers and compromising the sling's strength. Look for discoloration and/or fibers that have been fused together and often feel hard or crunchy.
TO PREVENT: Never use nylon or polyester slings where they can be exposed to temperatures in excess of 200° F. Never use nylon or polyester slings in or around chemicals without confirming that the sling material is compatible with the chemicals being used.



THE DAMAGE: **Broken/Worn Stitching** in the main stitch patterns of web slings has a direct adverse effect on the strength of a sling. The stitch patterns in web slings have been engineered to produce the most strength out of the webbing. If the stitching is not fully intact, the strength of the sling may be affected.
WHAT TO LOOK FOR: **Loose or broken threads** in the main stitch patterns.
TO PREVENT: Never pull slings from beneath loads where stitch patterns can get hung up or snagged. Never overload the slings or allow the load edge to directly contact the stitch pattern while lifting. Never place a sling eye over a hook or other attachment whose width/diameter exceeds 1/3 the eye length.



THE DAMAGE: **Knots** compromise the strength of all slings by not allowing all fibers to contribute to the lift as designed. Knots may reduce sling strength by up to 50%.
WHAT TO LOOK FOR: **Knots** are rather obvious problems as shown below.
TO PREVENT: Never tie knots in slings and never use slings that are knotted.



THE DAMAGE: **Illegible or Missing Tags**- The information provided by the sling tag is important for knowing what sling to use and how it will function.
WHAT TO LOOK FOR: If you cannot find or read all of the information on a sling tag, OSHA requires that the sling shall be taken out of service.
TO PREVENT: Never set loads down on top of slings or pull sling from beneath loads if there is any resistance. Load edges should never contact sling tags during the lift. Avoid paint or chemical contact with tags.



Red Core Yarns - are an **additional** warning of dangerous sling damage. All standard *Lift-All* Web Slings have this warning feature. When red yarns are visible, the sling should be removed from service immediately. The red core yarns become exposed when the sling surface is cut or worn through the woven face yarns. For other inspection criteria see OSHA/Manufacturer regulations on pages 6 through 8.

STANDARD WEB SLING TYPES

Hardware Slings

Unilink and *Web-Trap* hardware can help to extend sling life by protecting the webbing from abrasion on rough crane hooks. Hardware can often be reused, lowering sling replacement costs.

Type U (UU) - Has the preferred and economical *Unilink* fitting on each end for use in a vertical, choker or basket hitch. *Unilinks* allow choking from either end to save time and vary wear points. See page 22.

Type U

Type 1 (TC) - Has a *Web-Trap* triangle and choker fitting on either end. Typical use is in a choker hitch. Can also be used in vertical and basket hitches.

Type 1

Type 2 (TT) - Has a *Web-Trap* triangle on each end. Normally used in a basket hitch, but can also be used in a vertical hitch. They cannot be used as a choker.

Type 2

Eye Type

Type 3 (EE) - Flat Eye slings are very popular and can be used in all three types of hitches. They are easier to remove from beneath the load than sling Types 1, 2 and 4. Unless Type 4 is requested, Type 3 will be supplied as the standard EE sling.

Type 3

Type 4 (EE) - Twisted Eye slings are similar to Type 3 except the eyes are turned 90° to form a better choker hitch. The eyes of a Type 4 nest better on the crane hook.



Type 4

Endless Type

Type 5 (EN) - Endless slings are versatile and the most economically priced. They can be used in all three types of hitches. The sling can be rotated to minimize wear. The sling legs can be spread for improved load balance.

Type 5

Reverse Eye Type

Type 6 (RE)-An endless sling with butted edges sewn together to double the sling width. They have reinforced eyes and wear pads on both sides of body and eyes. The result is an extremely strong and durable sling.

Type 6

WEB SLING EYE TREATMENTS

Eye Wear Pads - The eyes of web slings are often subjected to the harsh treatment of rough crane hooks. Specialty eye treatments are available to help reduce the wear in that area, thereby extending sling life. The following photos illustrate the more common eye treatments using wear resistant webbing in various forms. Should you want non-standard eye treatment on your eye & eye web slings, please specify using the terminology below.

Type 3 - Flat Eyes

Type 4 - Twisted Eyes

F		Standard Style	T	
G		Lined Bearing Point	U	
H		Fully Lined Eye	V	
I		Wrapped Bearing Point	W	

Textured nylon wear resistant webbing is standard for these eye treatments
Other wear pad materials are available (see page 123).

Tapering Eyes - As a standard practice, the eyes, or bearing points of sling Types 3 and 4 are tapered to accommodate a crane hook on slings that are 3" and wider. Untapered eyes are available upon request. Type 5 (Endless) slings are NOT tapered unless specified on order. Dura-Web 2000 slings are not tapered in any width.

Type 3 - Flat Eyes

Type 4 - Twisted Eyes

Type 5 - Endless
(Showing Taper)

WEB SLING INFORMATION

Sling Length Tolerance for Web Slings

Sling Type	Tolerance *
1 Ply	1.5" + 1.5% of sling length
2 Ply	2.0" + 2% of sling length
3 & 4 Ply	3.0" + 3% of sling length

* For web sling widths wider than 6", add 1/2" to these values. For tighter tolerance or matched set length requirements, please consult with Customer Service.

Anti-Abrasion Treatment

Lift-All recommends that web slings be manufactured from abrasion resistant latex treated webbing. Treatment is standard on both nylon and polyester web slings. Natural, untreated webbing is available upon request.

Note: Heavy duty treatments are available as a supplemental process for greater protection.

Tuff-Tag and Warning Sheet

OSHA requires all web slings to show rated capacities and type of material. The *Lift-All Tuff-Tag* is made from an abrasion resistant polymer that will remain legible far longer than any leather or vinyl tags. In fact, a *Tuff-Tag* will consistently outlast the useful life of a sling.

A Warning Sheet is included with every web sling order from *Lift-All.* The sheet lists inspection information and operating practices applying to synthetic web slings.

Elasticity - The stretch characteristics of web slings depends on the type of yarn and the web finish. Approximate stretch at RATED SLING CAPACITY is:

NYLON		POLYESTER	
Treated	10%	Treated	7%
Untreated	6%	Untreated	3%

Prior to sling selection and use, review and understand the "Help" section.

Always use Wear Pads to protect synthetic slings from being cut by load edges.

See page 123

HOW TO ORDER

We have revised our web sling code to better define the product you are ordering. Changes to our previous web sling code are shown below in red.


EE 1 8 02 T F X 12
Sling Type (Two Letters)
UU = Type U = Unilink Each End
TC = Type 1 = Triangle & Choker
TT = Type 2 = Triangle Each End
EE = Type 3 & 4 = Eye & Eye
EN = Endless
RE = Reversed Eyes
WL = Wide Lift
Sling Length
(One or Two Digits)
Use actual pull to pull length (Reach) in feet.
X Indicates that sling length follows.
EYE TREATMENTS *
(One Letter for Eye & Eye Class 6 & 8 Slings Only)
FLAT EYES (Type 3)
F = Standard
G = Lined Bearing Point
H = Fully Lined
I = Wrapped Bearing Point
TWISTED EYES (Type 4)
T = Standard
U = Lined Bearing Point
V = Fully Lined
W = Wrapped Bearing Point
*See Eye Treatments - pg. 19.
Tapered Eye Policy:
1" & 2" wide slings are not tapered. 3" and wider Class 6 & 8 sling eyes are tapered. Other treatments can be accommodated. Please specify at time of order.
Number of Plies
1, 2, 3 or 4
Web Class - (One Digit or Two Letters)
2 = Dura-Web 2000
1 = Dura-Web 1000
8 = Webmaster 1600 or Tuff-Edge II
6 = Webmaster 1200
SH = Stone Handling
Sling Width in inches (Two Digits)
Web Material (One Letter)
T = Tuff-Edge
D = Polyester
N = Nylon

WEB SLING HARDWARE

Steel *Unilink* Web Sling Hardware
Combination Triangle and Choker Fitting

U. S. Patent No. 4789193

This forged, high carbon steel fitting, functions as both a triangle and choker.

Features, Advantages and Benefits

Promotes Safety

- Forged steel for strength and reliability
- Smooth rounded profile helps protect sling, worker and load

Saves Money

- May be rewebbed to reduce cost
- Zinc dichromate plated for longer life
- *Unilinks* cost less than triangle/choker combinations

Saves Time

- Large Crane hook opening - speeds rigging
- Positive *Web-Trap* capture - no need to stop and reposition web
- Functions both as a triangle and a choker - choke with either end



Unilink Codes And Specifications

Web Width (in.)	Part No.	Dimensions (in).				Weight (lbs.)
		L	D	H	Thick	
2	SU2	3 11/16	2	11/16	9/16	1.1
3	SU3	5 1/16	3	7/8	5/8	2.4
4	SU4	6 3/16	4	1	3/4	4.0

Avoid contact of hardware with load edges.
Unilink has the same rated capacities as TT or TC slings.

Forged Aluminum Triangles and Chokers

⚠ WARNING Read Definition on page 3

Aluminum is severely degraded by alkali, caustic environments, acids and salt water.

Aluminum Triangles and Chokers are available but may only be used with single ply web slings within the rated capacities shown in the table. They should not be used with *Dura-Web* 2000 webbing.

Forged from aircraft aluminum, this tough alloy is stronger than mild steel. Aluminum has the advantages of being lightweight, non-sparking and does not rust.

Note: Aluminum triangles and chokers DO NOT offer the advantages of the *Web-Trap* feature. Aluminum fittings are not as durable and cost more than steel.

WEB SLING HARDWARE

Web-Trap Steel Sling Hardware - Triangles and Chokers

A significant improvement in triangle and choker design - featuring positive web capture. Webbing can slip to the side of ordinary fittings, not with *Web-Trap*. These fittings feature alloy steel for lighter sling weight and a zinc di-chromate plating to inhibit rust.



Webbing can slip with ordinary fittings.

Web-Trap prevents side shift.



Alloy Steel - For One Or Two Ply Slings

Web-Trap Triangles							*Web-Trap* Chokers						
Web Width	Part No.	Dimensions (in.)				Weight (lbs.)	Part No.	Dimensions (in.)					Weight (lbs.)
		L	D	T	H			L	A	D	T	H	
*2"	ST-2	2 3/8	1 3/4	1/2	5/8	1.0	SC-2	5	2 3/8	1 3/4	1/2	5/8	1.9
*3"	ST-3	3 7/16	2	1/2	3/4	1.9	SC-3	6 1/4	3 3/8	2	1/2	3/4	3.6
*4"	ST-4	4 1/8	2 3/8	1/2	13/16	2.8	SC-4	7	4	2 3/8	1/2	13/16	5.1
6"	ST-6	5 1/2	3 1/8	3/4	1 1/16	6.6	SC-6	9 1/2	5 1/2	3 1/8	3/4	1 1/16	12

Alloy Steel - For One Ply Slings

Web-Trap Triangles							*Web-Trap* Chokers						
Web Width	Part No.	Dimensions (in.)				Weight (lbs.)	Part No.	Dimensions (in.)					Weight (lbs.)
		L	D	T	H			L	A	D	T	H	
8"	ST1-8	7 3/4	4	1/2	1 1/4	8	SC1-8	11 1/4	7 1/2	4	1/2	1 7/16	16
10"	ST1-10	8 1/2	5	3/4	1 7/16	16	SC1-10	12 7/8	8 1/4	5	3/4	1 1/2	28
12"	ST1-12	8 1/2	5 1/2	3/4	1 3/4	20	SC1-12	14 1/2	10	5 1/2	3/4	1 3/4	40

Alloy Steel - For Two Ply Slings

Web-Trap Triangles							*Web-Trap* Chokers						
Web Width	Part No.	Dimensions (in.)				Weight (lbs.)	Part No.	Dimensions (in.)					Weight (lbs.)
		L	D	T	H			L	A	D	T	H	
8"	ST2-8	7 3/4	4	3/4	1 1/4	12	SC2-8	11 1/4	7 1/2	4	3/4	1 7/16	25
10"	ST2-10	8 1/2	5	1	1 7/16	21	SC2-10	12 7/8	8 1/4	5	1	1 1/2	38
12"	ST2-12	8 1/2	5 1/2	1	1 3/4	27	SC2-12	14 1/2	10	5 1/2	1	1 3/4	54

* *Unlink* is standard fitting - Triangle and chokers available on special order only.

TUFF-EDGE® II

2X Stronger After Abrasion
2X Better Edge Cut Resistance

Tuff-Edge II Polyester Web Slings

U. S. Patent No. 4856387

You can expect longer sling life and lower overall costs when you switch to *Tuff-Edge II* slings. Resistance to the two properties that can rapidly degrade webbing, abrasion and edge cutting, is greatly improved with the use of our *Tuff-Edge II* webbing.

Using Federal Test Method 191A, *Tuff-Edge II* webbing was tested against standard yellow polyester webbing. After being subjected to the same number of hex bar abrasion cycles, the *Tuff-Edge II* webbing, with its' special silver treatment, achieved average break strengths that were twice that of the standard yellow webbing!

In a test developed specifically to measure edge cutting properties, the cut depth on the *Tuff-Edge II* webbing with special polymer edge yarns cut less than half the depth of the standard yellow polyester without the special edge yarns.

Although you should **always** pad and protect synthetic slings from load edges, normal wear and tear should be greatly reduced when using *Tuff-Edge II*, giving you greater sling life and reduced sling costs.

Always use Wear Pads to protect synthetic slings from being cut by load edges.

See page 123



Tuff-Edge II Features, Advantages and Benefits

Promotes Safety

- Red Core yarn warning system aids in the inspection process
- *Tuff-Tag* provides serial numbered identification for traceability
- Proven sling web construction

Saves Money

- Special polymer coated edge yarns improve edge cutting and abrasion to extend sling life
- Silver colored web treatment fights abrasion for additional sling life
- *Tuff-Tag* provides required OSHA information for the life of the sling, not just the life of the tag

Saves Time

- Easy identification - silver body, blue edges, blue center stripe

TUFF-EDGE WORKS!

WIRE ROPE & RIGGING CONSULTANTS

CRANE & EQUIPMENT TRAINING

Ship/Mail • 9428 Old Pacific Hwy Woodland, WA 98674

Voice • (800) 727-6355 • (360) 225-1100 Fax • (360) 225-1122 www.wrrc.com • E-Mail • rigtrig@wrrc.com

January 4, 2001

We have about 400 slings in use at our Crane & Rigging Training Center in Woodland, WA, along with a major assortment of rigging hardware from almost every major manufacturer in the U.S. In the training center, our participants rig and move loads which are 1 to 6 ton. Most of the loads are rigged with synthetic web slings and some roundslings. We have about 80 LiftAll slings on the property, which are used with our gantry and mobile cranes.

Our rigging takes a beating like everyone else's, even using wear pads on most lifts. Mr. Dave Pelkey, one of our Woodland based trainers helps instruct our students to inspect their slings on a use-by-use basis. As a result of the lift-by-lift, daily, monthly and annual inspections he discovered something that really surprised all of us.

Your Tuff-Edge web slings have an amazing ability to endure heavy usage where other web slings do not. Every training program we watch our students use the Tuff-Edge slings right along with other sling types in reasonably equal amounts. They seem to do a much better job resisting the common types of abrasion, crushing and surface nicking. We seem to be rejecting only 1 Tuff-Edge type sling for every 10 regular synthetic web slings.

Even though we instruct our students to use wear pads, it is not always feasible for every lift. Often slight damage occurs against a semi-smooth surface as a result of high p.s.i. and tightening during the lift. The Tuff-Edge slings seem to survive extremely well, when other slings made of standard nylon or polyester begin to show physical evidence of wear and tear.

Due to our independent place in the crane and rigging industry, we rarely make comments about the products manufactured for general use. In this case, I thought we should at least extend a compliment to the developers and designers of the Tuff-Edge sling. We intend on replacing our inventory with Tuff-Edge slings as the other brands wear out. It will be an excellent investment for us, with a great return. Keep up the good work!

Mike Parnell
President

Charter Member ACRP Association of Crane & Rigging Professionals

WRRC & CET are divisions of Industrial Training International, Inc.

THE OHIO BROACH & MACHINE COMPANY

ISO 9001 Certified

February 12, 2001

While looking over our current inspection report, it occurred to me that we really haven't been disposing of as many slings as we have in the past. Upon closer review, it appears that most of the slings that Ohio Broach has in service are your silver Tuff-Edge type.

A couple of years back when Ohio Broach started to replace the bad slings with your Tuff-Edge slings, the rejection rate during inspections of our nylon slings was at least in the +50% range. Since then the rejection rate has dropped dramatically. This past year it was as low as 18%.

Having our slings last longer has saved the company money and more importantly, it provides Ohio Broach with a safer work environment.

I would definitely recommend your Tuff-Edge product to anyone who uses nylon slings.

Thank you for your time and efforts that keep our work place safe.

Sincerely,

Neil Van De Motter
Production Control Manager

BROACHES • OHIO BROACHING MACHINES • BROACH SHARPENING • PRODUCTION BROACHING

Webmaster 1600 Nylon and Polyester* Slings
The Traditional Standard for Heavy Duty Slings

This grade of synthetic web sling is popular because most users consider its' strength and service life to be a good buy.



Features, Advantages and Benefits

Promotes Safety

- Red core yarn warning system aids in the inspection process
- *Tuff-Tag* provides serial numbered identification for traceability
- Proven sling web construction

Saves Money

- Yellow treatment for abrasion resistance and extended sling life
- *Tuff-Tag* provides required OSHA information for the life of the sling, not just the life of the tag.

* Note: Polyester web is identified by single blue surface stripe.

TUFF-EDGE AND *WEBMASTER* 1600 POLYESTER SLINGS

Type U *Unilink* Hardware Slings

(Also available as Types 1 & 2 at same Rated Capacities)



	Tuff-Edge II Part No.	Web Width (in.)	Rated Capacity (lbs.)*			*Webmaster* Part No. ***
			Vertical	Choker	V. Basket	
One Ply	UU1802T UU1803T UU1804T	2 3 4	3,200 4,800 6,400	2,500 3,800 5,000	6,400 9,600 12,800	UU1802D UU1803D UU1804D
Two Ply	UU2802T UU2803T UU2804T	2 3 4	6,400 8,800 11,500	5,000 7,040 9,200	12,800 17,600 23,000	UU2802D UU2803D UU2804D

Type 1 (TC) and Type 2 (TT) *Web-Trap* Hardware Slings



Type 1 (TC)



Type 1 (TC)



Type 2 (TT)



Type 2 (TT)

	Tuff-Edge II Part No.		Web Width (in.)	Rated Capacity (lbs.)*			*Webmaster* Part No. ***	
	Type 1	Type 2**		Vertical	Choker	V. Basket	Type 1	Type 2**
One Ply	TC1806T TC1808T	TT1806T TT1808T	6 8	9,600 12,800	7,700 10,200	19,200 25,600	TC1806D TC1808D	TT1806D TT1808D
	TC1810T TC1812T TC1816T	TT1810T TT1812T TT1816T	10 12 16	16,000 19,200 25,500	12,800 15,400 20,400	32,000 38,400 51,000	TC1810D TC1812D TC1816D	TT1810D TT1812D TT1816D
Two Ply	TC2806T TC2808T	TT2806T TT2808T	6 8	16,800 22,400	13,400 17,900	33,600 44,800	TC2806D TC2808D	TT2806D TT2808D
	TC2810T TC2812T TC2816T	TT2810T TT2812T TT2816T	10 12 16	28,000 33,600 44,800	22,400 26,800 35,800	56,000 67,200 89,600	TC2810D TC2812D TC2816D	TT2810D TT2812D TT2816D

Note:
2", 3" and 4" Hardware Slings feature *Unilink* fittings.
(See dimensions page 22.)
Web-Trap Triangles and Chokers are also available.
(See dimensions page 23.)
Three and four ply hardware slings and wider width hardware slings are available upon request.
** Type 2 (TT) can not be used in a choker hitch.
*** Replace the "D" with an "N" to order nylon.
(See "How to Order" on page 21.)

* **⚠ WARNING**

Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°. Refer to Effect of Angle chart page 10.

TUFF-EDGE AND *WEBMASTER* 1600 POLYESTER SLINGS

Eye and Eye Slings (Flat or Twisted)

Type 3 (Flat Eye-F)

Type 3 (Flat Eye-F)



Type 4 (Twisted Eye-T)



Type 4 (Twisted Eye-T)

	Tuff-Edge II Part No.	Web Width (in.)	Rated Capacity * (lbs.) Vertical	Choker	V. Basket	*Webmaster* Part No. ***
One Ply	EE1801TF	1	1,600	1,280	3,200	EE1801DF
	EE1802TF	2	3,200	2,500	6,400	EE1802DF
	EE1803TF	3	4,800	3,800	9,600	EE1803DF
	EE1804TF	4	6,400	5,000	12,800	EE1804DF
	EE1806TF	6	9,600	7,700	19,200	EE1806DF
	EE1808TF	8	12,800	10,200	25,600	EE1808DF
	EE1810TF	10	16,000	12,800	32,000	EE1810DF
	EE1812TF	12	19,200	15,400	38,400	EE1812DF
Two Ply	EE2801TF	1	3,200	2,500	6,400	EE2801DF
	EE2802TF	2	6,400	5,000	12,800	EE2802DF
	EE2803TF	3	8,800	7,040	17,600	EE2803DF
	EE2804TF	4	11,500	9,200	23,000	EE2804DF
	EE2806TF	6	16,300	13,000	32,600	EE2806DF
	EE2808TF	8	19,200	15,400	38,400	EE2808DF
	EE2810TF	10	22,400	17,900	44,800	EE2810DF
	EE2812TF	12	26,900	21,500	53,800	EE2812DF
Three Ply	EE3801TF	1	4,100	3,300	8,200	EE3801DF
	EE3802TF	2	8,300	6,600	16,600	EE3802DF
	EE3803TF	3	12,500	10,000	25,000	EE3803DF
	EE3804TF	4	16,000	12,800	32,000	EE3804DF
	EE3806TF	6	23,000	18,400	46,000	EE3806DF
	EE3808TF	8	30,700	24,500	61,400	EE3808DF
	EE3810TF	10	36,800	29,400	73,600	EE3810DF
	EE3812TF	12	44,000	35,200	88,000	EE3812DF
Four Ply	EE4801TF	1	5,000	4,000	10,000	EE4801DF
	EE4802TF	2	10,000	8,000	20,000	EE4802DF
	EE4803TF	3	14,900	11,900	29,800	EE4803DF
	EE4804TF	4	19,800	15,800	39,600	EE4804DF
	EE4806TF	6	29,800	23,800	59,600	EE4806DF
	EE4808TF	8	39,700	31,700	79,400	EE4808DF
	EE4810TF	10	49,600	39,600	99,200	EE4810DF
	EE4812TF	12	59,500	47,600	119,000	EE4812DF

Always use Wear Pads to protect synthetic slings from being cut by load edges.

See page 123

Note:
Tapering - Types 3 and 4 slings are tapered at 3" and wider unless otherwise specified.
*** Replace the "D" with an "N" to order nylon. (See "How to Order" on page 21.)

* **⚠ WARNING**

Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases.
Slings should not be used at angles of less than 30°.
Refer to Effect of Angle chart page 10.

Eye Length (Applies to all Web Slings)

Plies of Web	Sling Width (in.) 1	2	3	4	6	8	10	12
1	8 1/2	10	11	12	16	20	24	24
2	8 1/2	10	11	12	16	20	24	24
3	10	12	14	16	18	24	24	24
4	10	12	14	16	18	24	24	24

TUFF-EDGE AND *WEBMASTER* 1600 POLYESTER SLINGS

Endless Slings

Type 5



Type 5

	Tuff-Edge II Part No.	Web Width (in.)	Rated Capacity * (lbs.)			*Webmaster* Part No. ***
			Vertical	Choker	V. Basket	
One Ply	EN1801T	1	3,200	2,500	6,400	EN1801D
	EN1802T	2	6,400	5,000	12,800	EN1802D
	EN1803T	3	8,600	6,900	17,200	EN1803D
	EN1804T	4	11,500	9,200	23,000	EN1804D
	EN1806T	6	16,300	13,000	32,600	EN1806D
	EN1808T	8	19,200	15,400	38,400	EN1808D
	EN1810T	10	22,400	17,900	44,800	EN1810D
	EN1812T	12	26,900	21,500	53,800	EN1812D
Two Ply	EN2801T	1	6,200	4,900	12,400	EN2801D
	EN2802T	2	12,400	9,900	24,800	EN2802D
	EN2803T	3	16,300	13,000	32,600	EN2803D
	EN2804T	4	20,700	16,500	41,400	EN2804D
	EN2806T	6	28,600	23,000	57,200	EN2806D
	EN2808T	8	30,700	24,500	61,400	EN2808D
	EN2810T	10	33,600	26,800	67,200	EN2810D
	EN2812T	12	37,600	30,000	75,200	EN2812D
Three Ply	EN3801T	1	8,000	6,400	16,000	EN3801D
	EN3802T	2	16,000	12,800	32,000	EN3802D
	EN3803T	3	21,500	17,200	43,000	EN3803D
	EN3804T	4	28,700	23,000	57,400	EN3804D
	EN3806T	6	40,700	32,500	81,400	EN3806D
	EN3808T	8	46,000	36,800	92,000	EN3808D
	EN3810T	10	51,500	41,200	103,000	EN3810D
	EN3812T	12	59,200	47,300	118,400	EN3812D
Four Ply	EN4801T	1	10,000	8,000	20,000	EN4801D
	EN4802T	2	19,800	15,800	39,600	EN4802D
	EN4803T	3	26,700	21,300	53,400	EN4803D
	EN4804T	4	35,600	28,400	71,200	EN4804D
	EN4806T	6	50,500	40,400	101,000	EN4806D
	EN4808T	8	57,600	46,000	115,200	EN4808D
	EN4810T	10	67,200	53,700	134,400	EN4810D
	EN4812T	12	80,700	64,500	161,400	EN4812D

Always use Wear Pads to protect synthetic slings from being cut by load edges.

See page 123

Note: Type 5 (Endless) slings are Not tapered unless specified.

***Replace the "D" with an "N" to order nylon.

(See "How to Order" page 21)

* **⚠ WARNING**

Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases.
Slings should not be used at angles of less than 30°.
Refer to Effect of Angle chart page 10.

Tuflex is an Alternative ...

For three and four ply slings wider than 6", *Tuflex* Roundslings should be seriously considered. *Tuflex* offers increased flexibility, ease of use and lower cost. (See pages 45 through 48.)

DURA-WEB NYLON SLINGS

Best in Abrasion Resistance

Available in two strength classes, all *Dura-Web* slings feature premium abrasive resistant yarns covering all surfaces, for extended sling life and long term value.

Dura-Web Features, Advantages and Benefits

Promotes Safety

- Red core yarn warning system aids in the inspection process
- Striped webbing helps identify proper capacity
- *Tuff-Tag* provides serial numbered identification for traceability

Saves Money

- Abrasion resistant fibers cover both faces and edges for greater sling life
- *Tuff-Tag* provides required OSHA information for the life of the sling, not just the life of the tag.

Saves Time

- Striped capacity for quick identification

Dura-Web 2000 Capacity

Two Black stripes = 2,000 lbs. per inch of width (one ply only). 25% stronger than other webbing. The strongest abrasion resistant sling available.

Eyes of *Dura-Web* 2000 slings for Types 3-4-5 are not tapered in any width.

Dura-Web slings meet or exceed OSHA and ASME B30.9 requirements.



Dura-Web 1000 Capacity

One Black Stripe = 1,000 lbs. per inch of width (one ply only). The only light duty web sling with an abrasive resistant surface. Wider bearing surface, per capacity, helps protect load surface.

Dura-Web slings meet or exceed OSHA and ASME B30.9 requirements.

	Part No.	Web Width (in.)	Rated Capacity (lbs.)* Vertical	Choker	V. Basket
			Type U		
One Ply	UU1202N UU1203N UU1204N	2 3 4	4,000 6,000 8,000	3,200 4,800 6,400	8,000 12,000 16,000
Two Ply	UU2202N UU2203N UU2204N	2 3 4	8,000 10,800 14,400	6,400 8,600 11,500	16,000 21,600 28,800
			Type 3-F	Type 4-T	
One Ply	EE1201NF EE1202NF EE1203NF EE1204NF	1 2 3 4	2,000 4,000 6,000 8,000	1,600 3,200 4,800 6,400	4,000 8,000 12,000 16,000
Two Ply	EE2201NF EE2202NF EE2203NF EE2204NF	1 2 3 4	4,000 8,000 10,800 14,400	3,200 6,400 8,600 11,500	8,000 16,000 21,600 28,800
			Type 5		
One Ply	EN1201N EN1202N EN1203N EN1204N	1 2 3 4	4,000 8,000 12,000 16,000	3,200 6,400 9,600 12,800	8,000 16,000 24,000 32,000
Two Ply	EN2201N EN2202N EN2203N EN2204N	1 2 3 4	7,800 15,200 20,400 25,800	6,200 12,200 16,300 20,600	15,600 30,400 40,800 51,600

	Part No.	Web Width (in.)	Rated Capacity (lbs.)* Vertical	Choker	V. Basket
			Type U		
One Ply	UU1102N	2	2,000	1,600	4,000
Two Ply	UU2102N	2	4,000	3,200	8,000
			Type 3-F	Type 4-T	
One Ply	EE1101NF EE1102NF	1 2	1,000 2,000	800 1,600	2,000 4,000
Two Ply	EE2101NF EE2102NF	1 2	2,000 4,000	1,600 3,200	4,000 8,000
			Type 5		
One Ply	EN1101N EN1102N	1 2	2,000 4,000	1,600 3,200	4,000 8,000
Two Ply	EN2101N EN2102N	1 2	3,900 7,600	3,100 6,100	7,800 15,200

* **⚠ WARNING** Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°.

WEBMASTER 1200 SLINGS

Webmaster 1200 Polyester Slings

Standard duty *Webmaster* 1200 is designed as an economical sling for less frequent use.

Webmaster Features, Advantages and Benefits

Promotes Safety

- Red core yarn warning system aids in the inspection process
- Proven sling web construction
- *Tuff-Tag* provides serial numbered identification for traceability

Saves Money

- Wider bearing surface per capacity helps protect load surface
- Yellow treatment for abrasion resistance and extended sling life
- *Tuff-Tag* provides required OSHA information for the life of the sling, not just the life of the tag



Types U, 1 and 2



Types 3(F) and 4(T)



Type 5

Note:

Tapering - Types 3 and 4 slings are tapered at 3" and wider unless otherwise specified.

Type 5 (Endless) slings are NOT tapered unless specified.

* **⚠ WARNING**

Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases.
Slings should not be used at angles of less than 30°.
Refer to Effect of Angle chart page 10.

Hardware Slings (TYPES U, 1 AND 2)

	Part No.	Rated Capacity (lbs.)*		
		Vertical	Choker	V. Basket
One Ply	UU1602D	2,400	1,900	4,800
	UU1603D	3,600	2,900	7,200
	UU1604D	4,800	3,800	9,600
	TC1606D	7,200	5,800	14,400
	TT1606D	7,200	NA	14,400
Two Ply	UU2602D	4,800	3,800	9,600
	UU2603D	6,600	5,280	13,200
	UU2604D	8,600	6,900	17,200
	TC2606D	12,600	10,100	25,200
	TT2606D	12,600	NA	25,200

Eye and Eye Slings (TYPES 3 AND 4)

One Ply	EE1601DF	1,200	950	2,400
	EE1602DF	2,400	1,900	4,800
	EE1603DF	3,600	2,900	7,200
	EE1604DF	4,800	3,800	9,600
	EE1606DF	7,200	5,800	14,400
Two Ply	EE2601DF	2,400	1,900	4,800
	EE2602DF	4,800	3,800	9,600
	EE2603DF	6,600	5,280	13,200
	EE2604DF	8,600	6,900	17,200
	EE2606DF	12,300	9,840	24,600
Three Ply	EE3601DF	3,500	2,800	7,000
	EE3602DF	7,000	5,600	14,000
	EE3603DF	9,400	7,500	18,800
	EE3604DF	12,000	9,600	24,000
	EE3606DF	18,000	14,400	36,000
Four Ply	EE4601DF	4,200	3,400	8,400
	EE4602DF	8,000	6,400	16,000
	EE4603DF	12,000	9,600	24,000
	EE4604DF	16,000	12,800	32,000
	EE4606DF	23,500	18,800	47,000

Endless Slings (TYPE 5)

One Ply	EN1601D	2,400	1,900	4,800
	EN1602D	4,800	3,800	9,600
	EN1603D	6,500	5,200	13,000
	EN1604D	8,600	6,900	17,200
	EN1606D	12,200	9,800	24,400
Two Ply	EN2601D	4,800	3,800	9,600
	EN2602D	9,600	7,700	19,200
	EN2603D	11,700	9,400	23,400
	EN2604D	15,500	12,400	31,000
	EN2606D	22,500	18,000	45,000
Three Ply	EN3601D	6,200	4,900	12,400
	EN3602D	12,500	10,000	25,000
	EN3603D	16,300	13,000	32,600
	EN3604D	20,600	16,400	41,200
	EN3606D	29,300	23,400	58,600
Four Ply	EN4601D	7,700	6,200	15,400
	EN4602D	15,500	12,400	31,000
	EN4603D	20,800	16,600	41,600
	EN4604D	26,600	21,200	53,200
	EN4606D	37,800	30,200	75,600

REVERSE *EYE SLINGS*

Reverse Eye (RE) Slings

The Best General Purpose Web Sling Available

The Reverse Eye Sling is a modified endless sling, reinforced and protected on all sides. The most rugged and versatile of all web slings. The *Lift-All* enhanced version incorporates premium wear resistant webbing for protection on ALL surfaces.

Reverse Eye Features, Advantages and Benefits

Promotes Safety

- Superior choke hitch performance grips load securely
- Reinforced eyes augment strength
- Red core yarn warning system aids in the inspection process
- *Tuff-Tag* provides serial numbered identification for traceability

Saves Money

- Wear resistant web cover offers superior abrasion resistance and sling life
- Reversible eyes reduce wear and increase sling life
- Top grade slings using *Tuff-Edge* webbing are armored on all four sides resulting in the toughest web sling available

Saves Time

- Eyes nest well on crane hook for easy rigging
- Flat eye construction is available to facilitate removal from under loads

There are two grades of *Lift-All* Reverse Eye Slings: *Tuff-Edge* and *Webmaster* 1200.

The Reverse Eye Sling is Not Just an Endless Sling with Wear Pads.

Single Ply Endless with Reinforced Eyes
A. Extended web length makes 2 Ply eyes.
B. Reinforcing web piece sewn on to make 2 Ply eye.



Added Wear Pads to Both Sides of Body and Eyes.
C. Single Ply Endless Sling with butted sides.
D. Texturized Wear Pads on both sides of eyes.
E. Texturized Wear Pads sewn on both sides of body.

Completed RE sling may be 1-2 or 3 ply endless sling with reinforcing webbing for each loop, and texturized wear pad on each side of eyes and sling body.

Heavy Duty RE Slings - *Tuff-Edge*

Standard Duty RE Slings - *Webmaster* 1200

	Part No.	Rated Capacity (lbs.)*			Sling Thickness (in.)	Sling Width (in.)	Eye Length (in.)	Part No.	Rated Capacity (lbs.)*			Sling Thickness (in.)
		Vertical	Choker	V. Basket					Vertical	Choker	V. Basket	
One Ply	RE1802T RE1804T RE1806T	4,500 7,700 11,000	3,600 6,200 8,800	9,000 15,400 22,000	5/16 5/16 5/16	2 4 6	9 12 15	RE1602N RE1604N RE1606N	3,600 6,800 8,000	2,900 5,400 6,400	7,200 13,600 16,000	1/4 1/4 1/4
Two Ply	RE2802T RE2804T RE2806T	6,500 13,000 20,000	5,200 10,400 16,000	13,000 26,000 40,000	1/2 1/2 1/2	2 4 6	9 12 15	RE2602N RE2604N RE2606N	5,200 10,500 14,400	4,200 8,400 11,500	10,400 21,000 28,800	3/8 3/8 3/8
Three Ply	RE3804T RE3806T	16,400 25,500	13,100 20,400	32,800 51,000	11/16 11/16	4 6	14 18	RE3604N RE3606N	14,000 20,000	11,200 16,000	28,000 40,000	1/2 1/2

Reverse eye slings using *Webmaster* 1600 webbing are available on special order.

* **⚠ WARNING** Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°. Refer to Effect of Angle chart page 10.

TUFF-EDGE II HARDWARE / BRIDLE SLINGS

Hardware/Bridle Slings

Useful when fixed lifting points are available.

Features, Advantages and Benefits

Promotes Safety

- *Tuff-Edge II* web material is standard - helps prevent sling damage
- Better load control and balance by using fixed fitting points and multiple legs
- Standard oblong links and hooks are forged from alloy steel for strength and reliability
- Red core yarn warning system aids in the inspection process
- Hardware avoids cutting and abrasion of sling at bearing points
- *Tuff-Tag* provides serial numbered identification for traceability
- Proven sling web construction

Saves Money

- Soft web sling legs protect load
- Endless type allows shifting of wear points
- *Tuff-Edge II* material extends sling life
- Sling hooks and links can be rewebbed
- *Tuff-Tag* provides required OSHA information for the life of the sling, not just the life of the tag

Saves Time

- Lighter weight and easier to use than chain or wire rope
- Sling hooks quickly connect to loads having hoist rings or eye bolts

How to Order

S O S - EE1801TF x 8

Number of Legs
S - (Single - 1)
D - (Double - 2)
T - (Triple - 3)
Q - (Quad - 4)

Master Link
O - (Oblong)

Bottom Attachments
S - (Sling Hook)
O - (Oblong)

Web Sling Code
Refer to page 21 for Code Definitions

Length of Assembly - Feet
Bearing point to bearing point

Web Slings

TUFF-EDGE II HARDWARE / BRIDLE SLINGS



SOS
Single Leg
Oblong Link
Sling Hook
(EE1801T)



DOS
Double Leg
Oblong Link
Sling Hook
(EE1801T)



TOS
Triple Leg
Oblong Link
Sling Hook
(EE1801T)



QOE
Quad Leg
Oblong Link
(EE1801T)





Hardware/Bridle Slings

Part No. For Web Sling Legs	Web Width (in.)	Web Plies	Number of Legs	Rated Capacity (lbs.)*				Oblong Link (in.)	Sling Hook Alloy	
				Vertical	@ 60°	@ 45°	@ 30°	A x B x C	Size	E x R x T (in.)
EE1801TF	1	1	Single	1,600				1/2 x 2 1/2 x 5	1TA	3/4 x 3 1/8 x 1
	1	1	Double		2,700	2,200	1,600	1/2 x 2 1/2 x 5	1TA	3/4 x 3 1/8 x 1
	1	1	Triple		4,100	3,300	2,400	3/4 x 3 x 6	1TA	3/4 x 3 1/8 x 1
	1	1	Quad		5,500	4,500	3,200	1 x 4 x 8	1TA	3/4 x 3 1/8 x 1
EE2801TF	1	2	Single	3,000				1/2 x 2 1/2 x 5	1 1/2TA	7/8 x 3 21/32 x 1 1/16
	1	2	Double		5,100	4,200	3,000	3/4 x 3 x 6	1 1/2TA	7/8 x 3 21/32 x 1 1/16
	1	2	Triple		7,700	6,300	4,500	3/4 x 3 x 6	1 1/2TA	7/8 x 3 21/32 x 1 1/16
	1	2	Quad		10,300	8,400	6,000	1 x 4 x 8	1 1/2TA	7/8 x 3 21/32 x 1 1/16
EE1802TF	2	1	Single	3,000				1/2 x 2 1/2 x 5	1 1/2TA	7/8 x 3 21/32 x 1 1/16
	2	1	Double		5,100	4,200	3,000	3/4 x 3 x 6	1 1/2TA	7/8 x 3 21/32 x 1 1/16
	2	1	Triple		7,700	6,300	4,500	3/4 x 3 x 6	1 1/2TA	7/8 x 3 21/32 x 1 1/16
	2	1	Quad		10,300	8,400	6,000	1 x 4 x 8	1 1/2TA	7/8 x 3 21/32 x 1 1/16
EE2802TF	2	2	Single	6,000				3/4 x 3 x 6	3TA	1 1/4 x 4 11/16 x 1 1/4
	2	2	Double		10,300	8,400	6,000	1 x 4 x 8	3TA	1 1/4 x 4 11/16 x 1 1/4
	2	2	Triple		15,500	12,700	9,000	1 x 4 x 8	3TA	1 1/4 x 4 11/16 x 1 1/4
	2	2	Quad		20,700	16,900	12,000	1 1/4 x 4 3/8 x 8 3/4	3TA	1 1/4 x 4 11/16 x 1 1/4

NOTE: Hardware capacities correspond to the appropriate sling capacities.

* **⚠ WARNING** Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°.
Refer to Effect of Angle chart page 10.

WIDE-LIFT SLINGS

Wide-Lift (WL) Slings

Wide Load Support and Balance

Lift-All Wide-Lift slings support the load over a wide area to offer better balance for large loads - whether heavy or light. Wide bearing area reduces marring of soft load surfaces. Stiffeners are used at the base of the eyes to deter the body webbing from folding down the middle. Wide-Lift slings are for use in basket hitch only. Standard web material is *Webmaster* 1600 nylon. Polyester is available upon request.

All Wide-Lift Slings offer these benefits:

Promotes Safety

- Red Core Yarn warning system aids in the inspection process
- *Tuff-Tag* provides serial numbered identification for traceability
- Proven sling web construction

Saves Money

- Wide bearing area reduces marring of soft load surfaces
- Yellow treatment for abrasion resistance and extended sling life
- *Tuff-Tag* provides required OSHA information for the life of the sling, not just the life of the tag

Attached Eye Wide-Lift

For Light, Bulky Loads - Lifting eyes are attached to a single ply sling body. Available with One Ply eyes (WLA1) or Two Ply eyes (WLA2).

	Body Width (in.)	Part No.	Rated Capacity* (lbs.) Vertical Basket	Eye Length (in.)	Minimum Sling Length (in.)
One Ply Eye	6	WLA1806N	5,000	10	50
	8	WLA1808N	5,000	10	50
	10	WLA1810N	5,000	12	54
	12	WLA1812N	5,000	12	56
	16	WLA1816N	10,000	12	56
	20	WLA1820N	10,000	18	68
	24	WLA1824N	10,000	18	72
Two Ply Eye	6	WLA2806N	10,000	10	50
	8	WLA2808N	10,000	10	50
	10	WLA2810N	10,000	12	54
	12	WLA2812N	10,000	12	56
	16	WLA2816N	18,000	12	56
	20	WLA2820N	18,000	18	68
	24	WLA2824N	18,000	18	72
	30	WLA2830N	18,000	18	72
	36	WLA2836N	18,000	22	88
	48	WLA2848N	18,000	30	122

Note: Not recommended for use in a choker hitch.
Tuff-Edge II may be used for the attached eyes.
Custom slings with higher capacities are available.
Tuflex slings are also available as Wide-Lift Slings. See page 52.

Continuous Eye Wide-Lift

For Heavy Loads - Constructed from one endless sling with the two body lengths butted and joined side by side.

	Body Width (in.)	Part No.	Rated Capacity* (lbs.) Vertical Basket	Eye Length (in.)	Minimum Sling Length (in.)
One Ply Eye	6	WL1806N	15,400	9	40
	8	WL1808N	20,400	12	45
	12	WL1812N	30,800	18	60
	16	WL1816N	38,000	24	72
	20	WL1820N	45,000	30	88
	24	WL1824N	52,000	36	100
	30	WL1830N	45,000	45	120
	36	WL1836N	45,000	54	144
Two Ply Eye	6	WL2806N	28,600	9	40
	8	WL2808N	38,000	12	45
	12	WL2812N	57,200	18	60
	16	WL2816N	75,000	24	72
	20	WL2820N	90,000	30	88
	24	WL2824N	110,000	36	100
	30	WL2830N	90,000	45	120
	36	WL2836N	90,000	54	144

* **⚠ WARNING**

Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°.
Refer to Effect of Angle chart page 10.

DRUM HANDLING SLINGS

Lift-All Drum Handling Slings provide an easy, inexpensive way to handle steel drums. Available in two styles to suit your needs for handling drums in the vertical or horizontal position.

Vertical

Vertical Drum Handling Slings

Easily lift standing drums for transport. Tilt suspended drums to pour from open top or spigot. For use with ribbed steel drums, the ratcheting belly band tightens securely below the first rib.

Lightweight version (**DSV601D**) uses 1" polyester sling webbing and is rated for 300 lb. loads.

Heavyweight sling (**DSV602D**) uses 2" polyester sling webbing and is rated at 850 lbs.

Promotes Safety

- A wear pad, sewn on one side of the lifting strap, helps to avoid cutting of the sling.
- Ratchet tightens securely.

Saves Time

- Free end of ratchet strap sewn to stay properly threaded.
- Vertical legs sewn to belly band to maintain proper position.

To Order, specify Part No. and drum diameter in inches. i.e.: DSV602Dx24
(The standard 55 gal. drum has a 24" diameter.)

Horizontal

Note: If using in a chemical environment, contact *Lift-All* for sling material advice.

Horizontal Drum Handling Slings

Ideal for the quick and easy moving of steel drums in the horizontal position.

Part No. **DSH601D** uses 1" polyester sling webbing and is rated at 1,500 lbs.

Promotes Safety

- Strong 1" polyester webbing pulls drum hooks securely into rims at both ends of the drum during lift.

Saves Time

- One sling fits multiple size drums.
- Easy to disconnect.
- Uses 1/2" oblong link at top for easy connection to hoist hook.

To Order, specify Part No. DSH601D.

STONE HANDLING SLINGS

Stone Handling (SH) Slings

Special abrasion resistant 4-inch nylon webbing for handling stone, concrete and building panels.

Lift-All Stone Handling Slings feature a soft abrasion resistant wear pad woven onto the load side of the webbing, providing outstanding protection for both the sling and the polished stone surfaces.

Note: EE Sling - flat eye only - untapered 12" eye length.

Features, Advantages and Benefits

Promotes Safety

- Red core yarn warning system aids in the inspection process
- *Tuff-Tag* provides serial numbered identification for traceability
- Proven sling web construction

Saves Money

- Heavy, soft yarns on load side to help protect the sling from abrasion
- White pile yarns prevent color transfer to load
- Two ply version results in an abrasion resistant face on both sides
- *Tuff-Tag* provides required OSHA information for the life of the sling, not just the life of the tag

Saves Time

- Two ply version with abrasion resistance on both sides, does not need orientation by rigger

	Part No.	Vertical	Choker	V. Basket
One Ply	UU1SH4N	5,400	4,000	10,800
	EE1SH4N	5,400	4,000	10,800
	EN1SH4N	10,800	8,600	21,600
Two Ply	UU2SH4N	9,400	7,000	18,800
	EE2SH4N	9,400	7,000	18,800
	EN2SH4N	10,800	8,600	21,600

* **⚠ WARNING**

Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°.

GAS BOTTLE SLINGS

These specialty web slings make for easy and secure lifting of your gas bottle cylinders into position using cranes, hoists, forklifts, etc. Two standard versions are available. **GBS1N** slings automatically adjust to accommodate 9" Dia. x 50" H to 13" Dia. x 39" H bottles. **GBS2N** slings are designed for the convenient tandem lifting of one oxygen and one acetylene bottle as used in most welding operations. Each assembly is rated to lift 1,000 lbs.





Leather reinforced eyes for extended sling life.

Top assembly collar fits around standard valve caps to secure top of cylinder

Square rings connect bottom and top assemblies and allow for automatic adjustment

Six legs on bottom assembly surround and secure base of cyclinder.

Abrasion resistant webbing lines both sides of legs at bottom for longer sling life.

2 ply leather base provides additional protection from abrasion and cutting

The GBS2N slings have the same construction features of the GBS1N slings, but have been designed specifically to lift one each of the standard size oxygen and acetylene bottles commonly used in welding operations.

WEB SLING WEIGHTS (Approx.)*



Type U (UU)

Part No.	Minimum Standard Length		Add'l. Ft.
	Ft.	Wt.** (lbs.)	Wt. (lbs.)
***Unilink* Style**			
UU1802	3	2.7	0.12
UU1803	3	5.6	0.18
UU1804	4	9.2	0.24
UU2802	3	2.9	0.25
UU2803	3	5.8	0.38
UU2804	3	9.2	0.50
Triangle & Choker Style			
TC1802	3	3.5	0.12
TC1803	3	6.3	0.18
TC1804	4	9.0	0.24
TC1806	4	21	0.36
TC1808	5	27	0.48
TC1810	5	48	0.60
TC1812	6	65	0.72
TC2802	3	3.6	0.25
TC2803	3	6.5	0.38
TC2804	3	9.1	0.50
TC2806	4	21	0.76
TC2808	4	39	1.0
TC2810	5	63	1.3
TC2812	5	86	1.5
Triangle & Triangle Style			
TT1802	3	2.6	0.12
TT1803	3	4.6	0.18
TT1804	3	6.7	0.24
TT1806	4	15	0.36
TT1808	5	19	0.48
TT1810	5	36	0.60
TT1812	5	44	0.72
TT2802	3	2.7	0.25
TT2803	3	4.8	0.38
TT2804	3	7.0	0.50
TT2806	3	15	0.76
TT2808	4	28	1.0
TT2810	4	46	1.3
TT2812	5	60	1.5





* Weights will vary. Published weights are average weights for *Webmaster* 1600 slings.

** Approximate weight for the minimum standard length as shown.

WEB SLING WEIGHTS (Approx.)*

Type 3 (Flat Eye)



Type 4 (Twisted Eye)

Type 5

Eye & Eye Style

	Minimum Standard Length		Add'l. Ft. Wt. (lbs.)
	Ft.	Wt. ** (lbs.)	
EE1801	3	0.4	0.06
EE1802	4	0.9	0.12
EE1803	4	1.4	0.18
EE1804	4	1.9	0.24
EE1806	5	3.4	0.36
EE1808	6	5.3	0.48
EE1810	8	8.0	0.60
EE1812	8	9.8	0.72
EE2801	3	0.4	0.13
EE2802	3	0.9	0.25
EE2803	4	1.7	0.38
EE2804	4	2.3	0.50
EE2806	6	4.9	0.76
EE2808	6	6.5	1.0
EE2810	7	9.4	1.3
EE2812	8	13	1.5
EE3801	4	1.0	0.20
EE3802	4	2.1	0.40
EE3803	5	3.7	0.59
EE3804	5	5.0	0.79
EE3806	5	7.6	1.2
EE3808	7	13	1.6
EE3810	7	16	2.0
EE3812	7	20	2.4
EE4801	4	1.1	0.26
EE4802	4	2.2	0.53
EE4803	5	4.1	0.79
EE4804	5	5.5	1.1
EE4806	5	8.3	1.6
EE4808	7	15	2.1
EE4810	7	19	2.6
EE4812	7	23	3.2

Endless Style

	Minimum Standard Length		Add'l. Ft. Wt. (lbs.)
	Ft.	Wt. ** (lbs.)	
EN1801	3	0.4	0.12
EN1802	3	0.8	0.24
EN1803	3	1.3	0.36
EN1804	3	1.7	0.48
EN1806	3	2.5	0.72
EN1808	3	3.4	0.96
EN1810	3	4.2	1.2
EN1812	3	5.0	1.4
EN2801	3	0.8	0.25
EN2802	3	1.6	0.50
EN2803	3	2.5	0.76
EN2804	3	3.3	1.0
EN2806	3	4.9	1.5
EN2808	3	6.6	2.0
EN2810	3	8.2	2.5
EN2812	3	9.9	3.0
EN3801	3	1.2	0.38
EN3802	3	2.4	0.76
EN3803	3	3.6	1.1
EN3804	3	4.8	1.5
EN3806	3	7.2	2.3
EN3808	3	9.6	3.0
EN3810	3	12	3.8
EN3812	3	14	4.5
EN4801	3	1.6	0.52
EN4802	3	3.2	1.0
EN4803	3	4.9	1.6
EN4804	3	6.5	2.1
EN4806	3	9.7	3.1
EN4808	3	13	4.2
EN4810	3	16	5.2
EN4812	3	19	6.2

* Weights will vary. Published weights are average weights for *Webmaster* 1600 slings.

** Approximate weight for the minimum standard length as shown.

WEB SLING WEIGHTS (Approx.)*

Attached Eye Wide-Lift

Part No.	10 Ft. Sling Wt. (lbs.)	Add'l. Ft. Wt. (lbs.)
WLA1806	3.8	0.36
WLA1808	4.9	0.48
WLA1810	5.6	0.60
WLA1812	6.2	0.72
WLA1816	9.5	1.1
WLA1820	12	1.3
WLA1824	14	1.6
WLA2806	4.2	0.36
WLA2808	5.4	0.48
WLA2812	7.4	0.72
WLA2816	12	1.1
WLA2820	15	1.3
WLA2824	16	1.6
WLA2830	17	2.0
WLA2836	17	2.4
WLA2848	20	3.2

Continuous Eye Wide-Lift

Part No.	10 Ft. Sling Wt. (lbs.)	Add'l. Ft. Wt. (lbs.)
WL1806	5.8	0.54
WL1808	7.1	0.66
WL1810	8.4	0.78
WL1812	9.7	0.90
WL1816	12	1.1
WL1820	15	1.4
WL1824	17	1.6
WL1830	23	2.2
WL1836	27	2.5
WL2806	9.4	0.9
WL2808	12	1.1
WL2812	17	1.6
WL2816	22	2.1
WL2820	27	2.6
WL2824	31	3.0
WL2830	41	4.0
WL2836	48	4.6

* Weights will vary. Published weights are average weights using *Webmaster* 1600 webbing.

THE *TUFLEX* DIFFERENCE

All *Lift-All* slings meet or exceed OSHA and ASME B30.9 standards and regulations.

What is a *Tuflex* Roundsling?

It is an endless synthetic sling made from a skein (continuous loop or hank) of polyester yarn covered by a double wall tubular jacket. The roundsling body can also be compared to sling webbing with the tubular jacket face yarns woven without binder yarns; this allows the core yarns to move independently within the jacket.

Tufhide Jacket

Made from bulked nylon fibers, the double wall *Tufhide* jacket offers better abrasion resistance for our larger capacity *Tuflex* (EN360 and larger). In addition, *Tufhide* reduces the heat buildup that can damage other high capacity roundslings when used in a choker hitch.

Tuflex Roundslings Features, Advantages and Benefits

Promotes Safety

- Light weight reduces fatigue and strain on riggers
- Synthetic materials won't cut hands
- Consistent matched lengths for better multiple sling load control
- No loss of strength from abrasion to cover
- *Tuff-Tag* provides serial numbered identification for traceability
- Low stretch (about 3% at rated capacity) - reduces sling and load abrasion - good for low headroom lifts
- Conforms to shape of load to grip securely
- Load bearing yarns protected from UV degradation
- Red striped white core yarns provide added visual warning of sling damage
- Color coding provides positive sling capacity information

Saves Money

- Double wall cover for greater sling life
- Soft cover won't scratch load surface
- Conforms to shape of load for reduced load damage
- Seamless - no sewn edges to rupture prematurely, requiring removal from service
- EN360 and larger *Tuflex* feature *Tufhide* wear resistant nylon jacket for extra sling life
- *Tuff-Tag* provides required OSHA information for the life of the sling, not just the life of the tag

Saves Time

- Color coded capacities for quick identification
- Light weight and pliable for easy rigging and storage
- Independent core yarns choke tightly, but release easily after use
- Easy to carry - high strength to weight ratio for easy transportation

Construction Comparisons - Sling Webbing vs *Tuflex*

Sling Webbing

- Transverse pick yarns inter-relate with binder yarns
- Woven surface yarns cover each side and carry a portion of the load
- Strip of longitudinal core yarns bears majority of load
- Binder yarns secure the surface yarns to web core yarns
- Red core warning yarns



Sling Webbing (Side View)

Sling webbing, as graphically demonstrated, has its surface yarns connected from side to side, to not only protect the core yarns, but to position all surface and tensile yarns to work together to support the load. Wear or damage to Sling Webbing face yarns cause an immediate strength loss. This is why Sling Webbing has red core yarns to visually reveal damage and act as a basis for sling rejection.

Tuflex Roundslings

Tuflex

- Transverse pick yarns position surface yarns and protect core yarns
- Woven surface yarns also protect core yarns, carry no load
- Longitudinal core yarns carry 100% of load
- Red core warning yarns



Tuflex
(Side View)

Roundsling construction, as shown above, protects all load carrying core yarns from abrasion with an independent, woven jacket. Replacement is not necessary until the red striped white core yarns can be seen through holes in the jacket. When core yarns are visible, sling must be removed from service. *Tuflex* roundslings provide double wall protection for extended sling life.

ENVIRONMENTAL CONSIDERATION

Refer to Page 14

HOW TO ORDER

Ordering *Tuflex* Polyester Roundslings

1. Specify sling Part No. found in the charts throughout the *Tuflex* section

2. Specify sling length in feet (bearing point to bearing point). Refer to footnotes under *Tuflex* tables for specific sling lengths and tolerances.

   Endless and Eye & Eye styles of *Tuflex* are made to a tolerance of ± 1% of the specified length (± 1" minimum tolerance) and can stretch 3% at rated capacity.

   Braided *Tuflex* length tolerance is ± 5% of the ordered length (sling at rest). At its rated capacity, braided *Tuflex* will stretch approximately 9%.

Note: Matched lengths of slings must be specified at time of order.

Prior to sling selection and use, review and understand the "Help" sections pages 3 through 12.

Always use Wear Pads to protect synthetic slings from being cut by load edges.

See page 123

INSPECTION CRITERIA FOR *TUFLEX*

All slings should be inspected for damage prior to each use to assure that their strength has not been compromised. The following photos illustrate some of the common damage that occurs to indicate that the sling must be taken out of service.

THE DAMAGE: Cuts to the cover exposing internal core yarns – When internal core yarns are visible, the amount of damage done to the core yarns and the sling strength can not be determined without breaking the sling, therefore, the sling must be taken out of service.

WHAT TO LOOK FOR: Broken fibers of equal length indicate that the sling has been cut by an edge.

TO PREVENT: Use wear pads between the sling and all edges that come in contact with the sling.



THE DAMAGE: Holes/Snags/Pulls exposing internal core yarns.

WHAT TO LOOK FOR: Punctures or areas where fibers stand out from the rest of the sling surface.

TO PREVENT: Avoid sling contact with protrusions, both during lifts and while transporting or storing.

THE DAMAGE: Abrasion exposing internal core yarns.

WHAT TO LOOK FOR: Areas of the sling that look and feel fuzzy indicate that the fibers have been broken by being subject to contact and movement against a rough surface. Affected areas are usually discolored.

TO PREVENT: Never drag slings along the ground. Never pull slings from under loads that are resting on the sling. Use wear pads between slings and rough surface loads.



INSPECTION CRITERIA FOR *TUFLEX*

THE DAMAGE: Heat/Chemical

WHAT TO LOOK FOR: Melted or charred fibers anywhere along the sling. Heat and chemical damage can look similar and they both have the effect of damaging sling fibers and compromising the sling's strength. Look for discoloration and/or fibers that have been fused together and often feel hard or crunchy.

TO PREVENT: Never use *Tuflex* where they can be exposed to temperatures in excess of 200°F. Never use *Tuflex* in or around chemicals without confirming that the sling mateiral is compatible with the chemicals being used. For elevated temperatures up to 350°F, ask about our KeyFlex roundslings.

THE DAMAGE: Illegible or Missing Tags –The information provided by the sling tag is important for knowing what sling to use and how it will function.

WHAT TO LOOK FOR: If you cannot find or read all of the information on a sling tag, the sling shall be taken out of service.

TO PREVENT: Never set loads down on top of slings or pull slings from beneath loads if there is any resistance. Load edges should never contact sling tags during the lift. Avoid paint or chemical contact with tags.

THE DAMAGE: Knots compromise the strength of all slings by not allowing all fibers to contribute to the lift as designed.

WHAT TO LOOK FOR: Knots are rather obvious problems as shown here.

TO PREVENT: Never tie knots in slings and never use slings that are knotted.



THE DAMAGE: Cuts to the cover NOT exposing internal core yarns –*Tuflex* roundslings all have a double walled jacket protecting the inner core yarns from damage. If damage (except for chemical or heat) appears only to the outer jacket and does not expose the inner core yarns, the sling may remain in service. To extend sling life, the sling may be returned to Lift-All for inspection and application of a patch to cover the damaged area.

WHAT TO LOOK FOR: Broken fibers of equal length indicate that the sling has been cut by an edge. In this case, the inner jacket remains intact.

TO PREVENT: Use wear pads between the sling and all edges that come in contact with the sling.

TUFLEX ENDLESS ROUNDSLINGS

Tuflex Endless (EN)
The Most Versatile *Tuflex* Roundsling

Features, Advantages and Benefits

Maintains all the basic *Tuflex* features plus...

Promotes Safety

- Load stability and balance can be achieved by spreading sling legs.

Saves Money

- Wear points can be shifted to extend sling life
- The most flexible style of sling



Part No.	Color	Rated Capacity (lbs.)* Vertical	Choker	Basket	Minimum Length (ft.)	Approximate Measurements Weight (lbs. / ft.)	Body Dia. Relaxed (in.)	Width at Load (in.)	Mimimum Hardware Dia. ** (in.)
EN30	Purple	2,600	2,100	5,200	1 1/2	.2	5/8	1 1/8	1/2
EN60	Green	5,300	4,200	10,600	1 1/2	.3	7/8	1 1/2	5/8
EN90	Yellow	8,400	6,700	16,800	3	.5	1 1/8	1 7/8	3/4
EN120	Tan	10,600	8,500	21,200	3	.6	1 1/8	2 1/8	7/8
EN150	Red	13,200	10,600	26,400	3	.8	1 3/8	2 1/4	1
EN180	White	16,800	13,400	33,600	3	.9	1 3/8	2 1/2	1 1/8
EN240	Blue	21,200	17,000	42,400	3	1.3	1 3/4	3	1 1/4
EN360	Grey	31,000	24,800	62,000	3	1.7	2 1/4	3 3/4	1 1/2
EN600	Brown	53,000	42,400	106,000	8	2.8	2 3/4	4 5/8	1 7/8
EN800	Olive	66,000	52,800	132,000	8	3.4	3 1/8	5 1/4	2 1/8
EN1000	Black	90,000	72,000	180,000	8	4.3	3 5/8	6	2 1/2

* **⚠ WARNING** Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°.
Refer to Effect of Angle chart page 10.
** This is the smallest recommended connection hardware diameter to be used for a vertical hitch.

TUFLEX EYE AND EYE

A More Rugged and Durable *Tuflex*

The Eye and Eye Advantage

An additional jacket of texturized, abrasion resistant nylon covers the body of the standard *Tuflex*, forming two color coded lifting eyes.

Maintains all the basic *Tuflex* features plus ...

- Saves money by extending sling life where abrasion to sling body is a problem.



Part No.	Color of Eyes	Rated Capacity (lbs.)* Vertical	Choker	Basket	Minimum Length (ft.) +	Approximate Measurements Weight (lbs./ft.)	Body Width at Load (W) (in.)	Standard Eye Length (EL) (in.)	Mimimum Hardware Dia. ** (in.)
EE30	Purple	2,600	2,100	5,200	4	.25	2 1/4	10	1/2
EE60	Green	5,300	4,200	10,600	4	.36	2 1/2	10	5/8
EE90	Yellow	8,400	6,700	16,800	4	.50	2 1/2	12	3/4
EE120	Tan	10,600	8,500	21,200	5	.60	3 1/2	12	7/8
EE150	Red	13,200	10,600	26,400	5	.84	3 1/2	14	1
EE180	White	16,800	13,400	33,600	7	.96	3 1/2	16	1 1/8
EE240	Blue	21,200	17,000	42,400	7	1.5	4 1/4	16	1 1/4
EE360	Grey	31,000	24,800	62,000	7	1.8	6	20	1 1/2
EE600	Brown	53,000	42,400	106,000	8	2.7	7	24	1 7/8
EE800	Olive	66,000	52,800	132,000	10	3.3	8	30	2 1/8
EE1000	Black	90,000	72,000	180,000	12	4.2	9	36	2 1/2

* **⚠ WARNING** Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°.
Refer to Effect of Angle chart page 10.
** This is the smallest recommended connection hardware diameter to be used for a vertical hitch.
+ Shorter lengths available using reduced eye lengths.

BRAIDED *TUFLEX* ROUNDSLINGS

For the ultimate in big loads - (up to 612,000 lbs. in a vertical basket)
or for the security of multiple part sling lifting.

Redundant Safety

Tuflex braids are made from three [6 part] or four [8 part] individual *Tuflex*. Should one of these component slings be damaged while in use, the remaining undamaged slings should be able to safely return the load to the ground.



Braided *Tuflex* Features, Advantages and Benefits

Maintains all the basic *Tuflex* features plus ...

Promotes Safety

- Braided construction offers redundant safety
- User friendly compared to steel slings

Saves Money

- Large capacity slings are generally purchased for one major lift, then rarely used again. Braided *Tuflex* can be disassembled into component slings for general purpose lifting, if individual slings are correctly tagged.
- Can be returned for disassembly, inspection and retagging as individual slings.

Saves Time

- Easy to transport and hook-up

6 Part Flat Braid (B6E)

Part No.	Color	Rated Capacity (lbs.)* Vertical	Choker	Basket	Minimum Length (ft.) +	Approximate Measurements Weight (lbs./ft.)	Standard Eye Length (EL) (in.)	Width at Load (W) (in.)	Thickness at Load (in.)	Eye Dia. (ED) (in.)	Mimimum Hardware Dia. ** (in.)
B6E30	Purple	6,700	5,300	13,400	4 1/2	.8	15	3 1/4	3/4	1 3/4	5/8
B6E60	Green	13,500	10,800	27,000	5	1.2	15	3 3/4	1 1/8	2	1
B6E90	Yellow	21,400	17,100	42,800	5 1/2	1.6	15	4 1/4	1 1/4	2	1 1/4
B6E120	Tan	27,000	21,600	54,000	5 1/2	2.0	15	4 1/2	1 5/16	2 1/4	1 3/8
B6E150	Red	33,600	26,800	67,200	6 1/2	2.7	20	5 1/4	1 3/4	2 1/2	1 1/2
B6E180	White	42,800	34,200	85,600	7	3.2	20	5 1/2	2	2 3/4	1 3/4
B6E240	Blue	54,000	43,200	108,000	9	4.4	20	6 5/8	2 1/4	3 1/2	1 3/4
B6E360	Grey	79,000	63,200	158,000	9 1/2	6.5	30	8 1/4	2 1/2	4 1/4	2 1/2
B6E600	Brown	135,100	108,000	270,200	10 1/2	9.7	30	11	2 3/4	5	3
B6E800	Olive	168,300	134,600	336,600	13	12.0	30	12	4	5 1/4	3 1/2
B6E1000	Black	229,500	183,600	459,000	14 1/2	15.6	31	13 1/2	4 1/2	5 3/4	4

* **⚠ WARNING** Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°.
Refer to Effect of Angle chart page 10.
** This is the smallest recommended connection hardware diameter to be used for a vertical hitch.
+ Shorter lengths available using reduced eye lengths.

BRAIDED *TUFLEX* ROUNDSLINGS

Order Information

Ordering length should be based on sling at rest.

Braided *Tuflex* length tolerance is ±5% of the ordered length (sling at rest).

At its rated capacity, braided *Tuflex* will stretch approximately 9% and have a length variance of ±2%.

Always use Wear Pads to protect synthetic slings from being cut by load edges.

See page 123

8 Part Round Braid (B8E)

Part No.	Color	Rated Capacity (lbs.)* Vertical	Choker	Basket	Minimum Length (ft.) +	Approximate Measurements Weight (lbs./ft.)	Standard Eye Length (EL) (in.)	Width at Load (W) (in.)	Thickness at Load (in.)	Eye Dia. (ED) (in.)	Mimimum Hardware Dia. ** (in.)
B8E30	Purple	8,800	7,100	17,600	4 1/2	1.1	15	3 1/2	1	1 3/4	3/4
B8E60	Green	18,000	14,400	36,000	5	1.5	15	4	1 3/8	2	1 1/8
B8E90	Yellow	28,500	22,800	57,000	5 1/2	2.2	15	4 3/4	1 5/8	2 1/2	1 1/2
B8E120	Tan	36,000	28,800	72,000	5 1/2	2.6	15	5	1 3/4	2 1/2	1 1/2
B8E150	Red	44,900	35,900	89,800	6 1/2	3.6	20	6	2 1/8	2 3/4	1 3/4
B8E180	White	57,100	45,600	114,200	7	4.1	20	6 1/4	2 1/2	3 1/4	2
B8E240	Blue	72,000	57,600	144,000	9	5.6	20	7 1/2	2 3/4	3 3/4	2
B8E360	Grey	105,400	84,300	210,800	9 1/2	8.3	30	9 1/2	3 1/4	4 1/2	2 1/2
B8E600	Brown	180,200	144,100	360,400	10 1/2	12.0	30	13	3 3/4	5 1/2	3 1/2
B8E800	Olive	224,400	179,500	448,800	13	16.0	30	13 1/2	4 1/2	6	4
B8E1000	Black	306,000	244,000	612,000	14 1/2	20.0	31	15 3/4	5 1/4	6 1/2	4 3/4

* **⚠ WARNING** Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°. Refer to Effect of Angle chart page 10.

** This is the smallest recommended connection hardware diameter to be used for a vertical hitch.

+ Shorter lengths available using reduced eye lengths.

KeyFlex™ ARAMID ROUNDSLINGS

THE STRONGEST AND LIGHTEST SLINGS IN THE WORLD

Rigging injuries decrease when lighter, less cumbersome slings are used. Light, flexible *KeyFlex*™ Roundslings help prevent injuries.

Sling Weights per Capacities

On the average, *KeyFlex*™ Roundslings are:

- 53% lighter than *Tuflex*™ Roundslings,
- 82% lighter than Wire Rope Slings,
- 89% lighter than G80 Chain Slings

The chart at the right plots the weights of 20 ft. long slings at various capacities:

Sling Type	Vert. Rating	Weight
KeyFlex™	90,000 lbs.	42 lbs.
Tuflex™	90,000 lbs.	86 lbs.
Wire Rope	88,000 lbs.	357 lbs.
Chain	72,300 lbs.	358 lbs.



KeyFlex™ Benefits:

- Lowest weight per capacity reduces risk of back and other injuries to riggers.
- Low stretch (1% at rated capacity) reduces elastic bounce for better load control – allows for use in most low headroom situations – reduces sling and load abrasion.
- Aramid load yarns allow sling use up to 350° F versus 200° F for other synthetics.
- Lightweight and compact size promotes speedier rigging, transport and storage when compared to any other type of sling.

KeyFlex™ Capacities and Measurements

Part No.	Rated Capacity (lbs.)* Vertical	Choker	Basket	Minimum Length (ft.)	Approximate Measurements Weight (lbs. / ft.)	Body Dia. Relaxed (in.)	Width at Load (in.)	Minimum Hardware Dia. (in.)
KEN10K	10,000	8,000	20,000	3	.3	1	1 3/4	7/8
KEN15K	15,000	12,000	30,000	3	.5	1 1/8	2	1
KEN20K	20,000	16,000	40,000	3	.6	1 1/4	2 1/4	1 1/4
KEN25K	25,000	20,000	50,000	3	.7	1 1/4	2 1/2	1 3/8
KEN30K	30,000	24,000	60,000	3	.8	1 3/8	2 3/4	1 1/2
KEN40K	40,000	32,000	80,000	3	1.0	1 3/4	3	1 1/2
KEN50K	50,000	40,000	100,000	5	1.3	1 7/8	3 1/2	1 3/4
KEN60K	60,000	48,000	120,000	8	1.7	2	3 3/4	2
KEN70K	70,000	56,000	140,000	8	1.9	2 1/8	4	2 1/2
KEN80K	80,000	64,000	160,000	8	2.1	2 1/4	4 1/4	2 1/2
KEN90K	90,000	72,000	180,000	8	2.4	2 1/2	4 3/4	2 1/2
KEN100K	100,000	80,000	200,000	8	2.6	2 3/4	5	2 1/2
KEN125K	125,000	100,000	250,000	8	3.0	3	5 1/4	3
KEN150K	150,000	120,000	300,000	8	3.5	3 1/4	5 1/2	3 1/2
KEN175K	175,000	140,000	350,000	8	4.0	3 1/2	6	3 1/2
KEN200K	200,000	160,000	400,000	8	4.5	3 3/4	6 1/4	3 1/2

KeyFlex™ ARAMID ROUNDSLINGS

YOUR KEY TO LIFTING HEAVY LOADS USING THE LIGHTEST, MOST FLEXIBLE SLING AVAILABLE !

KeyFlex™ Roundslings Share Most of the Benefits of Standard *Tuflex*™ Roundslings

Promote Safety

- Synthetic materials won't cut hands
- Consistent matched lengths for better multiple sling control
- No loss of strength from abrasion on double walled jacket
- *Tuff-Tag*™ provides serial numbered identification for traceability
- Conforms to shape of load to grip securely
- Load bearing yarns protected from UV degradation
- Contrasting color core yarns provide visual warning of sling damage
  (*KeyFlex*™ : Orange jacket, Gold Core Yarns)
- Endless style promotes load stability by spreading sling legs

Saves Time

- Independent core yarns choke tightly, but release easily after use

Saves Money

- Double wall cover for greater sling life
- Soft cover won't scratch load surface
- Conforms to shape of load to reduce load damage
- Seamless – no sewn edges to rupture prematurely, requiring removal from service
- *Tufhide* wear resistant nylon jacket for extra sling life standard KEN60K and larger sizes
- *Tuff-Tag* provides required OSHA information for life of the sling, not just the life of the tag
- Wear points can be shifted to extend sling life
- Endless version is the most versatile style of sling
- *KeyFlex*™ Roundslings with damaged covers may be returned to our factory for inspection and possible repair and proof test.

Inspection Criteria

Remove from service when:

- Cuts to sling cover expose gold core yarns
- Holes, tears, snags or abrasion expose gold core yarns
- End fittings are pitted or corroded, cracked, distorted or broken
- The sling shows signs of melting, charring or chemical damage
- Capacity tag is illegible or missing
- Other visible damage that causes doubt as to strength of the sling



Environmental Considerations

- CHEMICAL - Do not use in a chemical environment without first contacting the Lift-All engineering department at 717-898-6615. Please provide specific chemical, concentration, temperature and time factors.
- TEMPERATURE –*KeyFlex*™ are approved for use up to 350° F.
- WARNING: These products may contain chemicals known to the State of California to cause cancer and/or birth defects or other reproductive harm.

Ordering Information

Specify the sling code and length in feet (bearing point to bearing point).
KeyFlex™ are made to a tolerance of ±1% of the specified length (±1″ minimum tolerance) and can stretch 1% at rated capacity.
Note: Matched lengths of slings must be specified at time of order. Available in endless style only.

* **⚠ WARNING** Always protect Roundslings from being cut or damaged by corners, edges or protrusions. Refer to wear pads section, page 123 for available protective devices.

WIDE-LIFT *TUFLEX*

WIDE-LIFT *TUFLEX*

Wide Load Support and Balance

Wide-Lift *Tuflex* slings distribute the load over a wide area and offer better balance of larger loads - whether heavy or light.

Tuflex Wide-Lift Features, Advantages and Benefits

Maintains all the basic *Tuflex* features plus ...

Promotes Safety

- Wide body distributes load over wide area and offers better balance

Saves Money

- Bearing point of eyes can be shifted to prolong sling life
- Custom sizes available to fit your needs

Saves Time

- Standard eye length is 12" - making hook-up easy and fast
- Standard body width is 12" - making load balancing easier

Note:
Wide-Lift slings should only be used in basket hitch

Consult factory for special requirements.

Code	Color of Eyes	Vertical Basket Hitch Rated Capacity* (lbs.)
WL30	Purple	5,200
WL60	Green	10,600
WL90	Yellow	16,800
WL120	Tan	21,200

POLYESTER STAGE SLINGS - BLACK

These lightweight roundslings are ideal for easy and inconspicuous suspension of stage sound and lighting equipment. Black sleeve material helps sling blend into its surroundings. *Lift-All* Stage Slings maintain the basic *Tuflex* features, advantages and benefits except that the color coding of the slings is achieved by using a color coded identification *Tuff-Tag.* Double Wall sleeve material is standard.



STEELFLEX & POLYESTER STAGE SLING INFORMATION

	Part No.	Rated Capacity (lbs.)* Vertical	Choker	Basket	Mimimum Length (ft.)	Approximate Measurements Weight (lbs. / ft.)	Body Dia. Relaxed (in.)	Width at Load (in.)
Polyester Stage Sling	BSEN30	2,600	2,100	5,200	1 1/2	.2	5/8	1 1/8
	BSEN60	5,300	4,200	10,600	1 1/2	.3	7/8	1 1/2
	BSEN90	8,400	6,700	16,800	3	.4	1 1/8	1 7/8
Steelflex	GACEN60	5,300	4,200	10,600	3**	.75	7/8	1 1/2

* **⚠ WARNING** Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°.
Refer to Effect of Angle chart page 10.
** Maximum length for Steelflex is 9 ft.

STEELFLEX ROUNDSLINGS

THE STEEL SLING
WITH THE FABRIC FEEL
(U.S Patent No. 6422624)



GACEN60



400° F Temperature Rating
NO Wire Rope Backup Needed
Core Inspection Window Standard

Designed for Suspension Applications where metal slings are required.

With the trend in stage rigging to require metal slings for all overhead suspension, the problem has been how to accomplish this in the most efficient and cost effective way. *STEELFLEX* ROUNDSLINGS are the answer to that problem!

The load-bearing member of *STEELFLEX* ROUNDSLINGS is made from steel Galvanized Aircraft Cable wound in an endless configuration. This wire core is encased in a black double-wall, polyester jacket. A unique inspection window allows for easy inspection of the core for broken wires and corrosion. The result is a highly flexible, easy to use sling that complies with all of the current rigging codes.

The benefits are many:

Increased Safety
- Improved cut resistance
- Higher heat resistance
- Conforms to load to grip securely
- Window allows complete core inspection

Saves Time
- No backup rigging required
- Fewer components to inventory and carry
- Superior flexibility makes rigging easy
- Tan colored Tuff-Tag confirms steel core

Saves Money
- Gives you the slings you want to use (roundslings), without having to buy the slings you would be required to use (wire rope or chain)
- Lowers show to show freight costs

Inspection Window

TUFLEX HARDWARE / BRIDLE SLINGS

Features, Benefits and Advantages

Maintains all the basic *Tuflex* features plus ...

Promotes Safety

- Bridles provide better load control and balance_
- Hardware avoids cutting and abrasion of sling at bearing points

Saves Money

- Reduced load damage - protected between pick-up point and crane hook

Saves Time

- Lighter weight and easier to use and store than wire rope or chain slings
- Sling hooks quickly connect to loads having hoist rings or eye bolts



How to Order

Specify:
1. Number of legs -
   S (Single-1), D(Double-2), T(Triple-3), Q(Quad-4)
2. Master Link - O (Oblong)
3. Bottom Attachments - S (Sling Hook), O (Oblong)
4. Tuflex Code
5. Length of Assembly -Feet (Bearing point to bearing point)

Example:
DOSEN90 X 10' is a double leg bridle, oblong master link, with sling hooks attached to each *Tuflex* EN90. Assembly length is 10 ft.

Part No.	Color		Rated Capacity (lbs.)* Single @ 90° Vertical	Double @ 60°	Quad @ 60°	Sling Hook ** Size	E x R x T (in.)	Oblong Link (in.) Oblong Link Stock Dia. A (in.) Single	Double	Quad
EN30	Purple		2,600	4,500	9,000	2TA	1 1/8 x 4 3/32 x 1 1/16	1/2	1/2	3/4
EN60	Green		5,300	9,100	18,300	4.5TA	1 9/16 x 5 25/32 x 1 1/2	3/4	3/4	1 1/4
EN90	Yellow		8,400	14,500	29,100	7TA	2 x 7 5/16 x 1 3/4	3/4	1	1 1/2
EN120	Tan		10,600	18,300	36,700	11TA	2 7/16 x 9 1/16 x 2 1/4	3/4	1 1/4	1 1/2
EN150	Red		13,200	22,800	45,700	11TA	2 7/16 x 9 1/16 x 2 1/4	1	1 1/4	1 3/4
EN180	White		16,800	29,100	58,200	15TA	2 13/16 x 10 1/32 x 2 15/32	1 1/4	1 1/2	2 1/4
EN240	Blue		21,200	36,700	73,400	22TA	3 1/2 x 12 15/32 x 3 11/32	1 1/4	1 1/2	2 1/4
EN360	Grey		31,000	53,700	107,300	20TC	3 1/2 x 14 1/16 x 4	1 1/2	2	2 3/4
EN600	Brown		53,000	91,800	183,600	30TC	4 1/16 x 20 1/8 x 4 3/4	2	2 1/2	3 1/2
EN800	Olive		66,000	114,300	228,600	40TC	5 9/16 x 23 3/4 x 5 3/4	2 1/4	3	4 1/4
EN1000	Black		90,000	155,800	311,700		NA	2 1/2	3 1/4	4 3/4

** Hook sizes have been increased to conform to latest industry standards.

LIFT-ALL HULL SAVER BOAT SLINGS

Polyester** web slings designed especially for use with travel lifts to lower and retrieve large boats.

Features, Advantages and Benefits

Promotes Safety

- *Tuff-Tag* provides required OSHA information for the life of the sling in a marine environment.
- *Lift-All* trained professionals are available for recommended seasonal inspection.
- Two ply *Hull Savers* are our standard for improved durability and UV resistance.

Saves Time

- Optional keel pad lead weights accelerate sinking to required lift depth.
- Quick disconnects are available to improve boat yard productivity.
- Extra eye offers versatility, reducing sling changing time and sling inventory.

Saves Money

- Low-stretch polyester webbing helps to avoid scuff damage to hulls.**
- HS polymer treatment is available to greatly extend sling life by resisting abrasion and UV degradation.
- Optional chine & keel pads protect boat and increase sling life.
- Edgeguard wear resistant webbing available - helps protect sling from abrasion.

Web Plies	*Hull Saver* Code	Width (in.)	[1] Rated Capacity* (lbs.)	Optional Pull Pin Shackles			
				Shackle Code	W (in.)	L (in.)	Weight Each (lbs.)
Two Ply	HS2804	4	23,000	PPS-4	4	3.75	3.2
	HS2806	6	32,600	PPS-6	6	4.75	6.8
	HS2808	8	38,400	PPS-6HD	6	4.75	9.8
	HS2810	10	44,800	PPS-6HD	6	4.75	9.8
	HS2812	12	53,800 [2]	PPS-6HD [2]	6	4.75	9.8



Pull Pin Shackles (Optional)

Notes:
1. Capacity in lbs. is the rating of one sling in a vertical basket hitch.
2. Derate sling to 48,000 when used with 6" HD Shackle (PPS-6HD)

** Note: Nylon webbing is available, but will stretch about 50% more than polyester and should not be used near acids. Polyester should not be used near caustics.

Custom *Hull Savers*

Lift-All will manufacture boat slings to fill your particular needs for width, length and capacity. Please call for quotations.

* **⚠ WARNING** Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°.
Refer to Effect of Angle chart page 10.

LIFT-ALL HULL SAVER BOAT SLINGS



STANDARD BOAT SLING MEASUREMENTS

1. Sling Width _____ in.
2. Sling Length _____ ft.
3. Two Ply
4. Width of eyes _____ in.

SLING MATERIAL

Low stretch polyester webbing is standard because it helps to reduce chine marring. Nylon webbing is available, but will stretch about 50% more than polyester and should not be used near acids. HS Polymer Treatment extends sling life.

☐ POLYESTER - Natural or Treated (circle choice)
☐ NYLON - Natural or Treated (circle choice)

BOAT SLING ACCESSORIES

A. Extra Eyes - for shortening sling to lift smaller craft. See Measurement #5

☐ Extra Eye #1 - Position _____ ft. from point X / Y (circle choice)
☐ Extra Eye #2 - Position _____ ft. from point X / Y (circle choice)
☐ Extra Eye #3 - Position _____ ft. from point X / Y (circle choice)

B. Quick Disconnect With Flaps - Saves time needed to lower the lift for removing slings from the hooks. Available for 6" or wider only. Protective flap to cover pin is standard. See Measurement #6. Position _____ ft. from point X / Y.

C. Quick Disconnect Pin - This reusable pin is necessary for Quick Disconnect operation. Pin is galvanized for corrosion resistance. GAC wire with retaining clip holds pin in place.

D. Keel Pad - Helps protect the sling from abrasion and cutting. Sliding sleeve style allows sling to adjust to center point without scraping along keel. Pad uses the same webbing as the sling. Standard length is 48".

☐ Sliding Style - Length _____ ft.

☐ Sewn-on Style - Length _____ ft. Starting _____ ft. from X / Y

E. Keel Pad Weights - Lead weights allow for speedy submersion of sling.

F. Chine Pads - Helps to protect boat chines and rub rails and the sling from abrasion damage. Sliding pad can be positioned to accommodate any size and style of boat. May be sewn to sling per your specification. Pad uses the same webbing as the sling. Standard length is 48".

☐ Sliding - Quantity _____Length _____ ft.

☐ Sewn-on - Quantity _____Length _____ ft. Starting _____ ft. from X / Y

G. Edgeguard - Special wear resistant webbing applied to sling edges to help protect the sling from abrasion.

H. Pull Pin Shackles - Promotes sling life by protecting eyes of sling. Easier attachment of sling to lifting hook. Galvanized steel for corrosion resistance. Reusable.

☐ Quantity _____

LIFT-ALL HULL SAVER BOAT SLINGS

Safe Operating Practices

⚠ WARNING Read Definition on page 3

- Inspect slings prior to each use and do not use if damaged
- Never allow people to be aboard the boat while it is suspended by slings
- Never work under or near a boat suspended by slings
- Boats must be properly blocked and stabilized before removing slings
- *Hull Saver* Boat Slings are capacity rated for vertical basket lifts. Do not exceed rated capacities
- When lifting with extra eyes, direction of pull must always be away from center point of the original sling length

Environmental Considerations

- Nylon and polyester are seriously degraded at temperatures above 200°F.
- Prolonged exposure to ultraviolet light adversely affects nylon and polyester. Slings become bleached and stiff when exposed to sunlight or arc welding
- Many acids, alkalis and chemicals have an adverse effect on nylon and polyester. See Chemical Environment Data chart on page 14.

Inspection Criteria for *Hull Saver* Boat Slings

⚠ WARNING Read Definition on page 3

Remove from service if any of the following is visible:

- Sling is bleached or stiff due to sunlight exposure
- Capacity tag is missing or illegible
- Red core warning yarns are visible
- Sling shows signs of melting, charring or chemical damage
- End fittings are excessively pitted, corroded, distorted, cracked or broken
- Cuts on the face or edge of webbing
- Holes, tears, snags or crushed web
- Signs of excessive abrasive wear
- Broken or worn threads in the stitch patterns
- Any other visible damage which causes doubt as to its strength

Refer to photographs illustrating damaged webbing on pages 16-17.

WIRE ROPE AND SLING BASICS

Two major and opposing characteristics of wire rope slings are flexibility and resistance to abrasion. To a great extent, these traits are a direct function of the number of wires. Fewer wires means larger diameter wires, better abrasion resistance, and reduced flexibility. More wires result in decreased wire diameter, reduced abrasion resistance, increased flexibility and kink resistance.

The scale below shows the relative position of the sling constructions shown in this catalog as they pertain to abrasion resistance and flexibility.

EIP = Extra Improved Plow (Steel)
FC = Fiber Core

Wire Rope Construction





WIRE ROPE SLINGS

Features, Advantages and Benefits

Promotes Safety
- *Tuff-Tag* for capacity and serial numbered identification for traceability.

Saves Money
- Least expensive, per capacity, of all steel slings.
- Use of EIP, IWRC rope gives 15% greater capacity than IP, IWRC ropes.

Saves Time
- Countless combinations of sling terminations - hooks, chokers and thimbles are available to fit specific lift requirements.

D/d - Basket Hitch Effect



⚠ WARNING

Read Definition on page 3

Tests have shown that whenever a sling body is bent around a diameter, the strength of the sling is decreased. D/d ratio is the ratio of the diameter around which the sling is bent divided by the body diameter of the sling.

The capacities in this catalog are based on the minimum D/d ratios that appear below each of the capacity tables. For more severe bending conditions, contact *Lift-All* for revised capacities.

Environmental Considerations

- Wire core wire rope (IWRC) must not be used at temperatures above 400°F.
- Fiber core wire rope (FC) must not be used at temperatures above 180°F.
- Fiber core ropes should not be subjected to degreasing solvents.

Inspection Criteria for Wire Rope Slings

Remove slings from service when:
- End attachments, including hooks, are cracked, deformed or obviously worn;
- Hook throat opening is increased more than 15%;
- Hook is twisted out of plane by more than 10%.

⚠ CAUTION

Do not inspect a sling by passing bare hands over the wire rope.

INSPECTION CRITERIA FOR WIRE ROPE SLINGS (Cont'd)

All slings should be inspected for damage prior to each use to assure that their strength has not been compromised. The following photos illustrate some of the common damage that occurs to indicate that the sling must be taken out of service.

THE DAMAGE: **Broken Wires**

WHAT TO LOOK FOR: The individual wires that make up the strands in a wire rope can break for various reasons including fatigue and overload. Wire rope slings must be taken out of service when you find 10 or more broken wires in one rope lay or 5 or more broken wires in one strand of one rope lay.

TO PREVENT: Avoid pulling rope across edges or protrusions.

THE DAMAGE: **Wear**

WHAT TO LOOK FOR: Flat areas on the individual wires. When wires have lost one third or more of their original diameter, the sling must be taken out of service.

TO PREVENT: Do not drag sling on the ground and do not drag loads over slings. Pad high wear areas.

THE DAMAGE: **Corrosion / Heat Damage**

WHAT TO LOOK FOR: Absence of lubrication and discoloration of rope.

TO PREVENT: Hang slings for storage away from moisture. Do not use wire core slings above 400° F or fiber core slings above 180° F.

THE DAMAGE: **Kinking, Bird Caging**

WHAT TO LOOK FOR: Bent strands of wire or strands standing out from their regular position in the body of the sling.

TO PREVENT: Protect rope from sharp edges of load by pads or other means. Do not shock load slings.

THE DAMAGE: **Crushing**

WHAT TO LOOK FOR: A section of rope that is flattened, where the cross section is no longer round.

TO PREVENT: Never allow loads to be set on top of slings.

HOW TO ORDER WIRE ROPE SLINGS

Prior to sling selection and use, review and understand the "Help" section pages 3 through 12.

We have developed the following wire rope sling code system to help you in ordering these products.

114 637 I EE X 12

- **114** — Define rope diameter (One to three digits) 1 1/4" shown in example.
- **637** — Leave blank for 6x19 IWRC, EIP construction. If other rope is desired, enter 637 for a 6x37 construction or EZ for Cable Laid rope.
- **I** — Leave blank for Domestic rope. Insert an "I" for slings made using imported rope.
- **EE** — Show end terminations or other styles. See chart below or use the following:
  Eye & Eye = EE
  Bridles - 2 Leg = 2LB
  3 Leg = 3LB
  4 Leg = 4LB
  Endless = EN
  Braids - 3 Part = 3PEE
  6 Part = 6PEE
  7 Part = 7PEE
  8 Part = 8PEE
- **X** — Indicates that sling length follows.
- **12** — Sling Length (Ft) (One or two digits) Refer to drawings on following pages on how to measure.

Note: Proof testing with certification available for all slings at an additional charge.

Standard Combinations

Eye & Eye (E/E)
Eye & Thimble (E/T)
Eye & Hook (E/TH)
Eye & Crescent Thimble (E/CT)
Eye & Slip-Thru Thimble (E/ST)
Thimble & Thimble (T/T)
Thimble & Hook (T/TH)


Thimble & Crescent Thimble (T/CT)
Thimble & Slip-Thru Thimble (T/ST)
Crescent Thimble & Hook (CT/TH)
Crescent Thimble & (CT/CT) Crescent Thimble
Slip-Thru Thimble & Hook (ST/TH)
Slip-Thru Thimble & (ST/ST) Slip-Thru Thimble

Sliding Choker



Tolerances and Minimum Lengths

Refer to tables for tolerances and minimum lengths.

Wire Rope Class

Standard rope classes are shown for each type and size of sling in the charts.
Specific rope constructions are available upon request.

PERMALOC WIRE ROPE SLINGS

Lift-All Permaloc Slings are made using the flemish splice technique to form the eyes. Unlike the simple return loop method that places 100% of its strength on the swaged sleeve, *Permaloc* slings have reserve strength should the sleeve become damaged in use.



Features, Advantages and Benefits

Maintains all the basic *Lift-All* wire rope sling features plus ...

Promotes Safety

- Reserve strength - integrity of eyes not solely dependent upon steel sleeves
- IWRC resists crushing better than FC ropes

Saves Money

- When specified, thimble eyes protect wire rope from wear for increased life
- Good abrasion resistance for longer life

Permaloc With Single Part Body



Mechanically swaged, flemish eye splice wire rope slings

IWRC (Independent Wire Rope Core)

Fiber core available at reduced capacities

Wire Rope Class		Rope Dia. (in.)	EIP, IWRC [1] Rated Capacity (tons)* Vertical	Choker	V. Basket	[2] Min. Sling Length	Standard Eye Size (in.) W x L	Thimbled Eye Size (in.) W x L	Eye Hook Cap. (tons)	Crescent Thimble Eye Size (in.) W x L	Slip Thru Thimble Eye Size (in.) W x L	Sliding Choker Hook (in.)
	6 x 19 EIP, IWRC	1/4	.65	.48	1.3	1' 6"	2 x 4	7/8 x 1 5/8	1	2 x 4	2 1/8 x 4 1/8	3/8
		5/16	1.0	.74	2.0	1' 9"	2 1/2 x 5	1 1/16 x 1 7/8	1	2 x 4	2 1/2 x 4 1/8	3/8
		3/8	1.4	1.1	2.9	2' 0"	3 x 6	1 1/8 x 2 1/8	1 1/2	2 x 4	2 1/2 x 4 1/8	3/8
		7/16	1.9	1.4	3.9	2' 3"	3 1/2 x 7	1 1/4 x 2 1/4	2	2 x 5	2 3/8 x 4 3/8	1/2
		1/2	2.5	1.9	5.1	2' 6"	4 x 8	1 1/2 x 2 3/4	3	2 1/4 x 6	2 3/8 x 4 3/8	1/2 **
		9/16	3.2	2.4	6.4	2' 9"	4 1/2 x 9	1 1/2 x 2 3/4	4 1/2	2 1/4 x 7	2 3/8 x 4 3/8	5/8
		5/8	3.9	2.9	7.8	3' 0"	5 x 10	1 3/4 x 3 1/4	4 1/2	2 3/4 x 7	3 3/8 x 6 5/8	5/8 **
		3/4	5.6	4.1	11	3' 6"	6 x 12	2 x 3 3/4	7	3 1/4 x 8 1/2	3 3/8 x 6 5/8	3/4 **
		7/8	7.6	5.6	15	4' 0"	7 x 14	2 1/4 x 4 1/4	11	4 1/2 x 10	3 3/4 x 7 1/8	7/8
		1	9.8	7.2	20	4' 6"	8 x 16	2 1/2 x 4 1/2	11	4 1/2 x 11 1/2	3 3/4 x 7 1/8	1
		1 1/8	12	9.1	24	5' 0"	9 x 18	2 7/8 x 5 1/8	15	4 7/8 x 13	4 3/8 x 8 3/8	1 1/8
	6 x 37 EIP, IWRC	1 1/4	15	11	30	5' 6"	10 x 20	3 1/2 x 6 1/2	15	5 1/2 x 14 1/2	4 3/8 x 8 3/8	1 1/4
		1 3/8	18	13	36	6' 0"	11 x 22	3 1/2 x 6 1/4	22	6 x 16	5 x 9 1/2	1 3/8
		1 1/2	21	16	42	7' 0"	12 x 24	3 1/2 x 6 1/4	22	6 x 17 1/2	5 x 9 1/2	1 1/2**
		1 3/4	28	21	57	8' 0"	14 x 28	4 1/2 x 9	30	7 x 20	6 3/4 x 11 3/4	-
		2	37	28	73	9' 0"	16 x 32	6 x 12	37	7 x 23 1/2	8 x 14 1/2	-
		2 1/4	44	35	89	10' 0"	18 x 36	7 x 14	45	8 1/2 x 26	8 x 15 1/2	-
		2 1/2	54	42	109	11' 0"	20 x 40	-	-	8 1/2 x 29 1/2	-	-

Note: Larger diameter slings available. Basket ratings are based on a minimum D/d of 25. See page 60.

1. 1 Ton = 2,000 lbs.
2. Minimum sling length when using standard eyes.

Note: **Length Tolerances** - Single Part Wire Rope Slings - Standard length tolerance is plus or minus two rope diameters, or plus or minus 0.5% of the sling length, whichever is greater.

** See page 77 for reduced choker capacity when using these hook sizes.

* **⚠ WARNING** Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°. Refer to Effect of Angle chart page 10.

PERMALOC BRIDLE SLINGS

Features, Advantages and Benefits

Maintains all the basic *Lift-All* wire rope sling features plus ...

Promotes Safety

- Bridles provide better load control and balance
- Independent wire rope core resists crushing

Saves Money

- Alloy steel hooks and links assure long life
- Thimble eyes protect wire rope from wear for increased life
- Reduces load damage by using fixed points on load

Saves Time

- Easier rigging provided when hooking into fixed lifting points

Permaloc Bridle Slings (With Single Part Body)				2-Leg Bridle				3-Leg Bridle				4-Leg Bridle			
				[1] Rated Capacity (tons)*				[1] Rated Capacity (tons)*				[1] Rated Capacity (tons)*			
	Rope Dia. (in.)	[2] Min. Sling Length	Eye Hook Cap. (tons)	60°	45°	30°	Oblong Link Stock Dia.	60°	45°	30°	Oblong Link Stock Dia.	60°	45°	30°	Oblong Link Stock Dia.
6 x 19 EIP, IWRC	1/4	1' 3"	1	1.1	.91	.65	1/2	1.7	1.4	.97	1/2	2.2	1.8	1.3	1/2
	5/16	1' 6"	1	1.7	1.4	1.0	1/2	2.6	2.1	1.5	1/2	3.5	2.8	2.0	3/4
	3/8	1' 8"	1 1/2	2.5	2.0	1.4	1/2	3.7	3.0	2.2	3/4	5.0	4.1	2.9	3/4
	7/16	1' 10"	2	3.4	2.7	1.9	3/4	5.0	4.1	2.9	3/4	6.7	5.5	3.9	1
	1/2	2'	3	4.4	3.6	2.5	3/4	6.6	5.4	3.8	1	8.8	7.1	5.1	1
	9/16	2' 2"	4 1/2	5.5	4.5	3.2	3/4	8.3	6.8	4.8	1	11	9.0	6.4	1 1/4
	5/8	2' 4"	4 1/2	6.8	5.5	3.9	1	10	8.3	5.9	1 1/4	14	11	7.8	1 1/2
	3/4	2' 9"	7	9.7	7.9	5.6	1 1/4	15	12	8.4	1 1/2	19	16	11	1 3/4
	7/8	3' 3"	11	13	11	7.6	1 1/4	20	16	11	1 1/2	26	21	15	2
	1	3' 6"	11	17	14	9.8	1 1/2	26	21	15	1 3/4	34	28	20	2 1/4
	1 1/8	4'	15	21	17	12	1 1/2	31	26	18	1 3/4	42	34	24	2 3/4
6x37 EIP, IWRC	1 1/4	4' 6"	15	26	21	15	1 3/4	38	31	22	2	51	42	30	2 3/4
	1 3/8	5'	22	31	25	18	1 3/4	46	38	27	2 1/4	-	-	-	-
	1 1/2	5' 6"	22	37	30	21	2	55	45	32	2 1/4	-	-	-	-
	1 3/4	6' 6"	30	49	40	28	2 1/4	-	-	-	-	-	-	-	-
	2	8'	37	63	52	37	2 3/4	-	-	-	-	-	-	-	-

Note: **Length Tolerances** - Single Part Wire Rope Slings - Standard length tolerance is plus or minus two rope diameters, or plus or minus 0.5% of

Other fittings and latches are available upon request.

1. 1 Ton = 2,000 lbs.
2. Minimum length based on thimbled eye and eye hook.

* **⚠ WARNING** Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°. Refer to Effect of Angle chart page 10.

GROMMETS AND ENDLESS SLINGS

Features, Advantages and Benefits

Maintains all the basic *Lift-All* wire rope sling features plus ...

Promotes Safety

- Load stability and balance can be achieved by spreading sling legs in a basket or choker hitch

Saves Money

- Wear points can be shifted to extend sling life
- The most versatile style of sling - fewer slings to inventory

Saves Time

- Ideal for turning loads
- More flexible than eye slings of comparable strength

Grommets - Strand Laid, Hand Tucked

Made from one strand of EIP, 19 or 37 wire, hand laid and spliced to form a seven strand rope with no noticeable splice area. No sleeves to snag or get in the way.



Order length by circumference.

Rope Dia. (in.)	Rated Capacity (tons)* Vertical	Choker	Vertical Basket	Minimum Sling Length	Splice Length (in.)
3/8	2.1	1.5	4.2	3' 0"	2 7/16
7/16	2.8	2.0	5.7	3' 6"	2 7/8
1/2	3.7	2.6	7.3	4' 0"	3 1/4
9/16	4.6	3.2	9.3	4' 6"	3 11/16
5/8	5.7	4.0	11	5' 0"	4 1/16
3/4	8.2	5.7	16	6' 0"	4 7/8
7/8	11	7.7	22	7' 0"	5 11/16
1	14	10	29	8' 0"	6 1/2

Vertical and Basket ratings are based on a minimum D/d of 5. See page 60.

Endless - Mechanical Splice

Made from one 6 x 19 or 6 x 37 EIP, IWRC wire rope, mechanically joined with steel sleeves. Achieves higher capacities at a lower cost.



Order length by circumference.

Rope Dia. (in.)	Rated Capacity (tons)* Vertical	Choker	Vertical Basket	Minimum Sling Length	Splice Length A (in.)
1/4	1.0	.71	2.0	3' 0"	8
5/16	1.6	1.1	3.1	3' 0"	8
3/8	2.3	1.6	4.5	3' 0"	8
7/16	3.1	2.1	6.1	6' 0"	10
1/2	3.9	2.8	7.9	6' 0"	10
9/16	5.0	3.5	10	6' 0"	10
5/8	6.1	4.3	12	6' 0"	10
3/4	8.8	6.2	18	8' 0"	16
7/8	12	8.3	24	8' 0"	18
1	15	11	31	8' 0"	20

Note: 3 sleeves used on 3/4" and larger.

Vertical and Basket ratings are based on a minimum D/d of 5. See page 61.

⚠ WARNING Read Definition on page 3.

Do not lift with hook in splice area - sling damage may occur.

* **⚠ WARNING**

Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases.
Slings should not be used at angles of less than 30°.
Refer to Effect of Angle chart page 10.

E-Z FLEX CABLE LAID SLINGS

E-Z Flex slings are made from a machine laid rope that consists of seven individual, galvanized ropes.

Features, Advantages and Benefits

Maintains all the basic *Lift-All* wire rope sling features plus ...

Saves Money

- Superior flexibility - resists damage from kinking
- Galvanized coating for corrosion resistance and longer life



7 x 7 x 7



7 x 7 x 19

Standard Combinations

Eye & Eye (E/E)



Eye & Thimble (E/T)



Eye & Hook (E/TH)

Eye & Crescent Thimble(E/CT)

Eye & Slip-Thru Thimble (E/ST)

Slip-Thru Thimble & Hook (ST/TH)

Slip-Thru Thimble & Slip-Thru Thimble (ST/ST)

Thimble & Thimble (T/T)

	Rope Dia. (in.)	Rated Capacity (tons)* Vertical	Choker	Vertical Basket	** Min. Sling Length	Standard Eye Size (in.) W x L	Thimbled Eye Size (in.) W x L	Eye Hook Cap. (tons)	Crescent Thimble Eye Size (in.) W x L	Slip Thru Thimble Eye Size (in.) W x L	Sliding Choker Hook (in.)
7 x 7 x 7	1/4	.50	.34	1.0	1' 6"	2 x 4	7/8 x 1 5/8	1	2 x 4	2 1/8 x 4 1/8	3/8
	3/8	1.1	.74	2.2	2' 0"	3 x 6	1 1/8 x 2 1/8	1 1/2	2 x 4	2 1/8 x 4 1/8	3/8
	1/2	1.9	1.3	3.7	2' 6"	4 x 8	1 1/2 x 2 3/4	2	2 1/4 x 6	2 3/8 x 4 3/8	1/2
	5/8	2.8	1.9	5.5	3' 0"	5 x 10	1 3/4 x 3 1/4	3	2 3/4 x 7	3 3/8 x 6 5/8	5/8
7 x 7 x 19	3/4	4.1	2.8	8.1	3' 6"	6 x 12	2 x 3 3/4	4 1/2	3 1/4 x 8 1/2	3 3/8 x 6 5/8	3/4
	7/8	5.4	3.7	11	4' 0"	7 x 14	2 1/4 x 4 1/4	7	4 1/2 x 10	3 3/4 x 7 1/8	7/8
	1	6.9	4.7	14	4' 6"	8 x 16	2 1/2 x 4 1/2	7	4 1/2 x 11 1/2	3 3/4 x 7 1/8	1
	1 1/8	8.3	5.8	17	5' 0"	9 x 18	2 7/8 x 5 1/8	11	4 7/8 x 13	4 3/8 x 8 3/8	1 1/8
	1 1/4	9.9	7.0	20	5' 6"	10 x 20	3 1/2 x 6 1/2	11	5 1/2 x 14 1/2	4 3/8 x 8 3/8	1 1/4
	1 1/2	13	9.1	26	7' 0"	12 x 24	3 1/2 x 6 1/4	15	6 x 17 1/2	5 x 9 1/2	1 1/2

** Minimum sling length when using standard eyes.
Basket ratings are based on a minimum D/d of 10. See page 60.
Other fittings are available upon request.

* **⚠ WARNING** Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°.
Refer to Effect of Angle chart page 10.

E-Z FLEX TWO LEG BRIDLE SLINGS

Features, Advantages and Benefits

Maintains all the basic *Lift-All* wire rope sling features plus ...

Promotes Safety

- Bridles provide better load control and balance

Saves Money

- Excellent flexibility - resists damage from kinking
- Galvanized coating for corrosion resistant longer life
- Alloy steel fittings assure long life

Saves Time

- Easier rigging provided when hooking into fixed lifting points
- Sliding choker hook speeds rigging of bundled materials

⚠ WARNING Read Definition on page 3.

Do not lift with hook in splice area - sling damage may occur.

E-Z FLEX Two Leg Bridles



	Rope Dia. (in.)	Rated Capacity (tons)* 60°	45°	30°	Rated Capacity (tons)* 60°	45°	30°	** Min. Sling Length	Oblong Link Stock Dia. (in.)	Eye Hook Cap. (tons)	Sliding Choker Hook (in.)
7 x 7 x 7	1/4	.87	.71	.50	.60	.49	.34	1' 3"	1/2	1	3/8
	3/8	1.9	1.5	1.1	1.3	1.0	.74	1' 8"	1/2	1 1/2	3/8
	1/2	3.2	2.6	1.9	2.2	1.8	1.3	2' 0"	3/4	2	1/2
	5/8	4.8	3.9	2.8	3.3	2.7	1.9	2' 4"	1	3	5/8
7 x 7 x 19	3/4	7.0	5.8	4.1	4.8	3.9	2.8	2' 9"	1	4 1/2	3/4
	7/8	9.4	7.6	5.4	6.4	5.2	3.7	3' 3"	1	7	7/8
	1	12	9.7	6.9	8.2	6.7	4.7	3' 6"	1 1/4	7	1
	1 1/8	14	12	8.3	10	8.2	5.8	4' 0"	1 1/2	11	1 1/8
	1 1/4	17	14	9.9	12	9.8	7.0	4' 6"	1 1/2	11	1 1/4
	1 1/2	22	18	13	15	13	9.1	5' 6"	2	15	1 1/2

** Minimum length based on thimbled eye and eye hook.

* **⚠ WARNING** Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°.

E-Z FLEX ENDLESS SLINGS

Features, Advantages and Benefits

Maintains all the basic *Lift-All* wire rope sling features plus ...

Promotes Safety

- Load stability and balance achieved by spreading sling legs in basket and choker hitches

Saves Money

- Wear points can be shifted to extend sling life
- Smaller rope diameter per capacity increases flexibility

Saves Time

- Ideal for turning loads
- More flexible than eye slings of comparable strength

⚠ WARNING Read Definition on page 3

Do not lift with hook in splice area - sling damage may occur.



Order length by circumference.

Note: 3 sleeves used on 3/4" and larger.

E-Z FLEX Endless Slings

	Rope Dia. (in.)	Rated Capacity (tons)* Vertical	Choker	Vertical Basket	Min. Sling Length	Splice Length A (in.)
7 x 7 x 7	1/4	.83	.54	1.7	2' 3"	10
	3/8	1.8	1.2	3.6	3' 0"	10
	1/2	3.0	2.0	6.1	4' 0"	12
	5/8	4.6	3.0	9.1	5' 0"	12
7 x 7 x 19	3/4	6.7	4.3	13	6' 0"	18
	7/8	8.9	5.8	18	7' 0"	18
	1	11	7.3	23	8' 0"	20

Vertical and Basket ratings are based on a minimum D/d of 5. See page 60.

* **⚠ WARNING** Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases.
Slings should not be used at angles of less than 30°.
Refer to Effect of Angle chart page 10.

HIDDEN TUCK HAND SPLICED SLINGS

Features, Advantages and Benefits

Maintains all the basic *Lift-All* wire rope sling features plus ...

Promotes Safety

- Hidden Tuck buries wire ends to avoid snags and injuries

Saves Time

- No steel sleeves to catch under load



Fiber Core



	Rope Dia. (in.)	EIP, FC Rated Capacity (tons)* Vertical	Choker	Vertical Basket	Min. Sling Length	Standard Eye Size (in.) W x L
6 x 19 EIP, FC	1/4	.54	.42	1.1	2' 0"	3 x 6
	5/16	.83	.66	1.7	2' 3"	3 x 6
	3/8	1.2	.94	2.4	2' 6"	3 x 6
	7/16	1.6	1.3	3.2	2' 9"	3 1/2 x 7
	1/2	2.0	1.6	4.0	3' 0"	4 x 8
	9/16	2.5	2.1	5.0	3' 6"	4 1/2 x 9
	5/8	3.1	2.6	6.2	4' 0"	5 x 10
	3/4	4.3	3.7	8.6	4' 6"	6 x 12
	7/8	5.7	5.0	11	5' 6"	7 x 14
	1	7.4	6.4	15	6' 0"	8 x 16

Basket ratings are based on a minimum D/d of 15. See page 60.

* **⚠ WARNING** Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases.
Slings should not be used at angles of less than 30°.
Refer to Effect of Angle chart page 10.

MULTI - PART CABLED SLINGS

Three Part Cabled

Constructed by hand cabling one rope to form a three part body with two part eyes.

3 x 7 x 19



3 x 6 x 19

3 Part Cabled

Features, Advantages and Benefits

Maintains all the basic *Lift-All* wire rope sling features plus …

Saves Money

- Good abrasion resistance increases useful life of sling
- Resists damage from kinking

Saves Time

- Flexible, easy to handle by rigger
- Small sleeve over component rope won't get in the way

	Component Rope (in.)	Sling Body Dia. (in.)	Rated Capacity (tons)* Vertical	Choker	Vertical Basket	Min. Sling Length	Standard Eye (in.) W x L	Crescent Thimble Eye Size (in.) W x L	Slip Thru Thimble Eye Size (in.) W x L
7 x 19 GAC	3/16	3/8	1.2	.82	2.4	2' 0"	3 x 6	2 x 4	2 1/8 x 4 1/8
	1/4	1/2	1.9	1.3	3.9	2' 6"	4 x 8	2 1/4 x 4	2 3/8 x 4 3/8
	5/16	5/8	3.0	2.1	6.0	3' 0"	5 x 10	2 3/4 x 5	3 3/8 x 6 5/8
	3/8	3/4	4.3	2.9	8.6	3' 6"	6 x 12	3 1/4 x 6	3 3/8 x 6 5/8
6 x 19 EIP,IWRC	7/16	7/8	5.8	4.0	12	4' 0"	7 x 14	4 1/2 x 9	3 3/4 x 7 1/8
	1/2	1	7.6	5.2	15	4' 6"	8 x 16	4 1/2 x 9	3 3/4 x 7 1/8
	9/16	1 1/8	9.6	6.6	19	5' 0"	9 x 18	4 7/8 x 10	4 3/8 x 8 3/8
	5/8	1 1/4	12	8.0	23	5' 6"	10 x 20	5 1/2 x 11	4 3/8 x 8 3/8
	3/4	1 1/2	17	11	34	7' 0"	11 x 22	6 x 12	5 x 9 1/2

Basket ratings are based on a minimum D/d of 10 (using sling body dia.). See page 60.

Seven Part Cabled

Constructed by hand cabling one rope to form a seven part body with four part eyes.



7 x 7 x 19



7 x 6 x 19

7 Part Cabled

Features, Advantages and Benefits

Maintains all the basic *Lift-All* wire rope sling features plus ....

Saves Money

- Resists damage from kinking

Saves Time

- Superior flexibility makes sling easy to rig and use
- Small sleeve over component rope won't get in the way

	Component Rope Dia. (in.)	Sling Body Dia. (in.)	Rated Capacity (tons)* Vertical	Choker	Vertical Basket	Min. Sling Length	Standard Eye (in.) W x L	Crescent Thimble Eye Size (in.) W x L	Slip Thru Thimble Eye Size (in.) W x L
7 x 19 GAC	1/8	3/8	1.3	.91	2.6	2' 0"	3 x 6	2 x 4	2 1/8 x 4 1/8
	3/16	9/16	2.8	1.9	5.6	2' 6"	4 x 8	2 1/4 x 6	2 3/8 x 4 3/8
	1/4	3/4	4.7	3.2	9.3	3' 0"	5 x 10	2 3/4 x 7	3 3/8 x 6 5/8
	5/16	15/16	6.5	4.5	13	3' 6"	6 x 12	3 1/4 x 8 1/2	3 3/4 x 7 1/8
	3/8	1 1/8	9.6	6.6	19	4' 0"	7 1/2 x 15	4 1/2 x 10	3 3/4 x 7 1/8
6 x 19	7/16	1 5/16	14	9.3	27	4' 6"	9 x 18	4 7/8 x 13	4 3/8 x 8 3/8
	1/2	1 1/2	18	12	35	5' 0"	10 x 20	5 1/2 x 14 1/2	4 3/8 x 8 3/8

Basket ratings are based on a minimum D/d of 10 (using sling body dia.). See page 60.

* **⚠ WARNING** Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°. Refer to Effect of Angle chart page 10.

MULTI - PART BRAIDED SLINGS

Six Part Flat Braid

Constructed by braiding one rope to form a six part flat body with web seized eyes.

6 x 7 x 19


6 x 6 x 19

6 Part Flat Braid

Features, Advantages And Benefits

Maintains all the basic *Lift-All* wire rope sling features plus ...

Promotes Safety

- Wide bearing surface provides better load control and balance
- Resists rotation, improving load control

Saves Money

- Resists damage from kinking
- Reduces load damage by gripping load better

Saves Time

- Flexible - easy to rig

	Component Rope Dia. (in.)	Sling Body Dia. (in.)	Rated Capacity (tons)* Vertical	Choker	Vertical Basket	Min. Sling Length	Standard Eye (in.) W x L	Crescent Thimble Eye Size (in.) W x L	Slip Thru Thimble Eye Size (in.) W x L
7 x 19 GAC	1/8	9/16 x 3/8	.84	.74	1.7	2' 0"	3 x 6	2 x 4	2 1/8 x 4 1/8
	3/16	13/16 x 1/2	1.8	1.5	3.5	3' 0"	4 x 8	2 1/4 x 7	2 3/8 x 4 3/8
	1/4	1 1/8 x 11/16	2.9	2.6	5.9	3' 6"	5 x 10	3 1/4 x 8 1/2	3 3/8 x 6 5/8
	5/16	1 3/8 x 7/8	4.1	3.6	8.2	4' 6"	6 x 12	4 1/2 x 11 1/2	3 3/8 x 6 5/8
	3/8	1 11/16 x 1	6.0	5.3	12	5' 0"	7 x 14	4 7/8 x 13	3 3/4 x 7 1/8
6 x 19	7/16	2 x 1 3/16	8.6	7.5	17	6' 0"	8 x 16	6 x 16	3 3/4 x 7 1/8
	1/2	2 1/4 x 1 5/16	11	9.8	22	6' 6"	9 x 18	6 x 17 1/2	4 3/8 x 8 3/8
	9/16	2 1/2 x 1 1/2	14	12	28	7' 0"	10 x 20	7 x 20	4 3/8 x 8 3/8
	5/8	2 13/16 x 1 11/16	17	15	35	8' 0"	11 x 22	7 x 23 1/2	5 x 9 1/2
	3/4	3 3/8 x 2	25	22	49	9' 0"	12 x 24	8 1/2 x 26	6 3/4 x 11 3/4

Basket ratings are based on a minimum D/d of 25 (using component rope). See page 60.

Eight Part Round Braid

Constructed by braiding one rope to form an eight part round body with four part web seized eyes.

8 x 7 x 19

8 x 6 x 19

8 Part Round Braid

Features, Advantages And Benefits

Maintains all the basic *Lift-All* wire rope sling features plus ...

Promotes Safety

- Resists rotation, for improved load control

Saves Money

- The most kink resistant sling available
- Greater flexibility for reduced load damage

Saves Time

- The most flexible sling available - easy to rig

	Component Rope Dia. (in.)	Sling Body Dia. (in.)	Rated Capacity (tons)* Vertical	Choker	Vertical Basket	Min. Sling Length	Standard Eye (in.) W x L	Crescent Thimble Eye Size (in.) W x L	Slip Thru Thimble Eye Size (in.) W x L
7 x 19 GAC	1/8	9/16	1.1	1.0	2.2	2' 0"	3 x 6	2 x 4	2 1/8 x 4 1/8
	3/16	13/16	2.4	2.1	4.7	3' 0"	4 x 8	2 1/4 x 6	2 3/8 x 4 3/8
	1/4	1 1/8	3.9	3.4	7.8	3' 6"	5 x 10	3 1/4 x 8	3 3/8 x 6 5/8
	5/16	1 3/8	5.5	4.8	11	4' 6"	6 x 12	4 1/2 x 10	3 3/4x 7 1/8
	3/8	1 11/16	8.1	7.1	16	5' 0"	7 x 14	4 5/8 x 12	3 3/4 x 7 1/8
6 x 19 EIP,IWRC	7/16	2	11	10	23	6' 0"	8 x 16	5 1/2 x 14	4 3/8 x 8 3/8
	1/2	2 1/4	15	13	30	6' 6"	9 x 18	6 x 16	5 x 9 1/2
	9/16	2 1/2	19	16	38	7' 0"	10 x 20	6 1/2 x 18	5 x 9 1/2
	5/8	2 13/16	23	20	46	8' 0"	11 x 22	7 x 20	6 3/4 x 11 3/4
	3/4	3 3/8	33	29	66	9' 0"	12 x 24	8 x 24	8 x 14 1/2

Basket ratings are based on a minimum D/d of 25 (using component rope). See page 60.

* **⚠ WARNING** Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°. Refer to Effect of Angle chart page 10.

SWAGED THREADED STUDS

- Choice of studs made of specially selected carbon steel or stainless steel
- Custom OEM engineering available



Straight Threaded Studs

Part No.	Rope Dia (in.)	Nominal Breaking Strength (tons)*	Dimensions (in.)				N.C. Thread #	N.F. Thread #
			A After Swage	B Approx.	C	D		
STS-8	1/4	3.4	7/16	4 1/16	1 1/2	1/2	13	20
STS-10	5/16	5.3	9/16	5 1/4	1 7/8	5/8	11	18
STS-12	3/8	7.6	5/8	6 1/4	2 1/4	3/4	10	16
STS-14	7/16	10.2	3/4	7 5/16	2 5/8	7/8	9	14
STS-16	1/2	13.3	7/8	8 1/4	3	1	8	14
STS-18	9/16	16.8	1	9 1/4	3 3/8	1 1/8	7	12
STS-20	5/8	20.6	1 1/8	10 1/8	3 3/4	1 1/4	7	12
STS-24	3/4	29.4	1 1/4	12 13/16	4 1/2	1 1/2	6	12
STS-28	7/8	39.5	1 1/2	14 9/16	5 1/4	1 3/4	5	12
STS-32	1	51.7	1 3/4	16 1/4	6	2	4 1/2	12
STS-36	1 1/8	65.0	2	18 1/4	6 3/4	2 1/4	4 1/2	12
STS-40	1 1/4	79.9	2 1/4	20 1/4	7 1/2	2 1/2	4	12



Turned Threaded Studs

Part No.	Rope Dia (in.)	Nominal Breaking Strength (tons)*	Dimensions (in.)				N.C. Thread #	N.F. Thread #
			A After Swage	B Approx.	C	D		
TTS-10	5/16	5.3	5/8	5 23/32	1 3/4	5/8	11	18
TTS-12	3/8	7.6	3/4	6 3/4	2	3/4	10	16
TTS-14	7/16	10.2	7/8	7 21/32	2 1/4	7/8	9	14
TTS-16	1/2	13.3	1	8 9/16	2 1/2	1	8	14
TTS-18	9/16	16.8	1 1/8	9 5/8	2 3/4	1 1/8	7	12
TTS-20	5/8	20.6	1 1/4	10 21/32	3 1/8	1 1/4	7	12
TTS-24	3/4	29.4	1 1/2	12 11/16	3 3/4	1 1/2	6	12
TTS-28	7/8	39.5	1 3/4	14 5/8	4 3/8	1 3/4	5	12
TTS-32	1	51.7	2	16 21/32	5	2	4 1/2	12
TTS-36	1 1/8	65.0	2 1/4	18 5/8	5 5/8	2 1/4	4 1/2	12
TTS-40	1 1/4	79.9	2 1/2	20 21/32	6 1/4	2 1/2	4	12
TTS-44	1 3/8	96.0	2 3/4	22 17/32	6 7/8	2 3/4	4	12
TTS-48	1 1/2	114	3	24 1/2	7 1/2	3	4	12

* Nominal Breaking Strength based on 6 x 19 or 6 x 37 IWRC, EIP wire rope, with assembly used as a straight tension member.

SWAGED SOCKET ASSEMBLIES

Features, Advantages and Benefits

Promotes Safety

- Achieves 100% of nominal rope breaking strength
- All assemblies are proof tested before shipment to customer

Saves Money

- Custom engineered assemblies are available for specific rigging needs

Rope Diameter (in.)	Minimum Pendant Length	Vertical Capacity (tons) *
1/4	11"	.68
5/16	1' 3"	1.1
3/8	1' 3"	1.5
7/16	1' 8"	2.0
1/2	1' 8"	2.7
9/16	2' 0"	3.4
5/8	2' 0"	4.1
3/4	2' 5"	5.9
7/8	2' 10"	8.0
1	3' 2"	10
1 1/8	3' 7"	13
1 1/4	4' 0"	16

* Values given apply to 6 x 19 or 6 x 37 IWRC, EIP rope when pendants are used for slings. When used as Boom Suspension System or other applications, contact *Lift-All* for ratings.

Open Swaged Sockets



Open and Closed Swaged Sockets



Closed Swaged Sockets



Swage Socket Dimensions (Forged Steel)

Rope Dia (.in.)	Open Socket R (in.)	O (in.)	D (in.)	Weight (lbs.)	Closed Socket W (in.)	K (in.)	Weight (lbs.)
1/4	1 5/32	11/16	11/16	.52	3/4	1/2	.38
5/16	1 11/32	13/16	13/16	1.12	7/8	11/16	.77
3/8	1 11/32	13/16	13/16	1.25	7/8	11/16	.72
7/16	1 1/2	1	1	2.08	1 1/16	7/8	1.42
1/2	1 1/2	1	1	2.08	1 1/16	7/8	1.35
9/16	1 5/8	1 1/4	1 3/16	4.48	1 1/4	1 1/8	2.92
5/8	1 5/8	1 1/4	1 3/16	4.75	1 1/4	1 1/8	2.85
3/4	2	1 1/2	1 3/8	7.97	1 7/16	1 5/16	4.90
7/8	2 3/8	1 3/4	1 5/8	11.30	1 11/16	1 1/2	6.63
1	2 3/4	2	2	17.80	2 1/16	1 3/4	10.30
1 1/8	3 1/8	2 1/4	2 1/4	27.50	2 5/16	2	14.50
1 1/4	3 1/2	2 1/2	2 1/2	35.75	2 9/16	2 1/4	20.75

WINCH LINES, HOIST LINES AND BUTTONS

Winch and Hoist Line Cables

Lift-All winch and hoist lines are made using 6 x 19 Wire Core ropes for better resistance to abrasion and crushing. Available with carbon hooks for large throat openings or alloy hooks for longer life.

Features, Advantages and Benefits

Promotes Safety

- *Permaloc* flemish eye splice for high strength efficiency
- Quality factory assembly avoids faulty termination

Saves Money

- Economical standard assemblies
- Heavy duty thimble in eye extends useful life

Saves Time

- No assembly time - ready to install
- Stainless steel latch keeps hook in proper place

Winch and Hoist Line Cables

6 x 19 Class-Bright (Uncoated)

Diameter (in.)	Breaking Strength IWRC
3/8	14,000 lbs.
7/16	19,000 lbs.
1/2	25,000 lbs.
9/16	32,000 lbs.
5/8	39,000 lbs.

Swaged Steel Buttons

Swaged steel buttons are designed for use as end stops on drum winding equipment such as hoists and winches.



After Swage Dimensions

Rope Diameter (approx. in.)	A	B
1/4	5/8	1 1/8
5/16	3/4	1 1/2
3/8	7/8	1 3/4
7/16	1	2
1/2	1 1/8	2 3/8
9/16	1 1/4	2 5/8
5/8	1 3/8	2 7/8
3/4	1 1/2	3 1/2
7/8	1 3/4	4 1/8
1	2	4 3/4
1 1/8	2 1/4	5 1/4
1 1/4	2 1/2	5 7/8
1 3/8	2 3/4	6 1/2
1 1/2	3	7 1/8

Non-Standard Buttons available.

Running lengths of cable with thimbled eye ends available

WIRE ROPE

Wire Rope

These high quality wire ropes are available in cut lengths or by the reel.

6 x 19 and 6 x 37 Class Wire Rope



	Wire Core
	Extra Improved Plow Steel (EIP) Higher Capacities
6 x 19 Class Six Strand Ropes Having 9 to 26 Wires Per Strand Better Abrasion Resistance	 6 x 19
6 x 37 Class Six Strand Ropes Having 27 to 49 Wires Per Strand More Flexible	 6 x 37

Rope Diameter (in.)	Approx. Weight per Foot (lbs.)	Nominal Breaking Strength (tons)
1/4	.12	3.40
5/16	.18	5.27
3/8	.26	7.55
7/16	.35	10.2
1/2	.46	13.3
9/16	.59	16.8
5/8	.72	20.6
3/4	1.04	29.4
7/8	1.42	39.8
1	1.85	51.7
1 1/8	2.34	65.0
1 1/4	2.89	79.9
1 3/8	3.50	96.0
1 1/2	4.16	114
1 5/8	4.88	132
1 3/4	5.67	153
1 7/8	6.50	174
2	7.39	198

Note: Specialty ropes are available upon request.

Rotation Resistant Wire Rope

	Rope Dia. (in.)	Approx. Weight per Foot (lbs.)	Nominal Breaking Strength (tons)
 19 x 7	3/8	.25	6.15
	7/16	.35	8.33
	1/2	.45	10.8
	9/16	.58	13.6
	5/8	.71	16.8
	3/4	1.02	24.0
	7/8	1.39	32.5
	1	1.82	42.2
	1 1/8	2.3	53.1

The Nominal Breaking Strength of a wire rope should be considered the straight line pull with both rope ends fixed to prevent rotation, which will ACTUALLY BREAK a new, UNUSED, rope. The Nominal Breaking Strength of a rope should NEVER BE USED AS ITS WORKING LOAD.

To determine the working load of a wire rope, the MINIMUM or NOMINAL Breaking Strength MUST BE REDUCED by a DESIGN FACTOR. The design Factor will vary depending upon the type of machine and installation, and the work permitted. YOU must determine the applicable Design Factor for your use.

For example, a Design Factor of "5" means that the Minimum or Nominal Breaking Strength of the wire rope must be DIVIDED BY FIVE to determine the maximum load that can be applied to the rope system.

Design Factors have been established by OSHA, by ANSI, by ASME and similar government and industrial organizations.

No wire rope should ever be installed or used without full knowledge and consideration of the Design Factor for the application.

The above is based on the 'Wire Rope Safety Bulletin' published by the "WIRE ROPE TECHNICAL BOARD".

SLING ATTACHMENTS, HOOKS, ETC.

Alloy Steel Eye Hooks

- Light weight hooks for heavy duty lifting



EIP IWRC Rope Dia. (in.)	Rated Capacity* (tons)	Dimension (in.)				Weight Each (lbs.)
		E	R	T	T w/ Latch	
1/4-5/16	1	3/4	3 1/8	1	7/8	.63
3/8	1 1/2	7/8	3 21/32	1 1/16	15/16	.85
7/16	2	1 1/8	4 3/32	1 1/8	1	1.4
1/2	3	1 1/4	4 11/16	1 1/4	1 1/8	1.9
9/16-5/8	4 1/2	1 9/16	5 25/32	1 1/2	1 3/8	3.7
3/4	7	2	7 5/16	1 31/32	1 11/16	7.3
7/8-1	11	2 7/8	9 1/16	2 1/4	2 1/16	15
1 1/8-1 1/4	15	2 13/16	10 1/32	2 15/16	2 1/4	22
1 3/8-1 1/2	22	3 1/2	12 15/32	3 11/32	3	38
1 3/4	30	3 1/2	14 1/16	4	3 5/8	60
2	37	4 1/2	18 3/16	4 1/4	3 3/4	105
2 1/4	45	4 15/16	20 1/8	4 3/4	4 1/4	148
2 1/2	60	5 11/16	23 23/32	5 3/4	5 1/8	228

Carbon hooks available.
Stainless steel latch available.

Swivel Eye Hooks

- Hook swivels beneath eye
- Built-in distortion detectors
- Drop forged alloy steel



EIP IWRC Rope Dia. (in.)	Rated Capacity* (tons)	Dimensions (in.)				Weight Each (lbs.)
		E	R	B	T	
1/4-5/16	1	1 1/4	4 5/8	1 3/32	1	1.3
3/8	1 1/2	1 1/2	5 7/16	1 3/8	1 3/32	1.8
7/16	2	1 3/4	6 1/4	1 21/32	1 1/8	2.8
1/2	3	1 3/4	6 1/2	1 21/32	1 1/4	3.3
9/16-5/8	5	2	7 17/32	1 25/32	1 17/32	7.2
3/4	7	2 3/4	9 19/32	2 3/8	1 31/32	13.6

Lodelok Eye Hooks

- Heavy duty latch with lock prevents accidental opening
- Drop forged alloy steel



Hook Size	EIP IWRC Rope Dia. (in.)	Rated Capacity* (tons)	Dimensions (in.)			Weight Each (lbs.)
			B	C	F	
9/32	1/4-3/8	1.7	1 3/32	5 3/8	1 5/8	2.5
3/8	7/16-9/16	3.5	1 3/8	6 21/32	2 1/4	4.6
1/2	5/8-3/4	6.0	1 9/16	8 25/32	2 29/32	10
5/8	7/8	9.0	2	10 3/8	3 3/16	16

Swivel Lodelok Hooks With Bushings

- Hook swivels beneath the eye
- Heavy duty latch with lock prevents accidental opening
- Drop forged alloy steel



EIP IWRC Rope Dia. (in.)	Rated Capacity* (tons)	Dimensions (in.)				Weight Each (lbs.)
		E	R	B	T	
1/4-3/8	1.7	1 1/2	7 5/32	1 5/16	1 5/8	3.5
7/16-5/8	3.5	1 3/4	8 23/32	1 5/8	2 1/4	4.8
1/2-7/8	6.0	2	11 5/32	1 3/4	2 29/32	10.6
1	9.0	2 3/4	13 13/32	2 3/8	3 3/16	17.0

Sorting Hooks

- Drop forged alloy steel, for maximum strength and toughness.



Dimensions (in.)				Weight (lbs.)
E	R	C	D	
1 7/16	7 11/16	5/8	2 5/8	6.8

Working load limit at tip - 2 ton.
Working load limit at bottom - 7 1/2 ton.

* **⚠ WARNING** Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°.
Refer to Effect of Angle chart page 10.

SLING ATTACHMENTS, HOOKS, ETC.

Alloy Oblong Master Links

- Drop forged through 1", formed and welded in larger sizes.



Rated Capacity* (tons)	Dimensions (in.)			Weight Each (lbs.)
	D	W	L	
3.05	1/2	2 1/2	5	.9
6.6	3/4	3	6	2.5
11.2	1	4	8	5.8
16.2	1 1/4	4 3/8	8 3/4	9.2
24.5	1 1/2	5 1/4	10 1/2	16
36.7	1 3/4	6	12	25
44.4	2	7	14	37
62.6	2 1/4	8	16	54
93.9	2 3/4	9	16	85

Sliding Choker Hooks

- Speeds rigging time of bundled loads.
- Reduces sling wear when used with thimbles.
  When using on multi-part slings, contact *Lift-All* for additional information.



Hook No. (Rope Dia.)	Rated Capacity* (tons)	Dimension (in.)	Weight (lbs.)
		H	
3/8	1.3	4 1/4	1.3
1/2	1.7	4 13/16	1.8
5/8	2.5	5 15/16	4
3/4	4.0	6 7/16	4.5
7/8 - 1	7.5	8 1/8	10
1 1/8 - 1 1/4	11.5	11 5/8	26
1 3/8 - 1 1/2	15	14 1/2	50

Screw Pin Anchor Shackles

- Carbon Shackle
- Alloy pin
- Heat treated and tempered



Note: This chart shows standard capacities and dimensions, but may vary depending on source of supply. Specify required capacity if critical.

Shackle Size Dim. D (in.)	Rated Capacity* (tons)		Dimensions (in.)				Weight per 100 Pieces (lbs.)
	CM	Others	P	W	L	B	
3/16	1/2	1/3	1/4	3/8	7/8	5/8	6
1/4	3/4	1/2	5/16	15/32	1 1/8	13/16	12
5/16	1	3/4	3/8	17/32	1 1/4	7/8	20
3/8	1 1/2	1	7/16	21/32	1 7/16	1 1/16	30
7/16	2	1 1/2	1/2	23/32	1 11/16	1 1/4	50
1/2	3	2	5/8	13/16	1 15/16	1 7/16	75
5/8	4 1/2	3 1/4	3/4	1 1/16	2 13/32	1 3/4	130
3/4	6 1/2	4 3/4	7/8	1 1/4	2 27/32	2	225
7/8	8 1/2	6 1/2	1	1 7/16	3 5/16	2 5/16	350
1	10	8 1/2	1 1/8	1 11/16	3 3/4	2 9/16	500
1 1/8	12	9 1/2	1 1/4	1 13/16	4 1/4	2 15/16	700
1 1/4	14	12	1 3/8	2 1/32	4 11/16	3 1/4	950
1 3/8	17	13 1/2	1 1/2	2 1/4	5 1/4	3 1/2	1250
1 1/2	20	17	1 5/8	2 3/8	5 3/4	3 3/4	1720
1 5/8	24	24	1 3/4	2 5/8	6 1/4	4 3/8	2350
1 3/4	30	25	2	2 7/8	7	5	2770
2	35	35	2 1/4	3 1/4	7 3/4	5 3/4	3900

* **⚠ WARNING** Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°.
Refer to Effect of Angle chart page 10.

CABLE & COMPONENTS

Galvanized and Stainless Steel Cable

7 x 7	Cable Diameter (in.)	Wt./Reel (lbs.)	Standard Length (ft./Reel)	Nominal Break Strength (lbs.)	
				Galvanized Cable (GAC)	Stainless Steel Cable (SSAC) Type 304
	1/16	5	500	480	480
	3/32	9	500	920	920
	1/8	15	500	1,700	1,760

7 x 19					
	3/32	9	500	1,000	920
	1/8	15	500	2,000	1,760
	5/32	12	250	2,800	2,400
	3/16	17	250	4,200	3,700
	1/4	25	250	7,000	6,400
	5/16	38	200	9,800	9,000
	3/8	52	200	14,400	12,000

Galvanized Cable Coated with Clear Vinyl

Galvanized Cable Construction	Cable Diameter (in.)	Coated To: (in.)	Wt./Reel (lbs.)	Standard Length (ft.)/Reel	Nominal Break Strength (lbs.)
7 x 7	1/16	3/32	7	500	480
	3/32	3/16	7	250	920
	1/8	3/16	10	250	1,700
7 x 19	1/8	3/16	10	250	2,000
	3/16	1/4	19	200	4,200
	1/4	5/16	28	200	7,000

Heavy Duty Wire Rope Thimbles



Rope Dia. (in.)	Dimensions (in.)			Weight Per 100 Pieces (lbs.)
	A	B	C	
1/4	1 5/8	7/8	15/16	8
5/16	1 7/8	1 1/16	17/32	14
3/8	2 1/8	1 1/8	21/32	22
7/16	2 5/16	1 1/4	3/4	36
1/2	2 3/4	1 1/2	15/16	51
5/8	3 1/4	1 3/4	1 1/32	75
3/4	3 3/4	2	1 1/4	147
7/8	4 1/4	2 1/4	1 7/16	185
1	4 1/2	2 1/2	1 11/16	300
1 1/8 - 1 1/4	5 1/8	2 7/8	1 13/16	400
1 1/4 - 1 3/8	6 1/2	3 1/2	2 3/16	817
1 3/8 - 1 1/2	6 1/4	3 1/2	2 9/16	1,175
1 5/8	8	4	2 23/32	1,700
1 3/4	9	4 1/2	2 27/32	1.775
1 7/8 - 2	12	6	3 3/32	2,500
2 1/4	14	7	3 5/8	3,950

Standard Wire Rope Thimbles



Rope Dia. (in.)	Dimensions (in.)			Quantity Per Bag	Weight Per Bag (lbs.)
	A	B	C		
1/8	1 5/16	11/16	1/4	100	4
3/16	1 5/16	11/16	5/16	100	4
1/4	1 5/16	11/16	3/8	100	4
5/16	1 1/2	13/16	7/16	80	3
3/8	1 5/8	15/16	1/2	80	4

CABLE & COMPONENTS

Wire Rope Clips

The following instructions, supplied by the Wire Rope Technical Board, will result in an approximate 80% efficiency rating when the clips are applied as instructed, on GAC, SSAC, RRL or RLL, 6 x 19 class or 6 x 37 class, fiber core or IWRC, non-Seale type construction wire rope. If applied to vinyl coated ropes, vinyl must first be stripped from clip connection area.



Right Way - For Maximum Rope Strength



How to Apply Clips

1. Turn back the specified amount of rope from the thimble. Apply the first clip one clip width from the dead end of the wire rope (U-bolt over dead end - live end rests in clip saddle). Tighten nuts evenly to recommended torque.
2. Apply the next clip as near to the loop as possible. Turn on nuts firmly but do not tighten.
3. Space additional clips, if required, equally between the first two. Tighten on nuts - take up rope slack - tighten all nuts evenly on all clips to recommended torque.
4. NOTICE! Apply the initial load and retighten nuts to the recommended torque. Rope will stretch and be reduced in diameter when loads are applied. Inspect periodically and retighten to recommended torque.

⚠ WARNING

Failure to make a termination in accordance with aforementioned instructions, or failure to periodically check and retighten to the recommended torque, may result in death or serious injury.

Drop Forged Wire Rope Clips

Rope Dia. (in.)	Minimum Number of Clips	Rope Turn-back (in.)	Torque (ft./lbs.)	Weight Per 100 Pieces (lbs.)
1/8	2	3 1/4	4 1/2	6
3/16	2	3 3/4	7 1/2	10
1/4	2	4 3/4	15	18
5/16	2	5 1/4	30	30
3/8	2	6 1/2	45	47
7/16	2	7	65	76
1/2	3	11 1/2	65	80
9/16	3	12	95	104
5/8	3	12	95	106
3/4	4	18	130	150
7/8	4	19	225	212
1	5	26	225	250
1 1/8	6	34	225	280
1 1/4	7	44	360	415
1 3/8	7	44	360	460
1 1/2	8	54	360	530

Malleable Wire Rope Clips

Rope Dia. (in.)	Minimum Number of Clips	Rope Turn-back (in.)	Torque (ft./ lbs.)	Quantity Per Bag	Weight Per Bag (lbs.)
1/8	3	5	3	200	10
3/16	3	6	5	150	12
1/4	3	7	15	100	12
5/16	3	8	15	100	15
3/8	3	10	30	50	11

Note: Malleable clips are not to be used for overhead lifting. Use in light duty, non-critical applications only.

SLING WEIGHTS (Approx.)

To estimate sling weights, multiply length x Per Foot Weight and add Zero Base Weight plus any additional fittings' weights.

Rope Dia. (in.)	*Zero Base Weight (lbs.)	Per Foot Weight (lbs.)	Thimbled Eye Wt. Ea. (lbs.)	Alloy Eye Hook Wt. Ea. (lbs.)	Crescent Thimble Wt. Ea. (lbs.)	Slip Thru Thimble Wt. Ea. (lbs.)	Sliding Choker Hook Wt. Ea. (lbs.)
1/4	.31	.12	.08	.63	.50	1.3	1.3
5/16	.47	.18	.14	.63	.50	1.3	1.3
3/8	.73	.26	.22	.85	.50	1.3	1.3
7/16	1.3	.35	.36	1.4	.50	1.5	1.9
1/2	1.7	.46	.51	1.9	.75	1.5	1.9
9/16	3.1	.59	.51	3.7	.75	1.5	1.9
5/8	3.5	.72	.75	3.7	1.2	3.4	4.0
3/4	5.7	1.0	1.5	7.3	2.0	3.4	4.5
7/8	8.9	1.4	1.9	15	3.3	5.6	10
1	13	1.9	3.0	15	3.8	5.6	10
1 1/8	18	2.3	4.0	22	5.0	8.6	26
1 1/4	25	2.9	8.2	22	6.8	8.6	26
1 3/8	32	3.5	12	38	8.0	10	50
1 1/2	41	4.2	12	38	8.0	10	50
1 3/4	65	5.7	18	60	17	18	
2	99	7.4	25	105	22	53	
2 1/4	169	9.4	40	148	39	70	
2 1/2	278	12	-	-	39	126	

* Zero Base Weight accounts for the additional rope and sleeves required to form two standard eyes.

SLING WEIGHTS (Approx.)

To estimate sling weights, multiply length x Per Foot Weight and add Zero Base Weight.

	2-Leg Bridle		3-Leg Bridle		4-Leg Bridle	
						
Rope Dia. (in.)	*Zero Base Weight (lbs.)	Per Foot Weight (2 Legs)	*Zero Base Weight (lbs.)	Per Foot Weight (lbs.) (3 Legs)	*Zero Base Weight (lbs.)	Per Foot Weight (lbs.) (4 Legs)
1/4	2.8	.23	2.8	.35	4.7	.46
5/16	3.2	.36	5.7	.54	6.9	.72
3/8	5.8	.52	7.5	.78	12	1.0
7/16	8.1	.70	14	1.0	17	1.4
1/2	10	.92	17	1.4	26	1.8
9/16	20	1.2	27	1.8	39	2.4
5/8	21	1.4	34	2.2	42	2.9
3/4	38	2.1	60	3.1	85	4.2
7/8	58	2.8	89	4.3	121	5.7
1	76	3.7	114	5.6	171	7.4
1 1/8	108	4.7	163	7.0	250	9.4
1 1/4	131	5.8	210	8.7	296	12
1 3/8	197	7.0	320	11		
1 1/2	230	8.3	350	13		
1 3/4	380	11				
2	550	15				

* Zero Base Weight includes Oblong Link, Thimbled Eyes and Sling Hooks

Acknowledgement

Lift-All wire rope slings and rated capacities comply with all OSHA, ASME B30.9, and Wire Rope Technical Board publications. Portions of this section of the catalog were taken from the Wire Rope Sling User's Manual with the permission of the Wire Rope Technical Board and the American Iron and Steel Institute.

LiftAlloy CHAIN SLING BASICS

***Lift-All* chain slings meet or exceed all OSHA, ASME B30.9 and NACM standards and regulations.**

LiftAlloy chain slings, available in Grades 80 and 100, are recommended for rugged industrial applications in harsh environments where flexibility, abrasion resistance and long life are required. OSHA required annual inspections can be performed by *Lift-All* trained personnel.

Features, Advantages and Benefits

Promotes Safety

- Permanent steel capacity tag is serialized for identification
- Welded slings offer the security of tamper proof assemblies

Saves Money

- Alloy Steel construction assures long life
- Can be repaired, proof tested and recertified by *Lift-All*

Saves Time

- Easy to inspect for damage
- Stores easily

Use of Chain Under Heat Conditions

When the chain itself is heated to temperatures shown below, the Working Load Limit (Rated Capacity) should be reduced as indicated.

Temperature of Chain (°F)	Reduction of Working Load Limit While at Temperature		Permanent Reduction of Working Load Limit After Exposure to Temperature	
	Grade 80	Grade 100	Grade 80	Grade 100
Below -40	Do Not Use	Do Not Use	None	None
Below -20	None	Do Not Use	None	None
400	10%	15%	None	None
500	15%	25%	None	5%
600	20%	30%	5%	15%
700	30%	40%	10%	20%
800	40%	50%	15%	25%
900	50%	60%	20%	30%
1000	60%	70%	25%	35%
Over 1000	REMOVE FROM SERVICE			

Consult *Lift-All* about galvanized chain

Consult *Lift-All* about chain to be used in pickling operations

HOW TO ORDER CHAIN SLINGS

14 D O S W 10 X 12

- **14** — Define chain diameter (One to three digits) 1/4" shown in example.
- **D** — Number of chain legs or other style. Single = S, Double = D, Triple = T, Quad = Q, Choker = C, Endless (w/o oblong) = E
- **O** — Master Link or Specials. Oblong = O, Basket = B, Adjustable = A, Endless: with oblong = E, w/o oblong = N
- **S** — Bottom Attachments. Sling Hook = S, Grab Hook = G, Foundry Hook = F, Latch Hook = L, Adjustables: Loop Style A = A, Loop Style B = B, Style A = SA, Style B = SB, Endless = Leave Blank
- **W** — Welded couplers = W, Mechanical couplers = M
- **10** — Grade 80 Chain = 8, Grade 100 Chain = 10
- **X** — Indicates that sling length follows.
- **12** — Sling Reach (Ft) (One or two digits) Refer to drawings on following pages on how to measure.

LiftAlloy CHAIN SLING BASICS

LiftAlloy Grade 80

- Proven reliability
- Available in welded or mechanically assembled slings
- Widest range of sizes and styles
- Greater temperature tolerance

LiftAlloy Grade 100

- Higher capacity per chain size can be used as an increased safety factor
- Higher capacity may allow use of smaller diameter chain for your lifts, reducing sling weight and cost
- Extreme abrasion resistance - more durable
- Shot blasted and oil finished chain for distinct, uniform appearance and corrosion resistance
- Power coated silver gray attachments for distinctive appearance, identification and corrosion resistance
- Meets or exceeds all OSHA, ASTM and NACM standards

Chain Wear Allowance

Determine wear by measuring cross section at link ends. If worn to less than the minimum thickness allowable, chain should be removed from service.

Chain Size (in.)	Minimum Allowable Thickness - A (in.)
7/8 (.218)	.189
9/32 (.281)	.239
3/8 (.375)	.342
1/2 (.500)	.443
5/8 (.625)	.546
3/4 (.750)	.687
7/8 (.875)	.750
1 (1.00)	.887
1 1/4 (1.250)	1.091



Minimum thickness based on OSHA recommendations.

Rated Capacity For *LiftAlloy* Chain Slings

Size of Chain		90°	60°	45°	30°	60°	45°	30°	Nominal Dimensions (in.)		Approx. No. of Links per ft.	Approx. Weight per 100 ft. (lbs.)
(in.)	(mm)	Single Chain @ 90° (lbs.)	Double Chain Slings * (lbs.)			Triple & Quad Chain Slings * (lbs.) **			Inside Length	Inside Width		
Grade 80												
7/32	5.5	2,100	3,600	3,000	2,100	5,450	4,450	3,150	.671	.296	17.9	45
9/32	7.0	3,500	6,100	4,900	3,500	9,100	7,400	5,200	.868	.395	13.8	74
3/8	10.0	7,100	12,300	10,000	7,100	18,400	15,100	10,600	1.222	.572	9.8	146
1/2	13.0	12,000	20,800	17,000	12,000	31,200	25,500	18,000	1.404	.720	8.5	258
5/8	16.0	18,100	31,300	25,600	18,100	47,000	38,400	27,100	1.733	.854	6.9	387
3/4	20.0	28,300	49,000	40,000	28,300	73,500	60,000	42,400	2.160	1.052	5.5	622
7/8	22.0	34,200	59,200	48,400	34,200	88,900	72,500	51,300	2.250	1.137	5.3	776
1	26.0	47,700	82,600	67,400	47,700	123,900	101,200	71,500	2.664	1.348	4.5	995
1 1/4	32.0	72,300	125,200	102,200	72,300	187,800	153,400	108,400	3.250	1.656	3.7	1,571
Grade 100												
7/32	5.5	2,700	4,700	3,800	2,700	7,000	5,700	4,000	.670	.284	17.9	45
9/32	7.0	4,300	7,400	6,100	4,300	11,200	9,100	6,400	.868	.380	13.8	73
3/8	10.0	8,800	15,200	12,400	8,800	22,900	18,700	13,200	1.181	.512	9.8	148
1/2	13.0	15,000	26,000	21,200	15,000	39,000	31,800	22,500	1.535	.688	8.5	255
5/8	16.0	22,600	39,100	32,000	22,600	58,700	47,900	33,900	1.890	.819	6.9	383
3/4	20.0	35,300	61,100	49,900	35,300	91,700	74,900	53,000	2.362	1.024	5.5	625

* **⚠ WARNING** Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°. Refer to chain chart this page and Effect of Angle chart page 10.

** A quad branch chai
four branches.
and used with branches at same angle of inclination.

INSPECTION CRITERIA FOR CHAIN

All slings should be inspected for damage prior to each use to assure that their strength has not been compromised. The following photos illustrate some of the common damage that occurs to indicate that the sling must be taken out of service.

THE DAMAGE: **Stretched Chain Links -** Indicates the sling has been extremely overloaded or subjected to shock loading.

WHAT TO LOOK FOR: Lengthening of the links and narrowing of the link width. Links that do not hinge freely with adjacent links are stretched and must be taken our of service, however, stretch **can** occur without this indicator.

TO PREVENT: Avoid overloading and shock loading.



THE DAMAGE: **Bent Links**

WHAT TO LOOK FOR: Bending usually occurs in only one or two adjacent links. Links will have an irregular shape when compared to other links.

TO PREVENT: Bent links are usually the result of the chain going around the sharp edge of a load during a lift. Load edges must be padded to protect both chain and load.

THE DAMAGE: **Weld Spatter**

WHAT TO LOOK FOR: Metallic bumps on any link of chain.

TO PREVENT: The heat from weld spatter can adversely affect the strength of a chain link. Slings must be shielded from welding operations.



THE DAMAGE: **Gouged Links**

WHAT TO LOOK FOR: Indentations on an otherwise smooth link surface.

TO PREVENT: Gouging of links is usually caused by heavy loads being dragged over or dropped onto the chain. Protect sling from these situations.

INSPECTION CRITERIA FOR CHAIN

THE DAMAGE: **Heat**

WHAT TO LOOK FOR: Discolored areas of chain

TO PREVENT: High temperatures begin to affect alloy chain strength at 400°F. When using chain slings at elevated temperatures, refer to the Lift-All temperature chart for chain slings for working load reductions.



THE DAMAGE: **Worn Links**

WHAT TO LOOK FOR: Excessive wear and a reduction of the material diameter, especially at the bearing points. Refer to Lift-All Wear Allowance Table for minimum allowable link thickness.

TO PREVENT: Wear is a natural result of sling use. Keeping load weights within the ratings of the slings being used will give the maximum sling wear life.

THE DAMAGE: **Bent/Worn/Cracked Hardware**

WHAT TO LOOK FOR: Wear of hooks and other fittings usually occurs at the bearing points. Hooks bent more than 10° from the plane of the unbent hook. Hooks opened more than 15% of the normal throat opening.

TO PREVENT: Never point load hooks or lift with hardware on a load edge.



LiftAlloy SINGLE CHAIN SLINGS

Chain Size (in.)	[1]Rated Capacity* Vertical (lbs.)		Approx. Weight 5 foot Reach Type SOS (lbs.)
	Grade 80	Grade 100	
7/32	2,100	2,700	4
9/32	3,500	4,300	5
3/8	7,100	8,800	10
1/2	12,000	15,000	18
5/8	18,100	22,600	27
3/4	28,300	35,300	44
7/8	34,200	-	58
1	47,700	-	79
1 1/4	72,300	-	121

Note: 1. Also referred to as “Working Load Limit”.

SOS Sling Hook | **SOG** Grab** Hook | **SOF** Foundry Hook | **SOL**‡ Lodelok Hook | **CO** Oblong Link

**Cradle grab hooks are standard, non-cradle hooks available on request.

LiftAlloy DOUBLE CHAIN SLINGS

Chain Size (in.)	[1]Rated Capacity* @ 60° (lbs.)		Approx. Weight 5 foot Reach Type DOS (lbs.)
	Grade 80	Grade 100	
7/32	3,600	4,700	8
9/32	6,100	7,400	10
3/8	12,300	15,200	17
1/2	20,800	26,000	32
5/8	31,300	39,100	51
3/4	49,000	61,100	74
7/8	59,200	-	99
1	82,600	-	134
1 1/4	125,200	-	211

Note: 1. Also referred to as “Working Load Limit”.

DOS Sling Hook | **DOG** Grab** Hook | **DOF** Foundry Hook | **DOL** Lodelok ‡ Hook

**Cradle grab hooks are standard, non-cradle hooks available on request.

* **⚠ WARNING** Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°. Refer to chain chart page 85 and Effect of Angle chart page 10.

‡ Not available in Grade 100.

LiftAlloy TRIPLE AND QUAD CHAIN SLINGS

Chain Size (in.)	[1]Rated Capacity* @ 60° (lbs.)		Approx. Weight 5 foot Reach Type TOS (lbs.)	Approx. Weight 5 foot Reach Type QOS (lbs.)
	Grade 80	Grade 100		
7/32	5,450	7,000	12	16
9/32	9,100	11,200	16	19
3/8	18,400	22,900	28	36
1/2	31,200	39,000	53	63
5/8	47,000	58,700	81	100
3/4	73,500	91,700	116	140
7/8	88,900	-	154	187
1	123,900	-	209	250
1 1/4	187,800	-	358	406

Note: 1. Also referred to as “Working Load Limit”.



TOS
Sling Hook



QOS
Sling Hook

LiftAlloy BASKET TYPE CHAIN SLINGS

Chain Size (in.)	[1]Rated Capacity* @ 60° (lbs.)			
	Single		Double	
	Grade 80	Grade 100	Grade 80	Grade 100
7/32	3,600	4,700	5,450	7,000
9/32	6,100	7,400	9,100	11,200
3/8	12,300	15,200	18,400	22,900
1/2	20,800	26,000	31,200	39,000
5/8	31,300	39,100	47,000	58,700
3/4	49,000	61,100	73,500	91,700
7/8	59,200	-	88,900	-
1	82,600	-	123,900	-
1 1/4	125,200	-	187,800	-

Note: 1. Also referred to as “Working Load Limit”.



SB
Single Basket Type



DB
Double Basket Type

* **⚠ WARNING** Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°.
Refer to chain chart page 85 and Effect of Angle chart page 10.

LiftAlloy ADJUSTABLE CHAIN SLINGS (Traditional Styles)

LiftAlloy Adjustable Loop Chain Slings

Chain Size (in.)	[1]Rated Capacity*@ 60° (lbs.)			
	Single		Double	
	Grade 80	Grade 100	Grade 80	Grade 100
7/32	3,600	4,700	5,450	7,000
9/32	6,100	7,400	9,100	11,200
3/8	12,300	15,200	18,400	22,900
1/2	20,800	26,000	31,200	39,400
5/8	31,300	39,100	47,000	58,700
3/4	49,000	61,100	73,500	91,700
7/8	59,200	-	88,900	-
1	82,600	-	123,900	-
1 1/4	125,200	-	187,800	-



SA
Style B **
(Standard)

DA
Style B **
(Standard)

Cradle grab hooks are standard, non-cradle hooks a available on request.

Slings shown here are the most popular of the traditional adjustable type slings. However, *Lift-All's* engineering staff can design whatever configuration is required to fit individual needs.

** Style B, single and double adjustable slings are furnished with approximately one (1) foot of chain in short branches unless otherwise specified in the order. Style A, hook is attached to master link with a coupling link.

LiftAlloy Adjustable Chain Slings

Chain Size (in.)	[1]Rated Capacity* (lbs.)			
	Single at 90°		Double at 60°	
	Grade 80	Grade 100	Grade 80	Grade 100
7/32	2,100	2,700	3,600	4,700
9/32	3,500	4,300	6,100	7,400
3/8	7,100	8,800	12,300	15,200
1/2	12,000	15,000	20,800	26,000
5/8	18,100	22,600	31,300	39,100
3/4	28,300	35,300	49,000	61,100
7/8	34,200	-	59,200	-
1	47,700	-	82,600	-
1 1/4	72,300	-	125,200	-



SAS
Style B *
(Standard)

DAS
Style B **
(Standard)

Cradle grab hooks are standard, non-cradle hooks available on request.



Style A **

LiftAlloy ENDLESS BASKET CHAIN SLINGS

Chain Size (in.)	[1]Rated Capacity* (lbs.)			
	Single at 90°		Double at 60°	
	Grade 80	Grade 100	Grade 80	Grade 100
7/32	2,100	2,700	3,600	4,700
9/32	3,500	4,300	6,100	7,400
3/8	7,100	8,800	12,300	15,200
1/2	12,000	15,000	20,800	26,000
5/8	18,100	22,600	31,300	39,100
3/4	28,300	35,300	49,000	61,100
7/8	34,200	-	59,200	-
1	47,700	-	82,600	-
1 1/4	72,300	-	125,200	-



SE
Single Endless

DE
Double Endless

Note: 1. Also referred to as "Working Load Limit".

* **⚠ WARNING** Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°.
Refer to chain chart page 85 and Effect of Angle chart page 10.

ADJUST-A-LINK GRADE 100 CHAIN SLINGS

(Patent No. 4941698)

The most easily adjustable and versatile chain sling is now stronger, too!
Ideal for machine shop and maintenance departments varied requirements.

New, Improved Master Control Plate *

Features, Advantages and Benefits

Promotes Safety

- Chain cannot be removed from the master control plate, assuring the capacity rating will not be compromised
- Alloy steel master control link for strength and reliability
- Each assembly serialized for traceability
- Complies with OSHA - proof tested and certified

Saves Money

- Grade 100 chain provides approximately 25% higher capacities than our previous *Adjust-A-Links* - replaces larger, more expensive slings
- New angled plate design reduces bending torque on chain and plate - reduces wear and extends sling life
- Wider top bearing surface reduces wear to both plate and crane hook
- Versatile - one sling does many jobs
- Using two *Adjust-A-Links* on the same crane hook eliminates the need for expensive triples and quads
- Heat treated alloy steel construction for long sling life
- Yellow powder coating on master plate and hooks prevents rust - extends sling life

Saves Time

- More compact plate design fits larger hooks for easier rigging
- Less bulky than typical double adjustable chain slings
- High visibility yellow fittings make assembly easy to spot
- Easily adjustable to accommodate a wide range of applications
- No time wasted searching for just the right sling

Never exceed rated capacities. Chain must be seated at the base of adjusting slot of the Master Control Link.



Note: To order latches on hooks, add an "L" to end of Part No.



Single

Double

Basket

* 1/2" size Master Link flame cut - not of new forged plate design - uses Grade 80 capacity ratings

Chain Size (in.)	[1]Rated Capacity * (lbs.)		Dimensions (in.)					6 ft. Length		10 ft. Length		14 ft. Length	
	Single @ 90°	Double @ 60°	Eye Width A	Eye Height B	Overall Width C	Overall Length D	Hook Opening E	Part No.	(lbs.)	Part No.	(lbs.)	Part No.	(lbs.)
7/32	2,700	4,700	2 3/16	2 11/16	3 15/16	5 1/8	15/16	30001G10	4.2	30002G10	6.2		
9/32	4,300	7,400	2 7/8	3 3/16	5 1/16	6 1/2	1 1/16	30003G10	7.5	30004G10	10.5		
3/8	8,800	15,200	3 3/4	4 1/8	6 3/4	8 11/16	1 9/16			30005G10	18.5	30006G10	24.5
1/2	12,000	20,800	4 3/8	4 3/8	9 3/4	12 3/4	2			30007	42	30008	52

* **⚠ WARNING** Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Adjust-A-Link Slings should not be used at angles of less than 45°. Refer to chain chart page 85 and Effect of Angle chart page 10.

HOOKS, MASTER LINKS, ETC.

Cradle Grab Eye Hook / Code G

Grade 80

Chain Size (in.)	Rated Capacity* (lbs.)	Dimensions (in.)						Weight Each (lbs.)
		B	D	E	I	L	M	
7/32	2,100	1.19	1.75	.36	1.19	.63	1.63	0.4
9/32	3,500	1.38	1.81	.36	1.19	.63	2.36	0.4
3/8	7,100	1.78	2.63	.45	1.75	.78	3.11	1.1
1/2	12,000	2.28	3.34	.59	1.88	1.03	3.94	2.3
5/8	18,100	2.75	4.08	.75	2.25	1.25	4.78	4.4
3/4	28,300	3.19	5.23	.88	2.88	1.44	6.25	8.8
7/8	34,200	3.75	5.69	1.00	3.00	1.75	6.50	10
1	47,700	4.31	7.00	1.19	3.88	1.88	8.09	21
1 1/4**	72,300	5.38	8.50	1.50	2.50	2.25	10.50	40

Grade 100

7/32	2,700	Use 9/32" Hook						
9/32	4,300	1.38	1.91	.36	1.06	.63	2.56	0.6
3/8	8,800	1.78	2.78	.47	1.38	.78	3.28	1.4
1/2	15,000	2.28	3.63	.59	1.81	1.03	4.22	3.1
5/8	22,600	2.75	4.08	.75	2.25	1.25	4.78	4.4
3/4	35,300	3.19	5.23	.88	2.88	1.44	6.25	8.8



** NOT cradle type
Note: Non-Cradle Grab Hooks are available upon request.

Foundry Hook / Code F

Grade 80

Chain Size (in.)	Rated Capacity* (lbs.)	Dimensions (in.)						Weight Each (lbs.)
		B	E	I	L	M	O	
9/32	3,500	1.56	2.50	1.00	.63	4.75	1.23	2.4
3/8	7,100	2.00	3.00	1.27	.75	5.75	1.50	4.5
1/2	12,000	2.50	3.50	1.50	1.00	6.88	1.75	7.1
5/8	18,100	3.00	4.00	1.81	1.25	8.06	2.03	12
3/4	28,300	3.50	4.50	2.20	1.50	9.25	2.56	20
7/8	34,200	4.00	5.00	2.25	1.75	10.38	2.78	26
1	47,700	4.50	5.50	2.59	2.13	11.56	3.03	37
1 1/4	72,300	5.13	6.00	3.17	2.38	12.88	3.81	58

Grade 100

9/32	5,700	1.56	2.50	1.00	.63	4.75	1.23	2.4
3/8	8,800	2.00	3.00	1.27	.75	5.75	1.50	4.5
1/2	15,000	2.50	3.50	1.50	1.00	6.88	1.75	7.1
5/8	22,600	3.00	4.00	1.81	1.25	8.06	2.03	12
3/4	35,300	3.50	4.50	2.20	1.50	9.25	2.56	20



* **⚠ WARNING**

Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases.
Slings should not be used at angles of less than 30°.
Refer to chain chart page 85 and Effect of Angle chart page 10.

HOOKS, MASTER LINKS, ETC.

Lodelok Eye Hooks

Grade 80

Chain Size (in.)	Rated Capacity* (lbs.)	Dimensions (in.)					Weight Each (lbs.)
		C	D	E	F	J	
9/32	4,300	5.37	.88	3.77	1.64	.91	2.5
3/8	8,800	6.65	1.07	4.76	2.27	1.14	4.6
1/2	15,000	8.79	1.58	6.26	2.91	1.46	10.0
5/8	22,600	10.36	1.97	7.37	3.20	1.81	16.0

Design factor @ 4:1



Cradle Grab Clevis Hook / Code G

Grade 80

Chain Size (in.)	Rated Capacity* (lbs.)	Dimensions (in.)				Weight Each (lbs.)
		D	E	T	M	
9/32	3,500	1.78	.36	1.19	1.63	0.5
3/8	7,100	2.56	.47	1.75	2.11	1.2
1/2	12,000	3.25	.59	2.13	2.88	2.4
5/8	18,100	4.08	.75	2.50	3.56	4.2
3/4	28,300	5.23	.88	2.88	5.50	9.6



Chain Sling Clevis Hook with Optional Latch / Code S

Grade 80

Chain Size (in.)	Rated Capacity* (lbs.)	Dimensions (in.)				Weight Each (lbs.)
		I	M	P	R	
9/32	3,500	.73	3.44	1.05	1.06	0.8
3/8	7,100	.95	4.47	1.28	1.31	2.0
1/2	12,000	1.17	5.27	1.66	1.56	4.5
5/8	18,100	1.44	6.08	2.19	1.75	6.5
3/4	28,300	1.69	7.34	2.56	2.19	12



HOOKS, MASTER LINKS, ETC.

Oblong Master Link / Code O

Link Size * (in.)			Type & Size of Chain Sling on which used				Weight Each (lbs.)
Diameter Material A	Inside Width B	Inside Length C	Single	Double	Triple	Quad	
13/32	1 1/2	3	7/32	7/32	-	-	0.3
1/2	2 1/2	5	9/32	9/32	7/32	7/32	0.8
3/4	3	6	3/8	3/8	9/32	9/32	2.1
1	4	8	1/2 or 5/8	1/2	3/8	3/8	4.6
1 1/4	4 3/8	8 3/4	3/4	5/8	1/2	1/2	9.2
1 1/2	5 1/4	10 1/2	7/8	3/4	5/8	5/8	16
1 3/4	6	12	1	7/8	3/4	3/4	25
2	7	14	1 1/4	1	7/8	7/8	37
2 1/4	8	16	-	1 1/4	1	1	54
2 3/4	9	16	-	-	1 1/4	1 1/4	85



* If sub-assemblies are used, inside dimensions may be reduced. Contact Lift-All if critical.

Chain Sling Eye Hook with Optional Latch / Code S

Grade 80

Chain Size (in.)	Rated Capacity* (lbs.)	Dimensions (in.)							Weight Each (lbs.)
		B	E	I	L	M	P	R	
7/32	2,100	-	1.25	.78	.75	3.06	.86	1.11	0.7
9/32	3,500	1.62	1.19	.73	.75	3.75	1.05	1.06	1.1
3/8	7,100	2.06	1.44	.95	.94	4.78	1.28	1.31	1.9
1/2	12,000	2.63	1.78	1.17	1.13	5.69	1.66	1.56	4.5
5/8	18,100	3.06	2.03	1.44	1.31	6.50	2.19	1.75	7.3
3/4	28,300	3.50	2.50	1.69	1.50	7.81	2.51	2.19	11
7/8	34,200	3.88	2.78	1.94	1.69	8.75	2.84	2.38	18
1	47,700	4.31	3.13	2.14	1.88	9.88	3.09	2.78	23
1 1/4	72,300	5.31	3.88	2.62	2.31	11.50	3.89	3.41	36



Grade 100

7/32	2,700	Use 9/32" Hook							
9/32	5,700	1.62	1.19	.73	.75	3.75	1.05	1.06	1.1
3/8	8,800	2.06	1.44	.95	.94	4.78	1.28	1.31	1.9
1/2	15,000	2.63	1.78	1.17	1.13	5.69	1.66	1.56	4.5
5/8	22,600	3.06	2.03	1.44	1.31	6.50	2.19	1.75	7.3
3/4	35,300	3.50	2.50	1.69	1.50	7.81	2.51	2.19	11

Note: When ordering, specify latch if desired.

HOOKS, MASTER LINKS, ETC.

Mechanical Coupling Links

Grade 80

Chain Size (in.)	Rated Capacity* (lbs.)	Dimensions (in.)				Weight Each (lbs.)
		A	B	C	E	
7/32	2,100	.25	1.41	.49	.41	0.12
9/32	3,500	.31	1.81	.63	.50	0.23
3/8	7,100	.50	2.41	.83	.75	0.65
1/2	12,000	.69	3.38	1.22	1.00	1.5
5/8	18,100	.81	4.06	1.50	1.25	2.6
3/4	28,300	.94	4.78	1.80	1.50	3.8
7/8	34,200	1.05	5.13	1.91	1.75	6.3
1	47,700	1.25	5.75	2.19	2.00	9.3
1 1/4	72,300	1.53	6.81	2.63	2.25	17



Plate Hook

Chain Size (in.)	Rated Capacity* (lbs.)	Dimensions (in.)					Weight Each (lbs.)
		A	B	L	M	W	
9/32	4,200	2.00	1.75	1.00	3.68	2.50	2.8
3/8	7,400	2.63	3.00	1.12	6.38	2.75	5.7
1/2	13,000	3.50	4.00	1.50	7.37	3.50	13
5/8	20,400	4.38	5.00	1.88	9.25	5.00	27
3/4	30,000	5.18	6.00	2.25	10.88	5.75	42
7/8	40,000	6.00	7.00	2.63	13.68	6.00	65



* Ratings are per hook
Do not use plate hooks at angles other than 60° from horizontal.
Do not attempt to lift using only one plate hook.

S Hook

Stock Dia. (in.)	Rated Capacity* (lbs.)	Dimensions (in.)				Weight Each (lbs.)
		A	B	F	R	
9/32	210	4 1/2	1 1/8	1 1/8	9/16	0.15
3/8	410	6	1 1/2	1 1/2	3/4	0.35
1/2	870	7 1/2	2	2	1	0.82
5/8	1,120	9	2 1/2	2 1/2	1 1/4	1.6
3/4	1,730	10 1/2	3	3	1 1/2	2.6
7/8	2,370	12	3 1/2	3 1/2	1 3/4	4.2
1	2,920	13	4	4	2	6.0
1 5/32	3,150	15	4 1/2	4 1/2	2 1/4	9.3
1 1/4	4,450	16	5	5	2 1/2	12
1 3/8	6,100	17	5 1/2	5 1/2	2 3/4	15
1 1/2	6,250	18	6	6	3	20



See page 116 for J-Hooks and Custom Engineered Lifting Devices.

*

⚠ WARNING Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°.
Refer to chain chart page 85 and Effect of Angle chart page 10.

CHAIN



LiftAlloy Grade 80 Welded Alloy Chain

- Primarily used for overhead lifting slings
- Proof tested
- Black finish

Welded Carbon Chain

- Grade 30 Proof Coil available as self colored, zinc plated or hot galvanized
- Grade 43 High Test available as bright finish, zinc plated or hot galvanized
- Grade 70 Binding (transport) is furnished with a gold finish as standard

Alloy Chain

Chain Size (in.)	Grade 80	
	Rated Capacity* (lbs.)	Weight Per CFT. (lbs.)
7/32	2,100	45
9/32	3,500	74
3/8	7,100	146
1/2	12,000	258
5/8	18,100	387
3/4	28,300	622
7/8	34,200	776
1	47,700	995
1 1/4	72,300	1571

Carbon Chain

Chain Size (in.)	Grade 30		Grade 43		Grade 70	
	Rated Capacity* (lbs.)	Weight Per CFT. (lbs.)	Rated Capacity* (lbs.)	Weight Per CFT. (lbs.)	Rated Capacity* (lbs.)	Weight Per CFT. (lbs.)
3/16	800	38	-	-	-	-
1/4	1,300	66	2,600	71	3,150	74
5/16	1,900	98	3,900	98	4,700	100
3/8	2,650	144	5,400	144	6,600	156
1/2	4,500	278	9,200	278	11,300	259
5/8	6,900	422	13,000	422	-	-
3/4	10,600	628	20,200	606	-	-

Note: Grade 30 Proof Coil, Grade 43 High Test and Grade 70 Binding (transport) tiedown chain and their fittings are not recommended for lifting or hoisting per ASME B30.9.

* **⚠ WARNING** Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°.
Refer to chain chart page 85 and Effect of Angle chart page 10.

Roughneck WIRE MESH SLINGS

Specialty Slings with Particular Properties and Uses

Widely used in metalworking shops and steel warehouses where loads are abrasive, hot or tend to cut web

Features, Advantages and Benefits

Promotes Safety

- Steel construction resists abrasion and cutting
- Each sling permanently stamped with capacity and serial number
- Good flexibility - grips load's contours
- Each sling proof tested and certified

Saves Money

- Grips load firmly without stretching - reduces load damage
- Resists abrasion and cutting for greater sling life
- Flexibility and low stretch reduce load damage
- Wide bearing area distributes load to help avoid load damage
- Repairable - thus very cost effective
- Alloy steel end fittings - plated for long life
- Wire mesh is galvanized - resists corrosion

Saves Time

- Width of mesh helps control and balance load
- End fittings fit most large crane hooks

Roughneck Wire Mesh Sling Construction

Standard Construction: Alloy steel end fittings, zinc plated. Mesh is galvanized high tensile steel. 10 gage is standard, 12 gage is available upon request

Optional Construction: Stainless steel mesh is available for corrosive and hotter environments.

Inspection Criteria for *Roughneck* Wire Mesh Slings

Remove the sling from service if any of the following is visible: (See Page 102)

- A broken weld or brazed joint along the sling edge
- A broken wire in any part of the mesh
- Reduction in wire diameter of 25% due to abrasion or 15% due to corrosion
- Lack of flexibility due to distortion of the mesh
- Visible distortion or wear of either end fitting
- Cracked end fitting

* **⚠ WARNING**

Environmental Considerations

- Wire mesh slings shall not be used at temperatures above 550°F.
- Store in a clean, dry area to avoid corrosive action

⚠ WARNING

Do not edge load. Full width of mesh must contact load.

How To Order

Specify:

1. Mesh Gage (10 or 12)
2. Mesh Width - Inches
3. Length - Feet (Bearing point to bearing point)
4. Sling Type (1 or 2)

Wire Mesh Width (in.)	Rated Capacity (lbs.) *		
	Vertical	Choker	Basket
10 Gage - Heavy Duty			
2 3	2,300 3,500	2,300 3,500	4,600 7,000
4 6	4,800 7,200	4,800 7,200	9,600 14,400
8 10	9,600 12,000	9,600 12,000	19,200 24,000
12 14	14,400 16,800	14,400 16,800	28,800 33,600
16 18	19,200 21,600	19,200 21,600	38,400 43,200
20	24,000	24,000	48,000
12 Gage - Medium Duty			
2 3	1,600 2,400	1,600 2,400	3,200 4,800
4 6	3,200 4,800	3,200 4,800	6,400 9,600
8 10	6,400 8,000	6,400 8,000	12,800 16,000
12	9,600	9,600	19,200

NOTE: The choker fitting must not be positioned against a load edge or directly on the triangle fitting.

Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°. Refer to Effect of Angle chart page 10.

Roughneck WIRE MESH SLINGS

Select The Proper Mesh

10 Gage - Heavy Duty



12 Gage - Medium Duty



This single 4" wide mesh sling in a choker hitch at load center of gravity provides adequate stability for many structural steel loads.



Prompt Shipment or Repair Service by Experts

Wire mesh slings with normal usage will eventually need repair and parts replaced. This can be done for relatively small cost. *Lift-All* wire mesh slings that are repaired are guaranteed to meet or exceed original specifications. Five *Lift-All* factories are strategically located in the U. S. to insure prompt service. We repair all types and brands of mesh slings.



Nom. Mesh Width (in.)	Terminal Dimensions (in.)				Terminal Thickness (in.)		Approx. Weight (lbs.) of 3 ft. Type 1 Slings		Mesh Weight (Per ft. in lbs.)	
MW	D	IL	TL	CL	10 GA	12 GA	10 GA	12 GA	10 GA	12 GA
2 3	2 2 1/4	3 3 3/8	3 7/8 4 3/8	5 5/8 6 1/4	1/2 1/2	1/2 1/2	6 8	5 8	1.3 1.9	1.1 1.8
4 6	3 3 1/2	4 4 1/2	5 5 5/8	6 3/4 7 3/4	1/2 1/2	1/2 1/2	10 16	10 14	2.5 3.9	2.3 3.4
8 10	4 1/2 4 3/4	6 6 1/4	7 1/2 8	9 10 7/8	1/2 1/2	1/2 1/2	22 28	21 26	5.1 6.4	4.5 5.6
12 14	5 5	6 1/2 6 1/2	8 5/8 8 3/4	11 3/8 12 3/4	1/2 1/2	1/2 1/2	34 40	32 37	7.6 8.9	6.8 7.9
16 18	5 1/4 5 1/2	7 7 1/2	9 1/8 9 3/4	14 1/4 15 3/4	3/4 3/4	1/2 1/2	57 67	38 44	10 11	9.0 10
20	5 3/4	7 3/4	10 1/8	17	3/4	1/2	77	51	13	11

Roughneck CHAIN MESH SLINGS

Specialty Slings for rugged applications.

Widely used in metalworking shops, and stevedoring where abrasive conditions or hot environments damage and destroy synthetic slings.

Features, Advantages and Benefits

Promotes Safety

- Each sling permanently stamped with capacity and serial number for traceability
- Steel construction resists abrasion and cutting
- Each sling proof tested and certified

Saves Time

- Width of mesh helps to balance and control loads
- End fittings fit most large crane hooks

Saves Money

- Alloy steel end fittings and Grade 80 Alloy chain resists abrasion and cutting for greater sling life
- Repairable - thus cost effective
- Low stretch and good flexibility reduces load damage
- Wide bearing area distributes load to help avoid load damage

Inspection Criteria for *Roughneck* Chain Mesh Slings

Remove sling from service if any of the following are visible:

- Wear, nicks, cracks, breaks, gouges, stretch, bends or weld spatter on chain or attachments
- Discoloration from excessive temperature
- Chain links and attachments won't hinge freely with adjacent links
- Visible distortion of either end fitting out of its plane
- Distortion or any collapse of eye width on either end fitting
- 15% reduction of original cross-sectional area of metal at any point of either end fitting
- Cracked end fitting

How to Order

Specify:

1. Chain size - ($^{7}/_{32}$", $^{9}/_{32}$", $^{3}/_{8}$" or $^{1}/_{2}$")
2. Type 1 (Triangle & Choker) or Type 2 (Triangle & Triangle)
3. Number of parts of chain
4. Length - Feet (Bearing point to bearing point)

Chain Size (in.)	Parts of Chain	Sling Width (in.)	Rated Capacity (lbs.)*		
			Vertical	Choker	Basket
7/32	3	1 1/2	5,000	5,000	10,000
	4	2	6,700	6,700	13,400
	5	2 1/2	8,400	8,400	16,800
	6	3	10,000	10,000	20,000
9/32	3	2 1/8	8,400	8,400	16,800
	4	2 3/4	11,000	11,000	22,000
	5	3 3/8	14,000	14,000	28,000
	6	4	16,800	16,800	33,600
3/8	3	3 1/4	17,000	N/A	34,000
	4	4 3/8	22,700	N/A	45,400
	5	5 3/8	28,400	N/A	56,800
	6	6 1/2	34,000	N/A	68,000
1/2	2	3	19,200	N/A	38,400
	3	4 1/2	28,800	N/A	57,600
	4	6	38,400	N/A	76,800

* **⚠ WARNING** Do not exceed rated capacities. Sling capacity decreases as the angle from horizontal decreases. Slings should not be used at angles of less than 30°.

Environmental Considerations

- Rated capacities of chain mesh are reduced at temperatures above 400°F. (See table page 84)
- Store in clean, dry area to avoid corrosive action

Roughneck CHAIN MESH SLINGS



Type 1
Triangle & Choker

Chain Size (in.)	Parts of Chain	Sling Width (in.)	Terminal Dimensions (in.)								5 ft. Type 2 Weight (lbs.)	Weight per ft. (lbs.)
			D	IL	TL	TW	CL	CW	T	H		
7/32	3	1 1/2	2 3/4	4 1/8	6 3/4	4 3/4	9	7 1/8	3/8	1 1/4	10	1.3
	4	2	3	4 1/2	7 1/8	5	9 3/8	7 1/4	3/8	1 1/4	12	1.8
	5	2 1/2	3 1/2	5 1/4	8	5 1/2	10 1/8	7 3/4	3/8	1 1/4	14	2.2
	6	3	3 3/4	5 5/8	8 1/4	5 3/4	10 5/8	8 1/4	3/8	1 1/4	17	2.7
9/32	3	2 1/8	2 3/4	4 1/8	6 3/4	4 3/4	9	7 1/8	1/2	1 3/4	14	2.2
	4	2 3/4	3	4 1/2	7 1/8	5	9 3/8	7 1/4	1/2	1 3/4	18	3.0
	5	3 3/8	3 1/2	5 1/4	8	5 1/2	10 1/8	7 3/4	1/2	1 3/4	22	3.7
	6	4	3 3/4	5 5/8	8 1/4	5 3/4	10 5/8	8 1/4	1/2	1 3/4	26	4.5
3/8	3	3 1/4	3 1/2	5 1/4	6 7/8	5			3/4	2 1/4	30	4.4
	4	4 3/8	4 3/8	6 1/2	8 1/8	6 3/8			3/4	2 1/4	41	5.8
	5	5 3/8	4 3/8	6 1/2	8 3/8	7 3/8			3/4	2 1/4	55	7.3
	6	6 1/2	5 1/4	7 7/8	9 3/4	8 1/4			3/4	2 1/4	59	8.8
1/2	2	3	3 1/2	5 1/4	6 7/8	5			1	3 1/8	33	5.2
	3	4 1/2	4 3/8	6 1/2	8 3/8	6 3/8			1	3 1/8	50	7.7
	4	6	5 1/4	7 7/8	9 3/4	7 3/4			1	3 1/8	62	10

Note: Length tolerance ± 2 chain links so plane is maintained.

INSPECTION CRITERIA FOR WIRE MESH SLINGS

All slings should be inspected for damage prior to each use to assure that their strength has not been compromised. The following photos illustrate some of the common damage that occurs to indicate that the sling must be taken out of service.

THE DAMAGE: **Overloading / Uneven Loading**

WHAT TO LOOK FOR: Mesh does not lie flat, appears distorted and/or will not bend easily.

TO PREVENT: Do not load in excess of rated capacity. Load edges must be straight / flat and in contact with full width of mesh at bearing points.



THE DAMAGE: **Wear**

WHAT TO LOOK FOR: Flat areas on the individual wires. When wires have lost 25% or more of their original diameter, the sling must be taken out of service.

TO PREVENT: Do not drag sling on the ground and do not drag loads over slings. Pad high wear areas.

THE DAMAGE: **Corrosion / Heat Damage**

WHAT TO LOOK FOR: Areas of discoloration. Remove slings with wire diameter reduction of 15% or more. Slings exposed to temperatures of 550° F or more must be removed from service.

TO PREVENT: Hang slings for storage away from moisture. Do not use mesh slings above 550° F. Consider using stainless steel mesh.

THE DAMAGE: **Broken Weld or Brazed Joint**

WHAT TO LOOK FOR: A cracked or separation of the wire at the edge or in the body of the mesh.

TO PREVENT: Do not side load mesh. Tension on sling must be distributed evenly across the entire width of the mesh.

THE DAMAGE: **Distortion or Wear of End Fittings**

WHAT TO LOOK FOR: Fittings that do not lie flat or have obvious areas of wear.

TO PREVENT: Never lift with fitting against a load edge or set load directly onto sling. Reduce wear by keeping loads within the rated capacity of the sling.



Load Hugger BASICS

Lift-All Load Hugger cargo control and load securement products are of the highest quality. They offer the van and flatbed operator a wide variety of options to meet Department of Transportation and CVSA requirements.*

Features, Advantages and Benefits

Promotes Safety

- Flexible, conforms to and controls the load
- Ratchet assembly allows easy adjustment
- All hooks and chain assemblies equal or exceed strength of webbing
- Meet all DOT (Department of Transportation) and CVSA (Commercial Vehicle Safety Alliance) regulations.

Saves Money

- Soft and wide - does not damage costly cargo
- Large selection - choose the capacity that's right for the load carried

Saves Time

- Light weight, easy to handle
- Large selection of end fastenings, winches and ratchets make choosing and using the correct assembly easy

Inspection Criteria

Remove from service if any of the following are visible:

- Cuts, holes, surface abrasion or crushed areas
- Burns or chemical damage
- Separation of load carrying stitch pattern
- Hardware, fittings or tensioning devices which are broken, bent, twisted, cracked, or have nicks and gouges
- Knotted webbing
- Splices or other makeshift repairs
- Damaged loop ends

See illustrations of damaged webbing on page 16 & 17; damaged chain and hooks on page 85.

Definitions

Working Load Limit: The maximum load that may routinely be applied to an assembly or component in straight tension.

Ultimate Strength: The load at which an assembly or component will fail in testing.

Department of Transportation Regulations 393, 102(b) use Ultimate Breaking Strength to calculate the number of tiedown assemblies required to secure a load.

Lift-All publishes Ultimate Strength for this purpose only. For safety, we recommend that only Working Load Limits be used for your calculations.

Environmental Considerations

- Nylon and polyester are seriously degraded at temperatures above 200° F.
- Prolonged exposure to Ultraviolet light adversely affects nylon and polyester. Tie down straps become bleached and stiff when exposed to sunlight or arc welding.
- Many acids, alkalis and chemicals have an adverse effect on nylon and polyester. See chart on page 14.

Safe Operating Practices

- Inspect tie down straps and all hardware when load is first being secured.
- Re-tighten tie downs periodically during run.
- Never use *Load Huggers* for anything other than securing cargo. Do not use for lifting loads or towing vehicles.
- Load should be securely blocked and stabilized before tensioning the straps.
- Never exceed rated capacities.
- Use caution when tossing straps and chain anchor assemblies over a load.
- Check installation of portable winches - ratchet pawl must be at top of toothed wheel and bolts tight against the rub rail.
- Weld-on winches should not be cracked.
- Corner protectors and wear pads should be used to protect *Load Huggers* from sharp edges and abrasion.
- All hardware must be in line with direction of pull to achieve full strength.

* CVSA - Commercial Vehicle Safety Alliance
Phone: 202-775-1623 Fax: 202-775-1624
www.cvsa.org

WEB SELECTION

Two **styles** of webbing are available for our 2”-4” ratchet assemblies and winch straps: **Standard** and ***Tuff-Edge***.

Two **strength classes** are available for 2” assemblies: **Single Stripe** and **Double Stripe.**

Standard Polyester Tiedown Webbing

This webbing offers exceptional value for everyday use.

***Tuff-Edge* Polyester Tiedown Webbing**

Special black polymer edge yarns provide 32% better edge cut resistance for longer assembly life.





Single Stripe - Used for 2" assemblies with a 1,600 lb. Working Load Limit.
Used in all 4" assemblies and winch straps.
Approximately 1/32" thick.





Double Stripe - Used for 2" assemblies with a 3,300 lb. Working Load Limit.
Used in all 3" assemblies and winch straps.
Approximately 3/64" thick.

RATCHET ASSEMBLIES

Type B Assemblies

Two piece assemblies with one fixed length of webbing and one adjustable length of webbing. Numerous end fittings are available to handle any requirements. (See following pages)

Series 1,000

- 1" wide polyester webbing
- Ultimate strength - 2,100 lbs. *
- Working Load Limit - 700 lbs. *

Series 5,000

- 2" wide polyester webbing
- Ultimate strength - 5,000 lbs.
- Working Load Limit - 1,600 lbs.

Series 10,000

- 2" wide polyester webbing
- Ultimate strength - 10,000 lbs.
- Working Load Limit - 3,300 lbs.

Series 15,000

- 3" or 4" wide polyester webbing
- Ultimate strength - 15,000 lbs.
- Working Load Limit - 5,000 lbs.



Type A Assemblies

One piece (endless) assembly for use without end fittings.

* When using flat hooks in Series 1,000, ultimate strength is 1,000 lbs., working load limit is 330 lbs.

1" TIEDOWN ASSEMBLIES

Webbing Ultimate Strength * (lbs.) Working Load Limit (lbs.)	Series 1,000 — 1" Wide Polyester 2,100 with Ratchet** / 1,000 with Cam 700 with Ratchet** / 330 with Cam			
	Buckle	**Part No. 10 Ft. Lgth.**	**Part No. 15 Ft. Lgth.**	**Weight (lbs.)**
Flat Hook **	Ratchet	60102	6A102	1.1
	Cam	60110	6A110	.7
Stamped Snap Hook	Ratchet	60104	6A104	1.5
	Cam	60113	6A113	1.0
U-Hook	Ratchet	60101	6A101	1.1
	Cam	60109	6A109	.7
Hook & Keeper 	Ratchet	60105	6A105	1.5
	Cam	60114	6A114	1.1
Open Hook (PE Coated or Zinc Plated) (PE Coated Hook shown)	Ratchet PE Hook	60103	6A103	1.7
	Ratchet ZP Hook	60106	6A106	1.6
	Cam PE Hook	60111	6A111	1.3
	Cam ZP Hook	60112	6A112	1.2
Type A (Endless) (Series 1,000 Cam Buckle shown)	Ratchet	60107	6A107	.9
	Cam	60108	6A108	.5

Note: Because end terminations vary proportionally with size, check with Lift-All if critical dimensions are required. Non-standard lengths available upon request.
* Ultimate strength of assembly when new.
** Exception: When used with Flat Hooks, 1" Ratchet Assembly rating is 1,000 lbs. ULTIMATE STRENGTH and 330 lbs. WORKING LOAD LIMIT.

Our popular 1" Ratchet Tiedown with vinyl coated Open Hooks is available in 15 foot lengths in a 16 piece display box (Part No. 6A103B)

RATCHET ASSEMBLIES

Webbing Ultimate Strength * Working Load Limit	Length	Series 5,000 — 2" Wide Polyester 5,000 lbs. 1,600 lbs.			Series 10,000 — 2" Wide Polyester 10,000 lbs. 3,300 lbs.		
		Standard Part No.	Tuff-Edge Part No.	Weight (lbs.)	Standard Part No.	Tuff-Edge Part No.	Weight (lbs.)
Flat Hook (Series 10,000 shown)	27'	60501	TE60501	4.6	61001	TE61001	5.8
	30'	60502	TE60502	4.8	61002	TE61002	6.0
Stamped Triangle (Series 5,000 shown)	27'	60503	TE60503	4.2	61003	TE61003	5.2
	30'	60504	TE60504	4.4	61004	TE61004	5.4
Stamped Snap Hook (Series 10,000 shown)	27'	60505	TE60505	4.6	61005	TE61005	6.2
	30'	60506	TE60506	4.8	61006	TE61006	6.4
Twisted Snap Hook (Series 10,000 shown)	27'	60507	TE60507	5.2	61007	TE61007	5.6
	30'	60508	TE60508	5.4	61008	TE61008	5.8
Forged Snap Hook (Series 10,000 shown)	27'	60509	TE60509	5.8	61009	TE61009	6.4
	30'	60510	TE60510	6.0	61010	TE61010	6.6
D-Ring	27'	60511	TE60511	4.2			
	30'	60512	TE60512	4.4			
U-Hook	27'	60513	TE60513	4.6	26422	TE26422	5.8
	30'	60514	TE60514	4.8	26423	TE26423	6.0
Hook & Keeper	27'	60515	TE60515	4.8			
	30'	60516	TE60516	5.0			
Chain Anchor	27'				61013	TE61013	13.0
	30'				61014	TE61014	13.2
Type A (Endless) (Series 5,000 Ratchet Buckle shown)	27'	60517	TE60517	3.8	61011	TE61011	4.4
	30'	60518	TE60518	4.0	61012	TE61012	4.6

Note: Because end terminations vary proportionally with size, check with *Lift-All* if critical dimensions are required. Non-standard lengths available upon request.

* Ultimate strength of assembly when new.

RATCHET ASSEMBLIES

Webbing Ultimate Strength * Working Load Limit	Length	Series 15,000					
		3" Wide Polyester 15,000 lbs. 5,000 lbs.			4" Wide Polyester 15,000 lbs. 5,000 lbs.		
		Standard Part No.	Tuff-Edge Part No.	Wt. (lbs.)	Standard Part No.	Tuff-Edge Part No.	Wt. (lbs.)
Flat Hook	27'	20482	TE20482	12.8	26424	TE26424	13.6
	30'	20483	TE20483	13.2	26425	TE26425	14.0
Forged Triangle	27'	20484	TE20484	14.0	26430	TE26430	14.8
	30'	20485	TE20485	14.4	26431	TE26431	15.2
Chain Grab Hook	27'	20486	TE20486	13.4	26426	TE26426	14.2
	30'	20487	TE20487	13.8	26427	TE26427	14.6
Chain Anchor Assembly	27'	20488	TE20488	16.8	26432	TE26432	17.6
	30'	20489	TE20489	17.2	26433	TE26433	18.0
U-Hook	27'	20494	TE20494	13.0	26436	TE26436	13.8
	30'	20495	TE20495	13.2	26437	TE26437	14.2
Sewn Eye	27'	20490	TE20490	11.0	26428	TE26428	11.8
	30'	20491	TE20491	11.4	26429	TE26429	12.2
Type A (Endless)	27'	20492	TE20492	10.6	26434	TE26434	11.4
	30'	20493	TE20493	11.0	26435	TE26435	11.8

WEAR PADS AND CORNER PROTECTORS

Sliding Sleeve

- Double walled tubular product
- Specify length when ordering
- Protects Load Hugger webbing from abrasion and helps resist cutting

Ratchet Protector

A sewn fabric pad used to protect surface finish of cargo and ratchet mechanism. Specify with order.

Corner Protector

A movable, rust-proof copolymer corner guard. Protects Load Hugger from sharp edges. Tough enough to be used with either chain or webbing. For other wear pad options, see pages 123-126 in the Accessories section.



WINCH STRAP ASSEMBLIES AND WINCHES

Series 12,000, *Load Huggers*
3 & 4 inch Wide Polyester Winch Assemblies

- Series 12,000 *Load Huggers* are made for securely mounted winches on flat bed trucks and trailers.
- Ultimate strength 15,000 lbs.
- Working load limit 5,000 lbs.
- Standard assemblies in 3" or 4" widths and 27' or 30' lengths
- Wear pads and corner protectors extend life of *Load Hugger* (see page 109)
- To order non-standards - specify width, length, and end fitting

Winches must be properly installed with ratchet pawl on top of toothed wheel to help prevent accidental disengagement.

Standard Winch #61222
For 3" & 4" Series 12,000 *Load Huggers* -7.8 lbs.

Portable Winch #61221
For 3" & 4" Series 12,000 *Load Huggers* - 8.8 lbs.

Winch Bar
#61223
For use with 61221 and 61222 - 4.8 lbs.

End Fitting	Web Width (in.)	Assembly Length (ft.)	Standard Part No	Tuff-Edge Part No.	Assembly Weight (lbs.)
Flat Hook					
	4	27	61201	TE61201	4.0
	4	30	61202	TE61202	4.6
	3	27	61203	TE61203	4.4
	3	30	61204	TE61204	4.8
Forged Triangle					
	4	27	61205	TE61205	4.4
	4	30	61206	TE61206	5.0
	3	27	61207	TE61207	4.8
	3	30	61208	TE61208	5.2
GrabHook					
	4	27	61209	TE61209	4.2
	4	30	61210	TE61210	4.8
	3	27	61211	TE61211	4.6
	3	30	61212	TE61212	5.0
Chain Anchor					
	4	27	61213	TE61213	6.0
	4	30	61214	TE61214	6.6
	3	27	61215	TE61215	6.4
	3	30	61216	TE61216	6.8
Sewn Eye					
	4	27	61217	TE61217	3.0
	4	30	61218	TE61218	3.6
	3	27	61219	TE61219	3.4
	3	30	61220	TE61220	3.8
U-Hook					
	4	27	61225	TE61225	4.2
	4	30	61226	TE61226	4.8
	3	27	61227	TE61227	4.6
	3	30	61228	TE61228	5.0

E - TRACK AND VAN INTERIOR ASSEMBLIES

To order non-standard interior van restraint assemblies specify:

- Overall length
- Fixed Length
- Cam buckle or ratchet buckle
- Spring loaded E-Track, 3 piece E-Track or any of the end fittings listed in Series 5,000 *Load Huggers* (page 108) may be attached
- Ultimate Assembly Strength: 2,500 lbs. with Cam Buckle
  3,000 lbs. with Ratchet
- Working load limit: 800 lbs. with Cam Buckle
  1,000 lbs. with Ratchet Buckle
- E-Track only works with E-Track fittings

Standard E-Track Straps	Standard Part No.	Tuff-Edge* Part No.	Wt. (lbs.)
2" x 12' Cam Buckle/Spring E Track Fittings - Yellow	60805	TE60805	1.6
2" x 16' Cam Buckle/Spring E Track Fittings - Gray	60806	TE60806	1.7
2" x 20' Cam Buckle/Spring E Track Fittings - Blue	60807	TE60807	1.8
2" x 12' Ratchet/Spring E Track Fittings - Yellow	60808	TE60808	2.0
2" x 16' Ratchet/Spring E Track Fittings - Gray	60809	TE60809	2.1
2" x 20' Ratchet/Spring E Track Fittings - Blue	60810	TE60810	2.2

**Tuff-Edge* web is yellow for all lengths.*

Van interior restraint assemblies are only as strong as the anchor or track to which they are attached.

Cam Buckle and
3 Piece **E-Track Fitting**

Spring Loaded **E-Track Fitting** (standard)

Horizontal E-Track #60801
12 Ga. Steel - Primed
10 ft. Sections - 17 lbs.

Vertical E-Track #60802
12 Ga. Steel - Primed
10 ft. Sections - 17 lbs.

Note: E-Track can be cut into lengths suitable for UPS shipments.

TIE DOWN CHAIN AND BINDERS

Tiedown Chain - Boomers (Grab hook each end)

Load Binders

Tiedown Chain - Boomers (Grab hook each end)	Standard Part No.	Wt. (lbs.)
5/16 x 20' G-70 Yellow Dichromate-Welded Hooks	16001	21.0
3/8 x 20' G-43 Self-colored-Welded Hooks	16002	32.0
5/16 x 20' G-70 Yellow Dichromate-Clevis Hooks	16005	21.0
3/8 x 20' G-43 Self-colored-Clevis Hooks	16006	32.0
Load Binders		
5/16 - 3/8 Lever Style	16004I	8.0
5/16 - 3/8 Ratchet Style	16003I	12.0

BASIC INFORMATION

Lift-All can provide a unique engineered device for your production requirements. Our custom devices range from large capacity beams to control and balance unwieldy loads, to fork lift attachments or small “S” or “J” hooks.

Features, Advantages and Benefits

Promotes Safety

- Specifically designed equipment makes each lift safer
- All equipment conforms to highest engineering standards and meets or exceeds government and industry regulations (ASME B30.20)
- Helps eliminate employee fatigue - raises morale and quality of work

Saves Money

- Productivity improves through efficiency when using properly designed lifting devices.
- Equipment can be designed to prevent costly load damage
- Rugged materials and construction provide long useful life

Inspection Criteria for Lifting Devices

Visually inspect lifting device and slings prior to each lift. Have competent person record inspection a minimum of once a year.

Check the following and correct before use:

- Structural deformation, cracks, excessive wear
- Loose or missing guards, fasteners, covers, stops or name plates
- Inoperable mechanisms including automatic hold or release devices
- Loose bolts or fasteners
- Cracked or worn gears, pulleys, sheaves, sprockets, bearings and chains
- Excessive wear of friction pads, linkage or other mechanical parts
- Excessive wear of hoist hooking points and load support clevises or pins

Safe Operating Practices

- Use only per ASME B30.20
- Check name plate to assure proper lifting capacity
- Lift a test load a sufficient distance to assure that the load is supported properly by the lifter and then inspect lifter for defects and deformation
- Instruct the operator in correct lifting practices including proper storage, load distribution, use of associated slings, temperature considerations, avoidance of obstructions, acceleration, side pulls and angle of lift. Read “Help” section, pages 3 through 12.
- Never lift over people and never ride the load
- For proper use of slings with lifting devices refer to ASME B30.9 and appropriate section of this catalog

How to Order - The Easy Order System

1. Photocopy appropriate drawing from the following pages
2. Fill-in your specific data
3. Fax to *Lift-All* at 717-898-1215.

Phone 1-800-909-1964

If we have questions, we will call you. Our engineering drawing will be faxed to you for approval and purchase order.

Prior to sling or lifting device selection and use, review and understand the “Help” section pages 3 through 12.

LiftAll
PRODUCTS FOR BETTER LIFTING



SPREADER BEAM



LOW HEADROOM LIFTING BEAM

Required information:

Opening required for Overhead Hook:

A (Height) _____
B (Width) _____
C (Max.) _____
Capacity Required _____
Spread _____
Headroom _____
D (Optional) _____

If adjustable beam required, list quantity and spread for any additional pairs of holes, pins and hooks.

_____
_____
_____
_____
_____

Quotation Needed By: _____
Date

Date _____ From _____
Person Requesting Quote

Distributor _____

Address _____

City _____ State _____ Zip _____

Phone ( )_____ Fax ( ) _____

Lift-All Dwg. No. _____ Customer Dwg. No. _____

User Company _____
User Contact - Name - Phone

Purchase Order No. _____

_____ _____
Signature Date

NOTE: Custom Engineered Products Cannot Be Returned

LiftAll
PRODUCTS FOR BETTER LIFTING

ALLOY S-HOOK





ALLOY J-HOOK







Required information:

S-Hook

Material Diameter _____

Rated Capacity _____

Chain Size: _____

A _____ B _____

C _____ D _____

R (Radius) _____

J-Hook

Style: Circle One A B C

Tip: Flat-Tapered _____

Rated Capacity _____

Chain Size: _____

A _____ B _____

C _____ D _____

E _____ F _____

R (Tip Radius) ____ _____

Special Instructions:

_____

_____

Quotation Needed By: _____
Date

Date _____ From _____
Person Requesting Quote

Distributor _____

Address _____

City _____ State _____ Zip _____

Phone ( )_____ Fax ( ) _____

Lift-All Dwg. No. _____ Customer Dwg. No. _____

User Company _____
User Contact - Name - Phone

Purchase Order No. _____

_____ _____
Signature Date

PL-1

NOTE: Custom Engineered Products Cannot Be Returned

STANDARD J-HOOKS

Alloy steel hooks, welded, heat treated, shot blast finish, proof tested and certified.

Foundry Sorting Hooks

Best for foundry and industrial general sorting operations.



Standard

Part No.	A	B	C	D	E	Chain Size Eye Fits Mech. Coupler	Rated Capacity * (lbs.)
FSA050	0.50	6.00	0.75	2.50	2.00	0.28	500
FSA063	0.63	8.50	0.75	3.50	3.25	0.28	800
FSA075	0.75	8.50	0.75	3.50	3.25	0.28	1300
FSA081	0.81	8.50	0.88	3.50	3.25	0.38	1600
FSA100	1.00	8.50	1.00	4.00	3.75	0.38	2500
FSA113	1.13	8.50	1.00	4.00	4.00	0.38	3500
FSA125	1.25	8.50	1.25	4.00	4.00	0.50	4500
FSA150	1.50	8.50	1.25	5.00	4.00	0.50	6000

Short

Part No.	A	B	C	D	E	Chain Size Eye Fits Mech. Coupler	Rated Capacity * (lbs.)
FSA050S	0.50	6.00	0.75	3.00	3.00	0.28	450
FSA063S	0.63	6.00	0.75	3.00	3.00	0.28	900
FSA075S	0.75	6.00	0.75	3.00	3.00	0.28	1400
FSA081S	0.81	6.00	0.88	3.00	3.00	0.38	2000
FSA100S	1.00	6.00	1.00	3.00	3.00	0.38	3000
FSA113S	1.13	6.00	1.00	3.00	3.00	0.38	4000
FSA125S	1.25	6.00	1.25	3.00	3.00	0.50	5500

STYLE B



STYLE A STYLE C



Flat Tip Hooks

Part No.	Part No.	Part No.	A	B	C	D	E	Rated Capacity * (lbs.)
JAA031	JBA031	JCA031	0.31	5.00	0.75	1.25	0.88	250
JAA038	JBA038	JCA038	0.38	6.00	0.75	1.50	1.13	350
JAA050	JBA050	JCA050	0.50	8.00	0.75	2.00	1.50	650
JAA063	JBA063	JCA063	0.63	9.00	1.00	2.50	1.88	850
JAA075	JBA075	JCA075	0.75	10.00	1.00	3.00	2.25	1200
JAA088	JBA088	JCA088	0.88	12.00	1.00	3.50	2.63	1500
JAA100	JBA100	JCA100	1.00	14.00	1.25	4.00	3.00	2000
JAA113	JBA113	JCA113	1.13	15.00	1.25	4.50	3.37	2250
JAA125	JBA125	JCA125	1.25	16.00	1.50	5.00	3.75	2750
JAA138	JBA138	JCA138	1.38	17.00	1.50	5.50	4.13	3000
JAA150	JBA150	JCA150	1.50	18.00	2.00	6.00	4.50	3500
JAA175	JBA175	JCA175	1.75	20.00	2.50	7.00	5.25	4000
JAA200	JBA200	JCA200	2.00	24.00	3.00	8.00	6.00	5000

* Rated Capacity based on bearing to bearing pull. Tip load capacity averages 30% of bearing to bearing rating.

LiftAll
PRODUCTS FOR BETTER LIFTING

STANDARD COIL LIFTER



STANDARD PALLET LIFTER



Required information:

Style Requested: ☐ Coil Lifter ☐ Pallet Lifter

Capacity _____

Minimum Coil I.D. _____

Size of Overhead Hook (Cap.) _____

A _____

B _____

C (Minimum) _____

D (Minimum) _____

E _____

F (Optional) _____

G _____

H (Optional) _____

R (Optional)

Back Stop Pad Yes ☐ No ☐

Special Instructions:

Quotation Needed By: _____
Date

Date _____ From _____
Person Requesting Quote

Distributor _____

Address _____

City _____ State _____ Zip _____

Phone ( ) _____ Fax ( ) _____

Lift-All Dwg. No. _____ Customer Dwg. No. _____

User Company _____
User Contact - Name - Phone

Purchase Order No. _____

_____ _____
Signature Date

PL-1

NOTE: Custom Engineered Products Cannot Be Returned

Tow-All VEHICLE STRAP

Vehicle Recovery Strap

Aids in removing vehicles stuck in snow, mud, sand and ditches.

Tow-All Vehicle Recovery Straps are made from strong durable *Tuff-Edge II* webbing with sewn eyes, lined with premium abrasion resistant webbing, on each end. The webbing is weather resistant and will not rot or mildew. It attaches quickly to vehicle frames or towing hooks.

Tow-Alls have a limited stretch. The elastic effect absorbs shock and aids in the recovery of disabled vehicles.



How to Order

Specify quantity and Part Number

Part No.	Ply	Web Width	Assembly Breaking Strength* (lbs.)	Rated Capacity (lbs.)
TS1802T	1	2	16,000	5,300
TS2802T	2	2	32,000	10,700
TS1803T	1	3	24,000	8,000
TS2803T	2	3	43,000	14,300
TS1804T	1	4	32,000	10,600
TS2804T	2	4	57,500	19,100
TS1806T	1	6	48,000	16,000
TS2806T	2	6	81,500	27,100

* Assembly breaking strength when new.

Tow-All Features, Advantages and Benefits

Promotes Safety

- Safer than chains or wire rope
- No dangerous hooks or metal parts

Saves Money

- Shock absorbing to reduce chance of vehicle damage

Saves Time

- Light weight and flexible for easy use and storage

Inspection Criteria for *Tow-All*

Remove from service if any of the following are visible:

- Signs of melting, charring or chemical damage
- Cuts on the face or edge of webbing
- Holes, tears, snags or crushed web
- Signs of excessive abrasive wear
- Broken or worn threads in the stitch patterns
- Any other visible damage which causes doubt as to its strength

Refer to photographs of damaged webbing on pages 16 & 17.

Safe Operating Practices

⚠ WARNING Read Definitions on page 3

- Do not use a damaged or defective strap - inspect before each use
- Do not exceed Rated Capacity
- Do not tie knots in strap
- Do not attach to bumpers
- Avoid dragging strap on ground
- Strap is permanently damaged when exposed to temperatures in excess of 200°F. Avoid muffler and hot exhaust systems.
- Stand clear of strap and vehicles when under load
- Avoid sharp edges, use padding where necessary
- Store in cool, dry and dark location

Note: Lift-All believes tow straps with metal end fittings are dangerous and, therefore, will not put metal hardware on TowAll straps.

CM MANUAL CHAIN HOISTS

All CM Hoists come with hardened alloy load chain and fully enclosed brake and housing for long life. Swivel hooks make connection and turning of load easy.



CYCLONE

Cyclone hoists are the premium grade manual chain hoists. Built for heavy duty use, these hoists are most often placed for permanent installation using the standard hook or mounting directly to a low headroom, plain or geared trolley.

- Cast aluminum body for strength
- Load Limiter - prevents hoist damage from excessive loads.
- Lifetime warranty against defects in workmanship and materials.
- Made in U.S.A.



SERIES 622

The Series 622 hoists are the economical choice in a quality manual chain hoist. Contractors favor the 622 because of its light weight and compact design.

- Stamped steel body for light-weight strength.
- Compact design for low head-room.
- One year warranty against defects in workmanship and materials.

Part No.	Std. Lengths (ft.)	Max. Cap. (tons)	Strands of Load Chain	Hand Chain		A (in.)	B (in.)	C (in.)	T (in.)	10 Ft. Net Wt. (lbs.)
				Pull (lbs.)[1]	Overhaul (ft.)[2]					
Cyclone										
14CH	10	1/4	1	23	22 1/2	12 7/8	10 7/8	7 3/8	1 11/32	40
12CH	10	1/2	1	46	22 1/2	12 7/8	10 7/8	7 3/8	1 11/32	40
1CH	10	1	1	69	30	14	10 7/8	7 3/8	1 1/8	43
112CH	10	1 1/2	1	80	40 1/2	17 5/16	10 7/8	9 7/8	1 5/16	70
2CH	10	2	1	83	52	17 5/16	10 7/8	9 7/8	1 5/16	70
3CH	10	3	2	85	81	21 1/2	12 1/4	9 7/8	1 5/8	103
4CH	10	4	2	88	104	21 1/2	12 1/4	9 7/8	1 5/8	103
5CH	10	5	3	75	156	24 1/2	14 1/2	9 7/8	1 5/8	138
6CH	10	6	3	90	156	25 1/2	14 1/2	9 7/8	1 3/4	142
8CH	10	8	4	89	208	35 1/2	17 1/2	9 7/8	2 5/16	248
10CH	10	10	5	95	260	35 1/2	17 1/2	9 7/8	2 5/16	251
Series 622										8 Ft. Wt.
12CHI	8,12,15,20	1/2	1	45	32	10	4 11/16	4 3/16	3/4	15
1CHI	8,12,15,20	1	1	74	39	12	5 19/32	5 3/16	7/8	22
2CHI	8,12,15,20	2	1	70	77	17	8 5/16	6 19/32	1 1/16	53
3CHI	8,12,20	3	2	54	154	22	8 5/16	6 19/32	1 1/4	69
5CHI	8,12,20	5	2	88	154	24	8 5/16	6 19/32	1 11/16	74
10CHI	8	10	4	90	308	32	14 13/16	6 19/32	2 3/16	139

[1] Pull required to lift rated load.
[2] Overhaul distance to lift load one foot.

CM LEVER PULLERS

Lever Pullers are highly versatile tools that can be used to pull, lift, drag or stretch. All CM Lever Pullers use hardened alloy steel chain for long life and forged steel swivel hooks with latches for safety and ease of use.



CM PULLER

Designed for heavy-duty construction and industrial applications. Fully enclosed lift wheel resists dirt and grit that can damage mechanism.

- Tough Aluminum alloy construction.
- Lifetime warranty against defects in workmanship and materials.
- Weatherproof
- Made in U.S.A.
- Low turning ratio results in quick chain movement

SERIES 653

Designed for close quarter, standard duty commercial applications. Short handle with low pull requirement makes these units easy to operate.

- Impact resistant, stamped steel frame, gear case and cover for durability and light weight.
- Hardened steel, redundant load sharing gears.
- Double pawl arrangement for optimum load control.
- Two chain guide rollers for precise chain fit.
- 5 year warranty.
- Rubber handle grip for added operator comfort.
- Minimal maintenance with no special tools required.

OPTIONAL OVERLOAD DEVICES FOR THE CM PULLERS

Two ways to protect your loads and lever pullers from overload damage are available as optional accessories to your CM PULLERS. Either device may be installed on your PULLER at time of order or ordered separately as a kit for simple installation on models already in use.

Part No.	Std. Lengths (ft.)	Max. Cap. (tons)	Lever Pull (lbs.)	Min. Hook Distance (in.)	Lever Length (in.)	Hook Throat Opening (in.)	5 Ft. Net Wt (lbs.)
CM Puller							
34P	5, 10, 20	3/4	58	10 3/4	21 1/4	1 1/32	16
112P	5, 10, 20	1 1/2	89	14 1/4	21 1/4	1 1/8	26
3P	5, 10, 20	3	95	17	21 1/4	1 7/32	38
6P	5	6	96	21 3/8	21 1/4	1 3/4	73
Series 653							
34PI	5, 10, 15, 20	3/4	33	12 6/8	11	1 1/8	15
112PI	5, 10, 15, 20	1 1/2	51	14 13/16	16 1/4	1 1/4	27
3PI	5, 10	3	77	18 11/16	16 1/4	1 9/16	45

LOAD LIMITER

(Not available on Series 653)

Stops excessive lever force from being transmitted to the PULLER.

LOAD SENTRY

(Not available on Series 653)

Deflection of the handle grip warns the user when excessive force is being applied to the lever handle.

CM MINI-RATCHET LEVER HOISTS

Mini-Ratchet Lever Hoists can lift up to 1,100 lbs. but are small enough to fit in your toolbox! These ratchet lever hoists are the most compact on the market. They perform just like our larger models, plus come with these great features:

602MH

550 LB. Capacity

603MH

1100 LB. Capacity

Designed for close quarter, standard duty commercial applications. Short handle with low pull requirement makes these units easy to operate.

- Plated load chain
- Weston style load brake
- Rubber hand grip for better comfort and control
- Lightweight design for easy transport and one-hand operation in confined space
- Forged hooks with latches are standard
- Impact resistant, all-steel frame, gear case and cover
- Hardened link-type alloy steel load chain for strength and long wear
- Free wheeling feature serves to quickly attach the load
- Your choice of either 5 ft. or 10 ft. lifts

Part No.	Length (ft.)	Capacity lbs.	Capacity kg.	Number of Chain Falls	Handle Length (in.)	Min. Distance Between Hooks (in.)	Lift w/ One Full Lever Turn (in.)	Handle Pull @ WLL (lbs.)	Net Wt. (lbs.)
602MH5	5	550	250	1	6.300	9.450	3.15	56	6.0
602MH10	10	550	250	1	6.300	9.450	3.15	56	7.0
603MH5	5	1100	500	1	6.375	11.125	1.57	78	7.0
603MH10	10	1100	500	1	6.375	11.125	1.57	78	8.0

LODELOK WEB HOOKS

This hook can be used on both Web Slings and Tuflex Roundslings

- Engineered load bearing surfaces reduce bearing pressures
- Forged, positive interlocking nose latch fully engages tip of hook
- Locking mechanism designed for ease of use with gloved hand
- High cycling, long life spring
- Modified I-Beam construction for greater strength
- Forged alloy steel, quenched and tempered
- Every hook proof tested to 2 times its Working Load Limit
- Engineered flat in hook's eye improves performance with web slings
- No catch points to snag lines
- Finish coat electrostatically applied and heat cured

Lodelok Hook Part No.	932WLHCM	38WLHCM	12WLHCM	58WLHCM
Working Load Limit @ 5:1	3,440	7,040	12,000	18,080
Tuflex	EN30	EN60	EN120	EN180
Web Slings (Eye & Eye), 1 Ply	EE1802	EE1804	EE1806	EE1810
Web Slings (Eye & Eye), 2 Ply	EE2801	EE2802	EE2804	EE2806
Web Slings (Endless), 1 Ply	EN1801	EN1802	EN1804	EN1806
Web Slings (Endless), 2 Ply	-	EN2801	EN2802	EN2803

Note: Slings shown represent the maximum size to be used with each hook.

Dimensions (In.)

Part No.	A	B	C	D	E	F Min.	H	J	Approx. Wt. Ea. (Lbs.)
932WLHCM	2.00	1.31	5.81	.88	3.77	1.64	0.63	.91	2.5
38WLHCM	2.50	1.78	7.37	1.07	4.76	2.27	0.75	1.14	4.6
12WLHCM	3.44	2.38	10.02	1.58	6.26	2.91	1.00	1.46	10.0
58WLHCM	3.94	2.62	11.31	1.97	7.37	3.20	1.25	1.81	16.0



⚠ WARNING

TO AVOID INJURY: Replace hook if nicked, gouged, cracked or hook exhibits any deformation. Inspect tip and throat for misalignment or deformation. Never apply shock loads. Do not side load or tip load. Do not exceed working load limit. Do not apply load to latch. Apply load slowly.

WEAR PADS

The Importance of Wear Pads

The number one cause of synthetic sling failure is cutting. When slings are cut, property damage and personal injury or death can result. Wear pads can help to reduce this problem by acting as a buffer between the load edge and the sling.

Used with steel slings, wear pads help protect both sling and load from damage along points of contact.



A - Tubular Quick Sleeve using Pukka Pad Material
B - Flat Quick Sleeve using Pukka Pad Material
C - Flat sewn sleeve using Webmaster 1600
D - Sewn-On Wear Pad using PVC
E - Edgeguard

Features, Advantages and Benefits

Promotes Safety

- Helps prevent sling cutting that can cause property damage, personal injury or death.

Saves Money

- Protects both sling and load from damage
- Increases sling life

Inspection Criteria of Wear Pads

If pad is damaged, the sling may also be damaged. Inspect both thoroughly and check slings for:

Web Slings

- Visible red core warning yarns
- Cuts on the face or edge of webbing
- Holes, tears, snags or crushed web
- Signs of excessive abrasive wear
- Broken or worn threads in the stitch patterns

Wire Rope Slings

- Broken wires
- Kinking
- Abrasive wear

Chain Slings

- Abrasive wear, nicks, bends, cracks, gouges or stretch

Tuflex Slings

- Holes in cover that expose red striped white core yarn

Safe Operating Practices

The sliding of slings along a load edge is a major cause of cutting. Loads must be rigged to prevent this.

Lift-All recommends that, prior to making a lift, the load be raised slightly, then lowered so that the wear pads can be inspected for damage. If pads show evidence of cutting, the lift should be tested again using different pad material. Contact *Lift-All* for pad alternatives.

⚠ WARNING

Wear pads may not prevent cutting or other sling damage. To avoid severe personal injury or death, keep all personnel clear of loads about to be lifted and suspended loads.

WEAR PAD STYLES

SLEEVE TYPE Preferred for slin Sleeve allows sling to adjust to lift without movememt against load edge.		
Flat Quick Sleeve	Use with: All Slings Available materials: All (except PVC)	*Velcro** allows easy installation and removal. Friction keeps sleeve in place when rigging.
Tubular Quick Sleeve	Use with: *Tuflex* Roundslings Chain and Wire Rope Slings Available materials: All (except PVC)	High strength *Velcro** for secure positioning, tubular design gives maximum useable surface and maximum pad life.
Flat Sewn Sleeve	Use with: All Slings Available mateirals: All (except PVC)	Preferred for long term use on single sling. May be repositioned as needed along sling length. May require factiory installation on slings with hardware and on single leg *Tuflex*.
Poly Pads	Use with: Web Roundslings (Limited range of sizes) Available materials: PVC	Slides easily along sling length for convenient sling protection. Must be installed at factory for web slings with hardware.
SEWN-ON TYPE For use on web slings where repetitive lifting situations subject known areas of the sling to cutting and/or abrasion. Eliminates the need to position pad before each lift.		
Sewn-On Wear Pad	Use with: Web Slings Only Available materials: All	For sling protection at expected wear points. Can be sewn anywhere on the sling, be any length and be on one or both sides.
Edgeguard	Use with: Web Slings Only Available materials: Texturized webbing or light duty leather	Helps protect edges of sling. Both edges will be covered to the length and position required.

WEAR PAD MATERIALS



Pukka-Pads (P) 5/16" Thick

- A high density, synthetic felt. Our best material.



***Webmaster* 1600 (N) 3/16" Thick**

- Heavy nylon sling webbing with red core warning yarns.

Heavy Leather (HL) 5/32" Thick

- Genuine top-grain cowhide (may require multiple pieces for longer lengths.)



PVC Belting (PVC) 1/8" Thick

- Non-absorbent conveyor type belting.

Texturized Webbing (TN) 3/32" Thick

- A bulked nylon fiber is used to produce a thin webbing that has good abrasion and cut resistance.

Ballistic Nylon (BN) 1/16" Thick

- A thin, 2-ply wear resistant fabric made of bulked nylon fiber, appropriate for wider sleeves and bundling applications.

* Velcro ® is a registered trademark of Velcro Industries B.V.

WEAR PADS

Flat Quick Sleeves

Flat Quick Sleeve Widths and Appropriate Slings [1]

Part No.	Sleeve Width[2] (in.)	Web Sling Width[3] (in.)	*Tuflex*				Wire Rope Sling Dia. (in.)	Chain Sling Size (in.)
			Single Leg	Double Leg	6-Part Braid	8-Part Braid		
3FQS	3	1					1/4 - 7/16	
4FQS	4	2	EN30/60	EE30			1/2 - 3/4	7/32 - 9/32
5FQS	5	3	EN90/120/150	EE60			7/8 - 1 1/8	3/8
6FQS	6	4	EN180	EE90/120	B6E30		1 1/4 - 1 1/2	1/2
8FQS	8	6	EN240/360	EE150/180/240	B6E60	B8E30	1 5/8 - 2 1/4	5/8
10FQS	10	8	EN600/800	EE360	B6E90/120	B8E60/90	2 1/2	3/4 - 7/8
12FQS	12	10	EN1000	EE600	B6E150/180	B8E120/150		1

Note: 1. Slings shown are the maximum recommended size for each sleeve width.
2. Width of sleeve depends on the material being used. This chart is based on using Pukka Pad material.
3. One or two ply only. For three or four ply, go to the next larger sleeve.

Sewn-On Wear Pads (Code WP)

PVC

Edgeguard (Code EG)

Texturized Web

Tubular Quick Sleeves

Tubular Quick Sleeve Widths and Appropriate Slings [1]

Part No.	Open Sleeve Width (A) (in.)	*Tuflex*				Wire Rope Sling Dia. (in.)	Chain Sling Size (in.)
		Single Leg	Double Leg	6-Part Braid	8-Part Braid		
4TQS	4					1/4	
5TQS	5					5/16 - 1/2	
6TQS	6	EN30//60				9/16 - 7/8	7/32
8TQS	8	EN90/120/150	EE30/60			1 - 1 1/2	9/32 - 3/8
10TQS	10	EN180/240	EE90/120	B6E30/60	B8E30	1 3/4 - 2	1/2 - 5/8
12TQS	12	EN360	EE150/180	B6E90	B8E60	2 1/4 - 2 1/2	3/4
14TQS	14	EN600/800	EE240		B8E90		7/8 - 1
16TQS	16	EN1000	EE360	B6E120/150	B8E120		1 1/4
18TQS	18		EE600	B6E180/240	B8E150/180		
20TQS	20		EE800				
22TQS	22		EE1000	B6E360	B8E240		
24TQS	24						
26TQS	26			B6E600	B8E360		
30TQS	30			B6E800	B8E600		
34TQS	34			B6E1000	B8E800		



Note: 1. Slings shown are the maximum recommended size for each sleeve width.
2. Tubular Pukka Pads not available under 12" open sleeve width.

WEAR PADS

Standard Sewn-Sleeves

Sewn-Sleeve Widths and Appropriate Sling [1]

Part No.	Sleeve Width[2] (in.)	Web Sling Width[3] (in.)	*Tuflex*				Wire Rope Sling Dia (in.)	Chain Sling Size (in.)
			Single Leg	Double Leg	6-Part Braid	8-Part Braid		
3SS	3	1	EN30/60				1/4 - 3/4	7/32
4SS	4	2	EN90/150	EE30/60			7/8 - 1 1/8	9/32 - 3/8
5SS	5	3	EN180/240	EE90/120	B6E30		1 1/4 - 1 1/2	1/2
6SS	6	4	EN360	EE150/180	B6E60	B8E30	1 5/8 - 1 3/4	5/8
8SS	8	6	EN600/800	EE240/360	B6E90/120	B8E60	2 - 2 1/2	3/4 - 7/8
10SS	10	8	EN1000	EE600	B6E150/180	B8E90/120/150		1
12SS	12	10		EE800/1000	B6E240	B8E180		1 1/4

Note: 1. Slings shown are the maximum recommended size for each sleeve width.
2. Width of sleeve depends on the material being used. This chart is based on using Pukka Pad material.
3. One or two ply only. For three or four ply, go to the next larger sleeve.

Poly Pads

Ea
slings and tiedowns. Poly Pads are designed to give protection when lifting or securing sharp or abrasive loads.

Part No.	Poly Pad	Web Width (in.)
60115	3 1/2 x 12	1 - 2
60116	6 x 12	3 - 4

How To Order

1. Choose code for width and style
   - TQS Tubular Quick Sleeve
   - FQS Flat Quick Sleeve
   - SS Flat Sewn Sleeve
   - WP Sewn-On Wear Pad
   - EG Edgeguard
   - _____ Poly Pad (Use Part No.)

2. Choose a Material
   - P 5/16" Heavy Duty Pukka-Pad
   - N *Webmaster* 1600 Nylon
   - HL Heavy Leather
   - TN Texturized Webbing
   - BN Ballistic Nylon (Tubular only)
   - PVC (Sewn-on Wear Pads only)

3. Length of Sleeve
   (if sewn-on pad, describe position on sling)
   _____ Feet

4. For Use On
   - ____ Web Sling - Code or Width
   - ____ *Tuflex* ____ Single-Leg - Code _____
   - ____ Double-Leg - Code _____



- ____ Chain Sling Size _____ inches
- ____ Wire Rope Sling - Dia. _____ inches

⚠ WARNING

Wear pads may not prevent cutting or other sling damage. To avoid severe personal injury or death, keep all personnel clear of loads about to be lifted and suspended loads.

HOIST RINGS

Hoist Rings Make Lifting Easy

Hoist rings provide the safest method of attaching pickup points to loads. Eye bolts, when lifted at an angle, tend to deform and fracture. Hoist rings are designed to eliminate this weakness.

Features, Advantages and Benefits

Promotes Safety

- Magnetic particle or X-ray inspection of components - assures highest quality
- Predetermines proper hook-up - discourages unauthorized rigging methods
- Designed for lifting at angles - safer than rigid eye bolts
- Fixed lift points prevent load and sling from slipping
- Every hoist ring stamped with rated capacity

Saves Money

- Hooks and slings are not in contact with load - reduces load and sling damage
- Alloy steel material - increases strength, reduces wear
- Black oxide finish - resists corrosion
- Highest industry quality for durability and longest life

Saves Time

- Easy hook-up and disconnect of load
- Full swivel and pivot action of Side-Pull Hoist Rings allows turning and flipping without unhooking
- Easy to Inspect

How To Order

Specify stock number.

Safe Operating Practices

Read and understand instruction sheet supplied with each hoist ring prior to use.

- Do not use a damaged or defective hoist ring - inspect before each use
- Do not overload
- Full thread length must be engaged and torqued according to tables-periodic retorquing may be required.

Hoist ring ratings apply to use at any angle. Be sure that sling tension does not exceed the rating of the hoist ring. Refer to “Effect of Angle of Lift”, page 10, to determine sling tension.



Eye Bolt - Weak, inflexible, deforms when loaded at angle



Side - Pull Hoist Ring

Strong, flexible, allows full 360° swiveling and pivoting.

Center - Pull Hoist Ring

Designed for top of load mounting. The industry standard.

HOIST RINGS

Center - Pull Hoist Rings

The industry standard hoist ring. Designed specifically for top of load mounting. Popular size hoist rings (1/2 - 13 through 1 - 8) are offered with two or more bolt lengths. Use longer length with softer parent materials, the shorter with hard materials such as steel.

Proof tested to 200% of Rated Load Capacity.



Center-Pull Hoist Rings (Dimensions in inches) — Bolt Kits ***

Thread Size A	Rated Capacity* (lbs.)	STD. Clevis		Long Clevis		Thread Length C	D	Radius E	Dia. F	G	H	Torque** (ft. lbs.)	Weight (lbs.)	Part No.	Weight (lbs.)
		Part No.	B	Part No.	B										
5/16-18	800	09439	2 21/32			9/16	3/4	7/16	3/8	1 27/32	1 1/4	7	.3	09448	.03
3/8-16	1,000	09387	2 21/32			9/16	3/4	7/16	3/8	1 27/32	1 1/4	12	.3	09449	.05
1/2-13	2,500	09440	3 3/4			1 1/16	1 3/16	11/16	1/2	2 9/16	2 3/8	28	1.0	09450	.16
1/2-13	2,500	09441	4 25/32	09506	6 23/32	3/4	1 1/2	7/8	3/4	3 1/2	2 3/8	28	2.5	09451	.14
1/2-13	2,500	09388	4 25/32	09507	6 23/32	1	1 1/2	7/8	3/4	3 1/2	2 3/8	28	2.5	09452	.16
1/2-13	2,500	09442	4 25/32	09508	6 23/32	1 1/4	1 1/2	7/8	3/4	3 1/2	2 3/8	28	2.5	09453	.17
5/8-11	4,000	09443	4 25/32	09509	6 23/32	1	1 1/2	7/8	3/4	3 1/2	2 1/4	60	2.7	09454	.27
5/8-11	4,000	09389	4 25/32	09510	6 23/32	1 1/4	1 1/2	7/8	3/4	3 1/2	2 1/4	60	2.7	09455	.29
3/4-10	5,000	09390	4 25/32	09511	6 23/32	1	1 1/2	7/8	3/4	3 1/2	2 1/8	100	3.0	09456	.40
3/4-10	5,000	09391	4 25/32	09512	6 23/32	1 1/2	1 1/2	7/8	3/4	3 1/2	2 1/8	100	3.0	09457	.46
3/4-10	7,000	09392	6 1/2	09513	8 23/32	1	2 5/16	1 13/32	1	5 1/8	2 15/16	100	7.0	09458	.46
3/4-10	7,000	09444	6 1/2	09514	8 23/32	1 1/2	2 5/16	1 13/32	1	5 1/8	2 15/16	100	7.0	09459	.52
7/8-9	8,000	09445	6 1/2	09515	8 23/32	1	2 5/16	1 13/32	1	5 1/8	2 13/16	160	7.0	09460	.62
7/8-9	8,000	09393	6 1/2	09516	8 23/32	1 1/4	2 5/16	1 13/32	1	5 1/8	2 13/16	160	7.0	09461	.66
1-8	10,000	09394	6 1/2	09517	8 23/32	1 1/4	2 5/16	1 13/32	1	5 1/8	2 11/16	230	7.5	09462	.92
1-8	10,000	09395	6 1/2	09518	8 23/32	1 1/2	2 5/16	1 13/32	1	5 1/8	2 11/16	230	7.5	09463	.97
1-8	10,000	09446	6 1/2	09519	8 23/32	2 1/4	2 5/16	1 13/32	1	5 1/8	2 11/16	230	7.5	09464	1.1
1 1/4-7	15,000	09396	8 23/32			1 7/8	3 3/16	1 3/4	1 1/4	6 1/2	4 3/16	470	14	09465	2.9
1 1/2-6	24,000	09397	12 15/32			2 3/4	4 3/16	2 1/4	1 3/4	8 1/2	6 5/16	800	33	09466	3.5
2-4 1/2	30,000	09447	12 15/32			3 1/8	4 3/16	2 1/4	1 3/4	8 1/2	5 13/16	1100	36	09467	7.3

Metric Center-Pull Hoist Rings (Dimensions in millimeters) — Bolt Kits ***

Thread Size A	Rated Capacity* (kgs.)	STD. Clevis		Long Clevis		Thread Length C	D	Radius E	Dia. F	G	H Std. Clevis	Torque** (kg.m.)	Weight (kgs.)	Part No.	Weight (kgs.)
		Part No.	B	Part No.	B										
M8 x 1.25	400	09482	67.8			12.5	19.0	10.9	9.7	46.7	32	1.0	.17	09489	.02
M10 x 1.50	450	09483	67.8			17.5	19.0	10.9	9.7	46.7	30	1.7	.17	09490	.03
M12 x 1.75	1,050	09403	121.4	09520	170.7	19.0	38.1	22.4	19.0	89.4	60.5	3.8	1.08	09491	.06
M16 x 2.0	1,900	09404	121.4	09521	170.7	29.0	38.1	22.4	19.0	89.4	56.5	8.2	1.12	09492	.12
M20 x 2.5	2,150	09484	121.4	09522	170.7	34.0	38.1	22.4	19.0	89.4	52.5	13.6	1.19	09493	.21
M20 x 2.5	3,000	09405	165.6	09523	206.0	32.0	58.7	35.6	25.4	130.6	73	13.6	3.03	09494	.23
M24 x 3.0	4,200	09406	165.6	09524	206.0	37.0	58.7	35.6	25.4	130.6	69	31.0	3.10	09495	.40
M30 x 3.5	7,000	09407	221.7			41.9	81.0	44.5	31.7	165.1	107.4	60.0	6.3	09496	.79
M30 x 3.5	7,000	09485	221.7			61.7	81.0	44.5	31.7	165.1	107.4	60.0	6.4	09497	.91
M36 x 4.0	11,000	09486	316.7			63.5	106.4	57.2	44.4	217.2	166.5	100.0	15.5	09498	1.52
M42 x 4.5	12,500	09487	316.7			68.0	106.4	57.2	44.4	217.2	160.5	100.0	16.0	09499	2.75
M48 x 5.0	13,500	09488	316.7			82.4	106.4	57.2	44.4	217.2	154.5	100.0	16.8	09500	3.27
M64 x 6.0	22,500	09655	419.1			101.6	146.0	76.2	57.2	297.6	210	290.0	40.0	09656	15.70

⚠ WARNING Do not exceed rated capacities. Be sure that sling tension does not exceed hoist ring capacity. Follow instructions on page 10.

** Stated load capacity based on specific thread torques as shown in chart.

*** Bolt kit contains bolt and retaining ring.

HOIST RINGS

Side - Pull Hoist Rings

This most versatile style of hoist ring is particularly suited for turning and flipping loads, but works equally well for top lifts. Used extensively in automotive stamping plants and injection molding operations for die changing.

- Full swivel & Pivot Action
- Alloy Steel, Black Oxide Finish
- Proof Tested to 200% of Rated Load Capacity



U.S. Patent #409,895

Side-Pull Hoist Rings (Dimensions in inches)

Part No.	Load Capacity (lbs.)	Thread Size A	B	C	D	E	F	G	H	I	J	K	L	M	Torque** (ft.lbs.)	Hex Size	Weight (lbs.)
10253	650	5/16 - 18	1 9/32	15/32	13/16	1/8	9/16	5/16	1	1	1 1/4	1 3/4	3	3/4	4	-	.5
10254	800	3/8 - 16	1 9/32	5/8	13/16	1/8	9/16	5/16	1	1	1 1/4	1 3/4	3	3/4	5	-	.5
10255	1,800	1/2 - 13	1 7/8	3/4	1 3/8	5/32	13/16	1/2	1 3/4	1 1/2	2 3/8	2	4 5/16	1 1/4	15	1/4	2
10256	2,500	5/8 - 11	1 7/8	15/16	1 3/8	5/32	13/16	1/2	1 3/4	1 1/2	2 3/8	2	4 5/16	1 1/4	25	5/16	2
10257	4,100	3/4 - 10	2 5/16	1 1/8	1 7/8	1/4	1 1/32	5/8	2 1/4	2	2 1/4	2 5/8	5 11/16	1 3/4	50	3/8	4
10258	7,100	1 - 8	2 5/16	1 1/2	1 7/8	1/4	1 1/32	5/8	2 1/4	2	2 1/4	2 5/8	5 11/16	1 3/4	130	1/2	4.5
10259	14,000	1 1/4 - 7	4 9/16	1 7/8	3 1/4	23/64	1 21/32	1 1/16	3 3/4	3	2 1/8	4 3/8	8 13/16	3	150	3/4	24.5
10260	17,200	1 1/2 - 6	4 9/16	2 1/4	3 1/4	23/64	1 21/32	1 1/16	3 3/4	3	2 1/8	4 3/8	8 13/16	3	250	3/4	30
10261	29,000	2 - 4 1/2	4 9/16	3	3 1/4	23/64	1 21/32	1 1/16	3 3/4	3	2 15/16	4 3/8	8 13/16	3	300	3/4	26.5

Metric Side-Pull Hoist Rings (Dimensions in millimeters)

Bushing is zinc plated silver.

Part No.	Load Capacity (kgs.)	Thread Size A	B	C	D	E	F	G	H	I	J	K	L	M	Torque** (kg.m.)	Hex Size	Weight (kgs.)
10262	325	M8 x1.25	33	16	21	3	14	8	25	25	52	44	76	19	.51	-	.25
10263	500	M10 x 1.5	33	20	21	3	14	8	25	25	52	44	76	19	1.1	-	.25
10264	725	M12 x 1.75	48	24	35	4	21	13	44	38	75	51	110	32	1.9	6	1
10265	1,400	M16 x 2.0	48	32	35	4	21	13	44	38	75	51	110	32	4.1	8	1
10266	2,290	M20 x 2.5	59	40	48	6	26	16	57	51	102	67	145	44	6.9	10	2
10267	3,050	M24 x 3	59	48	48	6	26	16	57	51	102	67	145	44	14	12	2
10268	4,850	M30 x 3.5	117	60	83	9	42	27	95	76	154	111	224	76	35	19	24.5
10269	7,500	M36 x 4	117	72	83	9	42	27	95	76	154	111	224	76	55	19	25
10270	8,700	M42 x 4.5	117	84	83	9	40	25	95	76	152	111	221	76	83	19	27.5
10271	10,000	M48 x 5	117	96	83	9	40	27	95	76	154	111	224	76	118	19	26

* **⚠ WARNING** Do not exceed rated capacities. Be sure that sling tension does not exceed hoist ring capacity. Follow Instructions on page 10.

** It is recommended that these torques be used when installing hoist rings.

Lifting Application Worksheet

Please fill in as much information as possible in order to aid in selecting the proper lifting equipment

Distributor _____
Date: _____
Contact Name:_____
Telephone: _____
Fax: _____

Description of the load being lifted

What is the load: _____
_____
Size of the load:
Weight: _____
Width: _____
Height: _____
Length: _____
Diameter: _____
Other Notes: _____
_____

Lifting Conditions

Overhead Height Clearance:_____
(From top of load)
Operating Temperature:
☐ Room ☐ Other _____ °F
Other Notes: _____
_____
If exposed to chemicals:
Chemical: _____
Conc: _____%
Temperature: ☐ Room ☐ Other _____ °F

Attach drawing of load and intended rigging configuration with dimensions.

Lifting Operation

☐ Lift and Transport ☐ Pull / Drag Load Only
☐ Lift and Turn ☐ Lift Load Only
☐ Other Notes: _____
_____

Lifting equipment being used (excluding slings)

Check the following equipment that performs the lift:
☐ A single hook/hoist/crane. Hook sizes used: ___
☐ Two hooks/hoists/cranes. Hook sizes used: ___
☐ Fork-lift. Width/thickness of the forks: _____
Distance between the inside edges of the forks:
_____ in.
Is a lifting beam to be used? ☐ Yes ☐ No
If Yes: Beam Span: _____ ft. _____ in.
Is it adjustable? ☐ Yes ☐ No
Is a new beam needed? ☐ Yes ☐ No
Other Notes: _____
_____

Rigging Configuration

Number of pick-up points: _____
Connection point information:
☐ Ring/Eye/Shackle
Size: _____ ID: ____" OD: ____" THK: ____"
☐ Wrapped around the load
☐ Trunnion/Pin Diameter: _____"
Is center of gravity an equal distance from all pick-up points? ☐ Yes ☐ No
Sling/legs attached to the load in a:
☐ Vertical Hitch ☐ Choker Hitch
☐ Basket Hitch ☐ Other _____
☐ Double Wrap Basket Hitch
☐ Double Wrap Choker Hitch
Other Notes: _____
_____

CONVERSION AND WEIGHT TABLES

Metric / English Conversions

Length

1 CM = .3937 In.
2.54 CM = 1 In.
.3048 M = 1 Ft.
1 M = 3.281 Ft.

Weight

.4536 Kg = 1 Lb.
1 Kg = 2.2046 Lbs.

Volume

.028 Cu. M = 1 Cu. Ft.
1 Cu. M = 35.314 Ft.

1 Cu. Ft. = 7.5 Gals.

Weights of Various Materials and Liquids

Pounds / cu. ft.					
Aluminum	165	Earth - Dry	75	Rubber	94
Asphalt	81	Earth - Wet	100	Sand - Dry	105
Brass	524	Gasoline	45	Sand - Wet	120
Brick	120	Glass	162	Steel	490
Bronze	534	Iron Casting	470	Water	63
Cement - Loose	95	Lead	708	Zinc	437
Cement - Set	183	Lumber - Fir	32		
Coal	56	Lumber - Oak	62		
Concrete	150	Lumber - RR Ties	50		
Crushed Rock	95	Oil, Motor	58		
Diesel	52	Paper	60		

Pounds / sq. ft.	
Steel Plate	
1/8"	5
1/4"	10
1/2"	20
1"	40
Aluminum Plate	
1/8"	1.75
1/4"	3.50
Lumber	
3/4" Fir	2
3/4" Oak	4

Pounds / gal.	
Gasoline	6.0
Diesel	7.0
Water	8.3

Decimal Equivalents

Fraction	Inches	Millimeters	Fraction	Inches	Millimeters
1/32	.0312	0.80	17/32	.5312	13.49
1/16	.0625	1.59	9/16	.5625	14.29
3/32	.0937	2.38	19/32	.5937	15.08
1/8	.125	3.18	5/8	.625	15.88
5/32	.1562	3.97	21/32	.6562	16.67
3/16	.1875	4.76	11/16	.6875	17.46
7/32	.2187	5.56	23/32	.7187	18.26
1/4	.250	6.35	3/4	.750	19.05
9/32	.2812	7.14	25/32	.7812	19.84
5/16	.3125	7.94	13/16	.8125	20.64
11/32	.3437	8.73	27/32	.8437	21.43
3/8	.375	9.53	7/8	.875	22.23
13/32	.4062	10.32	29/32	.9062	23.02
7/16	.4375	11.11	15/16	.9375	23.81
15/32	.46=87	11.91	31/32	.9687	24.61
1/2	.500	12.70	1	1.0	25.40

LiftAll®
PRODUCTS FOR BETTER LIFTING

TABLE OF CONTENTS

Lifting Beams

Economical
- Adjustable Spreader/Lifting Beam (ASLB16).....4
- Adjustable Lifting Beam (ALB17) 4
- Fixed Spread Lifting Beam (FSLB19).....5
- Basket Sling Lifting Beam (BSLB18)..... 5

Industrial
- Low Headroom Multiple Spread Lifting Beam (LHLB20).....6, 7
- Heavy Duty Twin Basket Sling Lifting Beam (HDLB22)..... 8
- Twin Hoist Lifting Beam (THLB25).....9

Spreader
- Fixed Spreader Beam (FSB30).....10
- Adjustable Spreader Beam (ASB32).....11
- Modular Spreader Beam (MSB14) 12

Coil Lifter

- Dixon Coil Hook with Pivoting Wedge (DCH80).....13
- Heavy Duty Coil Hook (HDCH82)..... 13

Construction Tools

Beam/Girder Clamps
- Beam Flange Clamp (BFC)..... 14
- Girder Clamp (GC)..... 14
- Beam Grab (F)..... 15

Pipe & Manhole Lifting
- Pipe Grab (C/S)..... 16
- Pipe Tongs (PLT)..... 17
- Concrete Manhole Lifter (MHL).....18
- Manhole Sleeve Lifter (MCL).....19
- Tea Cup Pipe Carrier (TC)..... 20
- Tea Cup Sling (TCS)..... 20
- Pipe Pick (CPP) 21
- Barrier Grab (BRG74)..... 22

Fork Lift Accessories

Booms
- Fixed Fork Lift Booms (FFLB)..... 23
- Single Fork Hook (SFH).....23
- Telescoping Fork Lift Booms (TFLB).... 24
- Double Fork Beam (DFB).....24
- Pivoting Fork Lift Booms (PFLB).....25

Specialty Products

- Fiberglass Battery Lifting Beam (BLB)..... 26
- Battery Lifting Beam, Low Headroom (BLBLHA) 27
- Adjust-A-Link 28
- Adjust-A-Leg 29

Gantry Cranes

- Fixed Steel (H90) 30, 31
- Adjustable Steel (K90) 32, 33
- Fixed Aluminum (HA90) 34
- Adjustable Aluminum (KA90) 35

PRODUCT INFORMATION

Quality Engineered Products

All of the products in this catalog have been engineered and produced to the highest quality standards and meet or exceed all applicable U.S. government standards including OSHA and ASME B30.20 and B30.9. Random proof testing is standard. Proof testing with certification is available upon request for a nominal charge.

Product Overview

Lifting Beams

Allow for multiple pick points of the load for balance or support issues. **Spreader Beams** have a top rigging that add stability to the lift. Available in 9 standard styles.

Pallet Lifters

Use overhead cranes for pallet movement where forklift trucks can't go. Available in 2 standard styles.

Coil Lifters

Use to lift, manipulate and reposition coils. Requires minimum aisle space equal to Lifter arm length. Available in 2 standard styles.

Beam/Girder Clamps

For use in lifting and positioning structural beams. Two styles may also be hung from load bearing beams to suspend hoists or other lifting devices.

Gantry Cranes

These portable cranes allow for the pick up and transport of a load wherever you have a smooth and level floor. Available in either steel or aluminum, fixed or adjustable height.

Pipe & Manhole Lifting

For the lifting and positioning of steel, iron and concrete pipe. Pipe Grabs are for metal pipes. Pipe Picks and Tea Cups for concrete pipes.

Forklift Accessories



Three styles of booms and two hook devices provide added lifting capabilities to your forklift trucks.

Barrier Grabs

Scissor style grab is the easy way to lift and move concrete road barriers. Auto-latch for hands-off operation.

Specialty Products

Battery Beams provide a non-conductive lifting method for industrial batteries. (i.e.- forklift batteries)

Adjust-A-Leg slings allow controlled lifting of loads where lift points are not equidistant from the load's center of gravity.

ECONOMICAL LIFTING BEAMS

Adjustable Spreader/Lifting Beam (ASLB16)



FEATURES
- Use for 2, 3 or 4 point lifting or as spreader beam (add top rigging)
- Adjustable lifting points
- Good for unbalanced loads
- Low headroom
- Shackles included
- 6" spread adjustments
- 4" bail adjustments
- Complies with ASME STANDARDS

OPTIONS
- Pair of swivel hooks – Code S*
- Top chain rigging – Code C



Rated Cap. (Tons)	Part No.*	Spread (Ft.)		Bail Adj. (in.)	Bolt Style Anchor Shackle (Tons)		Headroom (In.)	Weight (Lbs.)
		Max.	Min.		Top	Bottom		
1/4	ASLB.5	4	1	16	1 1/2	1 1/2	7.1	37
1/2	ASLB1	6	3	24	1 1/2	1 1/2	9.9	76
1	ASLB2	6	3	24	1 1/2	1 1/2	9.9	76
2	ASLB4	6	3	24	3 1/4	2	12.6	128
4	ASLB8	8	4	32	4 3/4	4 3/4	16.6	270
5	ASLB10	10	5	40	6 1/2	4 3/4	20.2	445
7	ASLB14	12	6	48	8 1/2	6 1/2	23.8	755

Adjustable Lifting Beam (ALB17)



FEATURES
- Adjust bail for unbalanced load
- 6" spread adjustments
- Shackles included
- Complies with ASME STANDARDS

OPTIONS
- Pair of swivel hooks – Code S*



Rated Cap. (Tons)	Part No.*	Spread (Ft.)		Bail Adj. (in.)		Bail Dimensions A●B●C●T (in.)	Headroom (In.)	Weight (Lbs.)
		Max.	Min.	Range	D			
1 1/4	ALB2.5	6	3	24	3	1.5●3●5●.63	14.7	150
2	ALB4	6	3	24	3	1.5●3●5●.63	14.7	155
4	ALB8	8	4.5	36	3	2●4●7●.75	19.8	285
5	ALB10	10	5	36	3	2●4●7●1	22.4	475

* For Optional Swivel Hooks, add an "S" to Part No. Contact Lift-All for added cost.

ECONOMICAL LIFTING BEAMS

Fixed Spread Lifting Beam (FSLB19)



Rated Cap. (Tons)	Part No.	Spread (Ft.)	Bail Dimensions A●B●C●H (in.)	Headroom (In.)	Weight (Lbs.)
1/2	FSLB1x4	4	A ● .75	13 1/4	39
	FSLB1x6	6	B ● 3.0	13 1/4	53
	FSLB1x8	8	C ● 5.0	13 1/4	64
	FSLB1x10	10	H ● .89	14 1/4	95
1	FSLB2x4	4	A ● 1.0	13 1/4	40
	FSLB2x6	6	B ● 3.0	14 1/4	75
	FSLB2x8	8	C ● 5.0	15 1/4	100
	FSLB2x10	10	H ● .89	15 1/4	117
2	FSLB4x4	4	A ● 1.0	16 3/4	45
	FSLB4x6	6	B ● 3.0	17 3/4	89
	FSLB4x8	8	C ● 5.0	19 3/4	114
	FSLB4x10	10	H ● 1.0	19 3/4	138
3	FSLB6x4	4	A ● 1.5	21	78
	FSLB6x6	6	B ● 4.0	23	138
	FSLB6x8	8	C ● 7.0	23	173
	FSLB6x10	10	H ● 1.0	23	284

FEATURES
- Fixed spread lifting
- Eye hooks with latches standard
- Sealed construction for cleaner beam
- Complies with ASME STANDARDS



Basket Sling Lifting Beam (BSLB18)



FEATURES
- Best beam for low headroom applications
- Fixed spread lifting
- Bent bar hooks allow for 2" wide sling eyes
  - One set for 3' & 4' spreads
  - Two sets for 6' – 12' spreads
- Spread 2 is ½ of Spread 1
- Complies with ASME STANDARDS





Rated Cap. (Tons)	Part No.	Spread (Ft.)	Bail Dimensions A●B●C●T (in.)	Headroom (In.)	Weight (Lbs.)
1/2	BSLB1x3	3		8 1/2	40
	BSLB1x4	4	A ● .88	8 1/2	48
	BSLB1x6	6	B ● 3.0	8 1/2	78
	BSLB1x8	8	C ● 5.0	8 1/2	95
	BSLB1x10	10	T ● .75	8 1/2	113
	BSLB1x12	12		9 1/2	171
1	BSLB2x3	3		8 1/2	40
	BSLB2x4	4	A ● .88	8 1/2	48
	BSLB2x6	6	B ● 3.0	9 1/2	93
	BSLB2x8	8	C ● 5.0	10 1/2	136
	BSLB2x10	10	T ● .75	10 1/2	175
	BSLB2x12	12		11 1/2	239
2	BSLB4x3	3		9 1/2	52
	BSLB4x4	4	A ● .88	10 1/2	75
	BSLB4x6	6	B ● 3.0	10 1/2	139
	BSLB4x8	8	C ● 5.0	11 1/2	169
	BSLB4x10	10	T ● .75	12 1/2	246
	BSLB4x12	12		13 1/2	326
5	BSLB10x3	3		13 1/2	104
	BSLB10x4	4	A ● 2.0	14 1/2	135
	BSLB10x6	6	B ● 4.0	15 1/2	211
	BSLB10x8	8	C ● 7.0	16 1/2	310
	BSLB10x10	10	T ● 1.25	17 1/2	423
	BSLB10x12	12		19 1/2	618

INDUSTRIAL LIFTING BEAMS

Low Headroom Multiple Spread Lifting Beam (LHLB20)



FEATURES

- Great for low headroom applications
- Swivel hooks with latches standard
- 3' & 4' beams have 2 spreads
- 6' & longer beams have 3 spreads (Inner spread lengths are shorter than outer spreads by 1' increments)
- Additional or repositioned holes available
- Complies with ASME STANDARDS

Rated Cap. (Tons)	Part No.	Spread (Ft.)	Bail / Hook Dimensions A●B●C●T●H (in.)	Headroom (In.)	Weight (Lbs.)
1/2	LHLB1x3	3	A ● .88 B ● 3.0 C ● 5.0 T ● .75 H ● .88	12 3/4	40
	LHLB1x4	4		12 3/4	50
	LHLB1x6	6		12 3/4	70
	LHLB1x8	8		12 3/4	95
	LHLB1x10	10		13 11/16	145
	LHLB1x12	12		13 11/16	165
	LHLB1x14	14		13 11/16	200
	LHLB1x16	16		14 11/16	265
	LHLB1x18	18		14 11/16	290
	LHLB1x20	20		14 11/16	330
1	LHLB2x3	3	A ● .88 B ● 3.0 C ● 5.0 T ● .75 H ● .88	12 3/4	40
	LHLB2x4	4		12 3/4	50
	LHLB2x6	6		13 11/16	90
	LHLB2x8	8		13 11/16	120
	LHLB2x10	10		14 11/16	170
	LHLB2x12	12		14 11/16	200
	LHLB2x14	14		15 11/16	280
	LHLB2x16	16		15 11/16	310
	LHLB2x18	18		16 11/16	405
	LHLB2x20	20		16 11/16	455
2	LHLB4x3	3	A ● .88 B ● 3.0 C ● 5.0 T ● .75 H ● .88	13 11/16	55
	LHLB4x4	4		13 11/16	70
	LHLB4x6	6		14 11/16	110
	LHLB4x8	8		15 11/16	170
	LHLB4x10	10		16 11/16	235
	LHLB4x12	12		16 11/16	265
	LHLB4x14	14		20	375
	LHLB4x16	16		20	420
	LHLB4x18	18		22	605
	LHLB4x20	20		22	680

Low Headroom Multiple Spread Lifting Beam (Continued)

Options:



Extra Holes
Allows for extra hook positions in addition to the standard holes. Specify number and spread.



FasPins
Allows for easy repositioning of hooks. Recommended for frequent hook position changes.



Extra Hooks
Allows for multiple pick points. Saves time from having to move hooks.

Rated Cap. (Tons)	Part No.	Spread (Ft.)	Bail / Hook Dimensions A●B●C●T●H (in.)	Headroom (In.)	Weight (Lbs.)
3	LHLB6x3	3		15 3/8	70
	LHLB6x4	4		15 3/8	85
	LHLB6x6	6	A ● 1.25	16 3/8	145
	LHLB6x8	8	B ● 3.0	17 1/4	205
	LHLB6x10	10	C ● 5.0	18 1/4	280
	LHLB6x12	12	T ● 1.0	20 1/8	410
	LHLB6x14	14	H ● 1.0	20 1/8	495
	LHLB6x16	16		20 1/8	560
	LHLB6x18	18		20 1/8	620
	LHLB6x20	20		22 1/8	915
5	LHLB10x3	3		19 9/16	80
	LHLB10x4	4		20 1/2	110
	LHLB10x6	6	A ● 2.0	21 1/2	210
	LHLB10x8	8	B ● 4.0	23 1/2	320
	LHLB10x10	10	C ● 7.0	23 1/2	380
	LHLB10x12	12	T ● 1.25	25 1/2	575
	LHLB10x14	14	H ● 1.94	25 1/2	690
	LHLB10x16	16		25 1/2	770
	LHLB10x18	18		30 1/2	1340
	LHLB10x20	20		30 1/2	1500
7 1/2	LHLB15x3	3	A ● 2.0	20 1/2	105
	LHLB15x4	4	B ● 4.0	23 3/8	175
	LHLB15x6	6	C ● 7.0	25 3/8	270
	LHLB15x8	8	T ● 1.25	27 1/4	420
	LHLB15x10	10	H ● 1.5	27 1/4	505
	LHLB15x12	12		27 1/4	585
10	LHLB20x3	3	A ● 2.0	23 1/2	115
	LHLB20x4	4	B ● 4.0	25 3/8	210
	LHLB20x6	6	C ● 7.0	27 1/4	340
	LHLB20x8	8	T ● 1.25	27 1/4	420
	LHLB20x10	10	H ● 1.56	30	775
	LHLB20x12	12		30	910

INDUSTRIAL LIFTING BEAMS

Heavy Duty Twin Basket Sling Lifting Beam (HDLB22)



FEATURES

- For use with slings in a basket hitch
- Latch hooks designed to minimize sling eye damage
- Two sets of fixed hooks are standard for all lengths over 4'
- Inner spread is ½ of outer spread
- Extra spreads available upon request
- Complies with ASME STANDARDS





Rated Cap. (Tons)	Part No.	Spread (Ft.)	Bail / Hook Dimensions A●B●C●T●H (in.)	Headroom (In.)	Weight (Lbs.)
1/2	HDLB1x3	3	A ● .88	8 1/2	50
	HDLB1x4	4	B ● 3.0	8 1/2	65
	HDLB1x6	6	C ● 5.0	8 1/2	110
	HDLB1x8	8	T ● .75	8 1/2	150
	HDLB1x10	10	H ● 1.06	9 1/2	200
	HDLB1x12	12		9 1/2	220
1	HDLB2x3	3	A ● .88	8 1/2	50
	HDLB2x4	4	B ● 3.0	8 1/2	65
	HDLB2x6	6	C ● 5.0	9 1/2	145
	HDLB2x8	8	T ● .75	10 1/2	210
	HDLB2x10	10	H ● 1.12	10 1/2	230
	HDLB2x12	12		11 1/2	290
2	HDLB4x3	3	A ● .88	9 1/2	70
	HDLB4x4	4	B ● 3.0	10 1/2	90
	HDLB4x6	6	C ● 5.0	10 1/2	160
	HDLB4x8	8	T ● .75	11 1/2	225
	HDLB4x10	10	H ● 1.12	12 1/2	300
	HDLB4x12	12		13 1/2	375
5	HDLB10x3	3	A ● 2.0	13 1/2	90
	HDLB10x4	4	B ● 4.0	14 1/2	160
	HDLB10x6	6	C ● 7.0	15 1/2	275
	HDLB10x8	8	T ● 1.0	16 1/2	350
	HDLB10x10	10	H ● 1.12	16 1/2	450
	HDLB10x12	12		16 1/2	500
7 1/2	HDLB15x3	3	A ● 2.0	14 1/2	155
	HDLB15x4	4	B ● 4.0	15 1/2	180
	HDLB15x6	6	C ● 7.0	16 1/2	330
	HDLB15x8	8	T ● 1.25	17 1/2	410
	HDLB15x10	10	H ● 1.75	17 1/2	500
	HDLB15x12	12		19 1/2	700
10	HDLB20x3	3	A ● 2.0	15 1/2	150
	HDLB20x4	4	B ● 4.0	16 1/2	200
	HDLB20x6	6	C ● 7.0	17 1/2	320
	HDLB20x8	8	T ● 1.25	19 1/2	500
	HDLB20x10	10	H ● 1.75	19 1/2	625
	HDLB20x12	12		19 1/2	700

INDUSTRIAL LIFTING BEAMS

Twin Hoist Lifting Beam (THLB25)



FEATURES

- For use with two hoists to increase lift capacity
- Swivel hook with latch standard

Center hook offset to accommodate hoists of unequal capacities.

Custom pick points for both top and bottom.

Center bail and extra pair of hooks for maximum versatility.

Rated Cap. (Tons)	Part No.	Spread (Ft.)	Bail / Hook Dimensions A●B●C●T●H (in.)	Headroom (In.)	Weight (Lbs.)
2	THLB4x6	6	A ● 1.5	16 3/4	125
	THLB4x8	8	B ● 3.0	16 3/4	160
	THLB4x10	10	C ● 5.0	17 3/4	240
	THLB4x12	12	T ● .63	17 3/4	280
	THLB4x14	14	H ● 1.12	18 3/4	360
	THLB4x16	16		18 3/4	400
4	THLB8x6	6	A ● 1.5	20	160
	THLB8x8	8	B ● 3.0	21	240
	THLB8x10	10	C ● 5.0	22	310
	THLB8x12	12	T ● .63	23	410
	THLB8x14	14	H ● 1.5	23	500
	THLB8x16	16		25	725
6	THLB12x6	6	A ● 1.5	27 1/2	220
	THLB12x8	8	B ● 3.0	28 1/2	300
	THLB12x10	10	C ● 5.0	28 1/2	380
	THLB12x12	12	T ● .75	30 1/2	550
	THLB12x14	14	H ● 2.06	30 1/2	640
	THLB12x16	16		30 1/2	780
10	THLB20x6	6	A ● 2.0	29	340
	THLB20x8	8	B ● 4.0	29	420
	THLB20x10	10	C ● 7.0	32	800
	THLB20x12	12	T ● 1.0	32	920
	THLB20x14	14	H ● 2.25	32	1100
	THLB20x16	16		32	1220
15	THLB30x8	8	A ● 2.0	38 1/4	740
	THLB30x10	10	B ● 4.0	38 1/4	865
	THLB30x12	12	C ● 7.0	38 1/4	1050
	THLB30x14	14	T ● 1.25	41 1/4	1930
	THLB30x16	16	H ● 2.25	41 1/4	2158
20	THLB40x8	8	A ● 2.0	35 1/2	830
	THLB40x10	10	B ● 4.0	38 1/2	1130
	THLB40x12	12	C ● 7.0	38 1/2	1266
	THLB40x14	14	T ● 1.25	38 1/2	1926
	THLB40x16	16	H ● 3.0	38 1/2	2196

SPREADER BEAMS

Fixed Spreader Beam (FSB30)

FEATURES

- Adds stability to lift where headroom is not limited
- Chain rigging standard, wire rope rigging available
- Complies with ASME STANDARDS





Rated Cap. (Tons)	Part No. *	Spread (Ft.)	Bail / Hook Dimensions A●B●C ●H (in.)	Headroom (In.)	Weight (Lbs.) With Chain	Weight (Lbs.) With Wire Rope
2	FSB4x4	4	A ● .5 B ● 2.5 C ● 5.0 H ● .97	34	55	59
	FSB4x6	6		46	72	75
	FSB4x8	8		58	96	98
	FSB4x10	10		70	111	112
	FSB4x12	12		82	133	133
	FSB4x16	16		106	283	265
	FSB4x20	20		132	474	450
	FSB4x24	24		156	519	486
5	FSB10x4	4	A ● 1.0 B ● 3.5 C ● 7.0 H ● 1.06	37	115	134
	FSB10x6	6		49	135	153
	FSB10x8	8		61	161	178
	FSB10x10	10		73	182	198
	FSB10x12	12		83	237	251
	FSB10x16	16		110	407	394
	FSB10x20	20		134	551	534
	FSB10x24	24		158	791	761
10	FSB20x4	4	A ● 1.25 B ● 4.38 C ● 8.75 H ● 1.5	41	188	231
	FSB20x6	6		53	222	258
	FSB20x8	8		64	266	297
	FSB20x10	10		77	302	327
	FSB20x12	12		86	371	391
	FSB20x16	16		113	533	543
	FSB20x20	20		138	706	705
	FSB20x24	24		163	1110	1098

* Add a "W" for Wire Rope Rigging
Add an "A" for Adjust-A-Leg Rigging

SPREADER BEAMS

Adjustable Spreader Beam (ASB32)

FEATURES

- Great versatility and stability where headroom is not limited
- Chain rigging standard, wire rope rigging available
- Telescoping spread adjusts in 1 in. increments
- Complies with ASME STANDARDS





Rated Cap. (Tons)	Part No. *	Spread (ft.)	Bail / Hook Dimensions A●B●C●H (in.)	Headroom Min/Max (in.)	Weight (Lbs.)	
					With Chain	With Wire Rope
2	ASB4x4-6 ASB4x6-10 ASB4x8-14 ASB4x12-20	4 to 6 6 to 10 8 to 14 12 to 20	A ● .5 B ● 2.36 C ● 3.94 H ● .97	48/57 72/88 96/113 132/166	79 98 192 268	81 98 190 263
5	ASB10x4-6 ASB10x6-10 ASB10x8-14 ASB10x12-20	4 to 6 6 to 10 8 to 14 12 to 20	A ● 1.0 B ● 3.94 C ● 7.09 H ● 1.41	55/64 79/95 102/126 138/172	139 207 266 752	144 205 257 727
10	ASB20x4-6 ASB20x6-10 ASB20x8-14 ASB20x12-20	4 to 6 6 to 10 8 to 14 12 to 20	A ● 1.25 B ● 5.51 C ● 10.63 H ● 1.78	60/69 74/111 108/132 144/163	144 244 548 798	175 265 559 793
15	ASB30x4-6 ASB30x6-10 ASB30x8-14 ASB30x12-20	4 to 6 6 to 10 8 to 14 12 to 20	A ● 1.5 B ● 5.25 C ● 10.5 H ● 2.22	64/72 87/104 111/135 147/180	243 476 623 894	324 541 671 913

* Add a "W" for Wire Rope Rigging

SPREADER BEAMS

Modular Spreader Beam (MSB14)

FEATURES

- Designed to accommodate spreads from 10' to 22'
- Capacities in 1 and 2 tons
- Lightweight
- Faspin with lanyard allows for quick adjustment of spread in 1' increments
- Hair pin cotter to rigging attachment
- Designed and manufactured to ASME standards

Outer Tube



Inner Tube – each system contains (2)

Short Tube



Lifting Eye Dimensions

Rated Cap. (Tons)	Part No.	Spread (ft.) Min/Max	at Min. Spread	at Max. Spread	A	B	C	Hook Opening With Latch	Wt. (lbs.)
1	MSB2	10/22	135.6	150.7	0.5	2.5	5	0.97	195
2	MSB4	10/22	135.6	150.7	1.75	3	6	0.97	275

Recommended Optional Top Rigging (Add "R" to Part Number)
2 Sets of 2-Leg Tuflex Roundslings per Beam

Spreader Part #	For Spreader Lengths	Rigging Part #
MSB2	10' – 16' 16' – 22'	DO-EN30 x 11'6" DO-EN30 x 16'
MSB4	10' – 16' 16' – 22'	DO-EN60 x 11'6" DO-EN60 x 16'

COIL LIFTERS

Dixon Coil Hook with Pivoting Wedge (DCH80)



FEATURES

- For easy upending of coils from horizontal to vertical
- Pivoting wedge great for lifting coils that have been stacked
- Wedge also acts as a coil retainer
- Excels in use with small, lightweight coils
- Good for limited overhead clearance
- Standard handle for easier coil positioning
- Complies with ASME STANDARDS

Rated Cap. (Tons)	Part No.	Max. Coil Width (in.)	Max. Radial (in.)	Min. ID (in.)	Bail Dimensions A●B●C●T (in.)	Wt. (lbs.)
1/2	DCH1x6	6	13	9	.81●2●3.3●.5	20
1/2	DCH1x12	12	13	13	.81●2●3.3●.5	28
1	DCH2x8	8	16	10	.81●2●3.3●.5	23
2	DCH4x10	10	18	12 1/2	1●2.6●4●.75	42
3 1/2	DCH7x12	12	20	14 1/2	1.81●3.6●5.3●1	80

Heavy Duty Coil Hook (HDCH82)



FEATURES

- Designed for heavy duty applications
- High tensile alloy steel plate reduces physical size and weight
- Counter balanced to hang level when empty
- Inside radius on hooks avoid coil edge contact
- Curved coil saddle is standard
- Guide handles for ease of hook positioning
- Handles a wide range of coil widths
- Available with optional padding for additional coil protection
- Complies with ASME STANDARDS

Rated Cap. (Tons)	Part No.	Coil Width (in.) Max/Min	Throat	HR Headroom	Bail Dimensions (in.)				Wt. (lbs.)
					A	B	C	T	
5	HDCH10x36	36/24	24	37-3/8	1-1/2	4	7	1-1/4	420
	HDCH10x48	48/30	24	38	1-1/2	4	7	1-1/4	584
	HDCH10x60	60/36	24	38-1/2	1-1/2	4	7	1-1/4	680
7- 1/2	HDCH15x36	36/24	24	37-1/2	1-1/2	4	7	1-1/2	615
	HDCH15x48	48/30	24	38-1/4	1-1/2	4	7	1-1/2	774
	HDCH15x60	60/36	24	39	1-1/2	4	7	1-1/2	942
10	HDCH20x48	48/30	24	41-1/4	2	5	9	1-3/4	928
	HDCH20x60	60/36	24	41-3/8	2	5	9	1-3/4	1295
	HDCH30x72	72/42	24	42-1/2	2	5	9	1-3/4	1616
15	HDCH30x48	48/30	30	47-7/8	2	5	9	1-3/4	1450
	HDCH30x60	60/36	30	48	2	5	9	1-3/4	1824
	HDCH20x72	72/42	30	48-3/4	2	5	9	1-3/4	2227
20	HDCH40x60	60/36	30	52-1/8	2-1/4	6	12	2	2175
	HDCH40x72	72/42	30	52-5/16	2-1/4	6	12	2	2625

CONSTRUCTION TOOLS

Beam Flange Clamp (BFC)

Great for the lifting of or suspension from I-Beams

FEATURES

- Light weight, portable design
- Jaw opening adjusts to a wide range of beam types and flange widths
- Built-in suspension pin for minimum headroom
- Opposing thread screw spindles for rapid operation
- Large Bail option available for large crane hooks
- Complies with ASME STANDARDS





Large Bail Option

Rated Cap. (Tons)	Part No.	Flange Width (W) (in.)		Suspension Pin Dia. (P) (in.)	Hook Clearance (H) (in.)	Wt. (lbs.)
		Min.	Max.			
1	BFC1	3	7 1/2	7/8	2 1/4	8
2 1/2	BFC2 1/2	3	7 1/2	7/8	2 1/8	9
5	BFC5	6	12	1 3/8	2 1/8	18

Girder Clamp (GC)

Designed for the lifting of or suspension from large girders and I-Beams

FEATURES

- Heavy duty design for lifting wide range of flange beams and plate girders
- Screw-spindle design ensures positive grip
- Opposing thread screw spindles for rapid operation
- Simple design for minimum maintenance
- Complies with ASME STANDARDS





Rated Cap. (Tons)	Part No.	Flange Width (W) (in.)		Max. Flange Thickness (T) (in.)	Shackle Dim. (in.)		Wt. (lbs.)
		Min.	Max.		Stock Dia. (A)	Inside Dia. (B)	
15	GC15	6	24	3	1.6	3.9	234
20	GC20	6	24	3	2.1	5	291
25	GC25	6	24	3	2.1	5	330

CONSTRUCTION TOOLS

Beam Grab (F)
(For vertical lifting only, not suspension)



FEATURES
- Heavy duty design for lifting wide flange beams and plate girders
- Recessed base accepts studs in beam surface
- Eliminates need for slings, chokers and spreader bars
- Complies with ASME STANDARDS

Rated Cap. (Tons)	Part No.	Unit Height (H) (in.)	Flange Width (W) (in.)		Flange Thickness (T) (in.)		Wt. (lbs.)
			Min.	Max.	Min.	Max.	
5	F5	22 3/4	4	4	1/4	1/4	68
			5	5	1/4	3/8	
			6	10	1/4	1	
15	F15	30 1/8	7	7	1/2	3/4	187
			8	8	1/2	1	
			9	9	1/2	1 1/4	
			10	10	1/2	1 1/2	
			11	17	1/4	2	
25	F25	44 7/8	16	17	1 1/4	3	594
			18	24	1	3	
35	F35	52.9	16	18	2.14	4	833
			20	22	2	4	
			24	24	1.75	4	
			26	26	1.75	4	
			28	36	1	4	



Operation:
1. Lower grab onto beam.
2. Lift arms, if necessary, to slide under beam flange.
3. As beam is lifted, pressure forces arms together to secure beam.
4. The heavier the beam, the greater the clamping force.

CONSTRUCTION TOOLS

Pipe Grab (C or S)

(For cast iron or steel pipe only)



FEATURES

- Automatically clamps to pipe when lowered onto it
- Moveable outriggers stabilize the pipe during lift
- No blocking required
- Quick and efficient handling of properly balanced pipe
- Complies with ASME STANDARDS

Rated Cap. (lbs.)	Cast Iron		Steel		Height (H) (in.)	Width (W) (in.)	Depth (D) (in.)	Shackle Dim. (in.) Dia.●B●C	Wt. (lbs.)
	Part No.	Pipe OD (in.)	Part No.	Pipe OD (in.)					
450	C3	4.0	S3	3.5	10	5	6	.38●1.03●1.44	7
600	C4	4.8	S4	4.5	14	8	7	.44●1.16●1.69	9
1000	C6	6.9	S6	6.63	17	11	11	.5●1.31●1.88	15
1400	C8	9.05	S8	8.63	22	13	14	.5●1.31●1.88	25



Operation:

1. Lower grab onto approximate center of pipe. Grab will open and seat on pipe.
2. Lift slowly to check for pipe balance. Never exceed a 15° angle.
3. If angle exceeds 15°, lower pipe and reposition grab.

CONSTRUCTION TOOLS

Pipe Tongs (PLT)

(For vertical lifting only, not suspension)

Adjustable

Fixed

FEATURES

- Pipe Tongs are made of sturdy construction to handle pipe, round bars, castings, etc
- Tongs are provided with bare steel curved gripping arms
- Optional replaceable urethane pads available to protect smooth or polished surfaces
- Load must be balanced and controlled when lifting
- May be used in pairs with a lifting beam for added stability
- Complies with ASME STANDARDS



Specifications – Fixed Diameter

Rated Cap. (lbs.)	Part No.	Dia. (in.)	Headroom (in.) Min.	A (in.)	B (in.)	Wt. (lbs.)
1000	PLTF5	5	15 -1/2	0.5	1.31	17
2000	PLTF8	8	23 -1/2	0.5	1.31	25

Specifications – Adjustable Diameter

Rated Cap. (lbs.)	Part No.	Bare Steel Range Min/Max (in.)	Urethane Pad Range Min/Max (in.)	Headroom When Lifting Min/Max Dia. (in.)	Pad Width (in.)	A (in.)	B (in.)	Wt. (lbs.)
1000	PLTA4	2 - 4	1 1/4 - 3 1/4	13.46 - 11.78	2.25	.5	1.31	6
2000	PLTA8	4 - 8	3 1/4 - 7 1/4	21.06 - 18.70	5	.5	1.31	18
2000	PLTA12	7 - 12	6 1/4 - 11 1/4	39.71 - 34.40	6	.88	2.28	50
2000	PLTA15	10 - 15	9 1/4 - 14 1/4	37 - 33.63	6	.75	2	73





⚠ WARNING

Decreasing the load by bumping or substantial imbalance can, under certain circumstances loosen the grip.
Do not use in diameters other than those specified on nameplate.

CONSTRUCTION TOOLS

Concrete Manhole Lifter (MHL)

FEATURES

- Designed for 4"-6" concrete wall thickness
- Will not damage concrete seat
- Legs can be quickly positioned to balance load
- 2 and 3 leg models available
- Conforms to ASME B30.9 & B30.20

Note: Constant tension required to maintain positive load contact.

Rated Cap. (lbs)	Part No.	Description	Max. Dia.	Wt. (lbs.)
10,000	MHL5	2 Leg Model (42" each)	92.5	131
15,000	MHL7 1/2	3 Leg Model (2@42", 1@72")	101	181
5,000	MHLC	Clamp Only	-	45





2 Leg Model



3 Leg Model



CONSTRUCTION TOOLS

Manhole Sleeve Lifter (MCL)

FEATURES

- Easy to attach and release from sleeve
- The quick and easy way to place cast manhole sleeves
- 2 or 3 leg versions available
- Complies with ASME STANDARDS



TWO LEG LIFTERS

THREE LEG LIFTERS

Rated Cap. (lbs)	Part No.	Description	Wt. (lbs.)
1,000	MCL1/2	2 Leg Model	24
1,500	MCL3/4	3 Leg Model (2@18", 1@30")	26

Note: Flange diameter range 12"-30".







LiftAll®
PRODUCTS FOR BETTER LIFTING

CONSTRUCTION TOOLS

Tea Cup Pipe Carrier (TC)



Model TC66

FEATURES
- Efficiently handles concrete water and sewer pipes
- Three sizes available to lift up to 18 tons
- Standard hand grip for ease of installation
- Optional spoon handle available to assist Tea Cup placement (Model TC66 only) in small diameter pipes
- Complies with ASME STANDARDS



Rated Cap. (Tons)	Part No.	Dimensions (in.)							Wt. (lbs.)
		A	B	C	D	E	F	G	
6.6	TC66	5 9/16	2	2 1/8	1 1/8	4 3/4	1 3/4	1 1/8	9
13	TC130	6	2 1/2	2 5/8	1 3/8	5 3/4	1 3/4	1 3/8	12
18	TC180	8	3	3 1/4	1 5/8	7 5/8	2 3/4	1 5/8	22

Tea Cup Spoon Handle (TCSH) (Includes Bolt-on Lip)

Tea Cup Sling (TCS)

For use with Tea Cup Carriers
- 5 ft. standard length

Rated Cap. (Tons)	Part No.	Sling Dia. (in.)	For Use With:	Wt. (lbs.)
4.9	TCS34	3/4	TC66	9
6.6	TCS78	7/8		14
8.5	TCS1	1	TC130	19
10	TCS118	1 1/8		26
13	TCS114	1 1/4		33
18	TCS112	1 1/2	TC180	52

OPERATION

1. Drop TCS Sling down through hole in pipe.
2. Align and insert Tea Cup Pipe Carrier onto sling.
3. Lift pipe.





CONSTRUCTION TOOLS

Pipe Pick (CPP)
(For concrete pipe only)

FEATURES
- Simple and fast
- No need to reach inside the pipe
- Worker remains above the pipe at all times
- Use to easily join lengths of pipe

Rated Cap. (lbs)	Part No.	Min.Pipe ID (in.)	Bail Dimensions (in.)				Dimensions (in.)				Wt. (lbs.)
			A	B	C	T	D	E	F	G	
3,000	CPP1.5	12	0.69	1.69	1.81	0.63	1.5	23.5	10.25	17.75	10
6,000	CPP3	14	0.81	2	2.19	0.75	2	28.5	12	22.5	18
10,000	CPP5	16	1.06	2.69	2.75	1	2.75	43.75	13	38.75	46



Insert Position

Lifting Position

CONSTRUCTION TOOLS

Barrier Grab (BRG74)



FEATURES

- Labor saving, quick and easy hands-off operation
No slings or chains to attach
- Reduces damage to barrier due to moving
- Replaceable polyurethane lifting pads for unpainted barriers
- Replaceable steel "Dog Point" lifting pads for painted barriers (typical in coastal areas)
- Complies with ASME STANDARDS

Rated Cap. (lbs)	Part No.	Wt. (lbs.)
With Polyurethane Lifting Pads		
8,500	74-4 1/4	450
14,500	74-7 1/4	505
With Steel "Dog Point" Lifting Pads		
8,500	74-4 ¼-D	450
14,500	74-7 ¼-D	505

The Barrier Grab is designed to handle 6"-12" nominal widths at the barrier top (W)





1. Grab in open position is placed onto barrier. Auto-latch will disengage when hoist line becomes slack.



2. Raising crane hook will then cause pads to engage barrier.



3. Lower barrier into position.



4. Slack in hoist line will engage auto-latch, holding grab open for removal and placement of next barrier.

FORK LIFT ACCESSORIES

Fixed Fork Lift Booms (FFLB)

FEATURES
- Fixed length beam design
- Restraining chain with grab hook

FFLB-15 – Single Pick Point
- Use with 1" or 2" wide web sling
- Optional swivel hook available





FFLB-40 – Multiple Pick Points
- 5 alternate hook positions at 1 foot intervals
- Fixed or swivel hooks available







Part No.	Max. Cap. (lbs.)	Headroom (in.)	Maximum Capacity at Hook Position (lbs.)					Wt. (lbs.)
			4'	5'	6'	7'	8'	
FFLB-15	1500	7	-	-	-	-	1,500	185
FFLB-40	4000	6.3	4,000	3,500	3,000	2,500	2,000	200

Single Fork Hook (SFH)

FEATURES
- Easy attachment – no tools required
- Welded construction for durability
- Promotes versatility of fork lift trucks
- 3,000 lb. rated capacity



Fixed Hook Part No.	Swivel Hook Part No.	Dimensions (in.)						Wt. (lbs.)
		A	B	C (Fixed)	C (Swivel)	D	E	
SFHF4	SFHS4	4 1/2	2 1/2	4 11/16	6 9/16	1	1	7
SFHF5	SFHS5	5 1/2	2 1/2	4 11/16	6 9/16	1	1	8
SFHF6	SFHS6	6 1/2	2 1/2	4 11/16	6 9/16	1	1	9

Note: Fixed hook shown, swivel hook also available.

FORK LIFT ACCESSORIES

Telescoping Fork Lift Booms (TFLB)



FEATURES
- Telescoping boom for versatility
- T-Pin locks boom into position
- Handle on end for easy extension of boom
- Swivel hooks with latch are standard
- Restraining chain with grab hook standard
- 12 ft. maximum horizontal reach





Part No.	Maximum Capacity at Hook Position (lbs.)							Wt. (lbs.)
	3'-6'	7'	8'	9'	10'	11'	12'	
TFLB30	3,000	3,000	2,600	2,200	1,900	1,600	1,500	340
TFLB40	4,000	3,200	2,600	2,200	1,900	1,600	1,500	340
TFLB60	6,000	5,000	4,200	3,500	3,000	2,700	2,500	390
TFLB80	8,000	7,000	5,700	4,800	4,100	3,600	3,100	520

Double Fork Beams (DFB)

FEATURES
- Easy attachment – no tools required
- Welded construction for durability
- Promotes versatility of fork lift trucks



Fixed Hook Part No.	Swivel Hook Part No.	Rated Capacity (lbs.)	Dimensions (in.)							Wt. (lbs.)
			A	B	C	F (Fixed)	F (Swivel)	E	F	
DFBF4	DFBS4	4,000	20	3/8	3	9 1/8	9 3/8	1 7/16	1 11/32	20
DFBF10	DFBS10	10,000	24	3/8	3 1/8	10 3/4	12 5/8	1 13/16	1 11/16	45

Note: Fixed hook shown, swivel hook also available.

FORK LIFT ACCESSORIES

Pivoting Fork Lift Booms (PFLB)

FEATURES

- Vertical adjustability in 5 increments up to 40°, 6' 4" maximum height
- Telescoping boom for versatility
- T-Pin locks boom into position
- Handle on end for easy extension of boom
- Swivel hooks with latch are standard
- Restraining chain with grab hook standard reach







Extends to 12' Max. in 1' Increments

Part No.	Maximum Capacity at Hook Position (lbs.)							Wt. (lbs.)
	3'-6'	7'	8'	9'	10'	11'	12'	
PFLB30	3,000	3,000	2,600	2,200	1,900	1,600	1,500	350
PFLB40	4,000	3,200	2,600	2,200	1,900	1,600	1,500	350
PFLB60	6,000	5,000	4,200	3,500	3,000	2,700	2,500	420
PFLB80	8,000	7,000	5,700	4,800	4,100	3,600	3,100	540

LiftAll®
PRODUCTS FOR BETTER LIFTING

SPECIALTY BEAMS

Fiberglass Battery Lifting Beam (BLB)



FEATURES

- Non-conductive for lifting industrial size fork lift or similar batteries
- Up to 70% lighter than other beams
- Available for single or multiple size batteries
- Heavy duty capacities of 4,800 lbs. and 7,000 lbs
- Acid resistant coated polyester straps and hooks
- 36" standard spread – custom lengths available
- Swivel hooks standard





Fixed Length (BLBF)

Rated Cap. (lbs.)	Part No.*	Oblong Size (in.) Dia.●B●C	Headroom (in.)	Wt. (lbs.)
4,800	BLB48F	.63●3●6	29	16
7,000	BLB70F	.75●2.75●5.5	30	20

Adjustable (BLBA)

Rated Cap. (lbs.)	Part No.*	Oblong Size (in.) Dia.●B●C	Headroom (in.)	Wt. (lbs.)
4,800	BLB48A	.63●3●6	39	17
7,000	BLB70A	.75●2.75●5.5	40 1/2	20

Note: Maximum spread range is 12"
* Add a "J" to Part No. for Optional J Hooks

Optional J Hooks

Available in place of swivel hooks



SPECIALTY BEAMS

Battery Lifting Beam (BLBLHA)

Low Headroom, Adjustable

FEATURES

- Low Headroom, 18.3"
- Adjustable to handle batteries of different lengths
- Non-conductive beam
- Acid-resistant, coated polyester straps with either swivel or J-hook

J Hooks Standard
Swivel Hooks Available

Rated Cap. (lbs.)	Part No.	Standard Spread (in.)	Wt. (lbs.)
7,000	BLBLHA	45	110



SPECIALTY SLINGS

Adjust-A-Link

The adjustable, two leg chain sling

Never exceed rated capacities. Chain must be seated at the base of adjusting slot of the Master Control Link.

FEATURES

- Chain Cannot be removed from the master control plate, assuring the capacity rating will not be compromised
- Alloy steel master control plate for strength and reliability
- Each assembly serialized for traceability
- Complies with OSHA – proof tested and certified
- Grade 100 chain provides approximately 25% higher capacities than our previous *Adjust-A-Links* – replaces larger, more expensive slings
- New angled plate design reduces bending torque on chain and plate - reduces wear and extends sling life
- Wider top bearing surface reduces wear to both plate and crane hook
- Versatile – one sling does many jobs
- Using two *Adjust-A-Links* on the same crane hook eliminates the need for expensive triples and quads
- Heat treated alloy steel construction for long sling life
- Yellow powder coating on master plate and hooks prevents rust – extends sling life
- More compact plate design fits larger hooks for easier rigging
- Less bulky than typical double adjustable chain slings
- High visibility yellow fittings make assembly easy to spot
- Easily adjustable to accommodate a wide range of applications
- No time wasted searching for just the right sling





Single



Double



Basket

Chain Size (in.)	[1]Rated Capacity * (lbs.)		Dimensions (in.)					6 ft. Length		10 ft. Length		14 ft. Length	
	Single @ 90°	Double @ 60°	Eye Width A	Eye Height B	Overall Width C	Overall Length D	Hook Opening E	Part No.	(lbs.)	Part No.	(lbs.)	Part No.	(lbs.)
7/32	2,700	4,700	2 3/16	2 11/16	3 15/16	5 1/8	15/16	30001G10	4.2	30002G10	6.2		
9/32	4,300	7,400	2 7/8	3 3/16	5 1/16	6 1/2	1 1/16	30003G10	7.5	30004G10	10.5		
3/8	8,800	15,200	3 3/4	4 1/8	6 3/4	8 11/16	1 9/16			30005G10	18.5	30006G10	24.5
1/2	12,000	20,800	4 3/8	4 3/8	9 3/4	12 3/4	2			30007	42	30008	52

SPECIALTY SLINGS

Adjust-A-Leg

The adjustable, two leg wire rope sling





FEATURES

- Easily adjust the legs for a level lift of unbalanced and non-symmetrical loads
- Can be locked in place for repetitive lifts
- Use in pairs for 4 point lifts
- Can be used as top rigging for spreader beams
- Great as rigging to move machinery
- Complies with ASME STANDARDS

Rated Cap.* (Tons) (Legs @ 45˚)	Part No.	Std. Reach (ft.)	Rope Dia. (in.)	Top Assembly Dim. (in.) A●B●C●T	Hook Size (Tons)	Wt. (lbs.)
1	AAL1	3	5/16	1.13●3.13●5●.63	1	7.5
2	AAL2	4	5/16	1.13●3.13●5●.63	1 1/2	20
4	AAL4	6	7/16	1.13●3.13●5●.63	3	32
6	AAL6	9	9/16	1.75●5.25●8.38●.81	4 1/2	76
8	AAL8	9	5/8	1.75●5.25●8.38●.88	7	90
12	AAL12	9	3/4	2.38●5.63●8.75●1.06	11	152
15	AAL15	9	7/8	2.38●5.63●8.75●1.06	11	175

* Reach should be a length of 70% or greater of the distance between pick up points.

Operation

For a level lift, adjust the leg lengths so that the master plate is above the approximate center of gravity. Test position by lifting only until one end of the load is raised. Lower and reposition master plate and legs for another test. Repeat until load raises without tilting. Adjust-A-Leg must be loaded to at least 10% of rated capacity before legs will fully lock into place.

Typical Applications



Level lifting of non-symetrical loads where lift points are not equidistant from center of gravity.



Level lifting of symetrical loads where lift points are not equidistant from center of load.



Lifting of any load at an angle.

GANTRY CRANES

Fixed Steel (H90)



FEATURES

- Balanced design allows for easy rolling, even under load
- Simple bolt together construction
- Includes 4 steel swivel casters
- Easy set-up and maintenance
- Conforms to AISC, OSHA and CMAA specifications

Rated Cap. (Tons)	Height Under Beam (H) in Ft.	Nominal Span (Ft.)	A	B	C	D (in.)	E (in.)	Caster Dia. (in.)	Weight (Lbs.)	Model No.
1	10	10	10' 4"	11' 6"	5' 6"	6	3.33	6	825	H90-1-10/10
		12	12' 4"	13' 6"	5' 6"	8	4	6	930	H90-1-10/12
		14	14' 4"	15' 6"	5' 6"	8	4	6	967	H90-1-10/14
		16	16' 4"	17' 6"	5' 6"	10	4.66	6	1136	H90-1-10/16
	12	10	10' 4"	11' 6"	6' 6"	6	3.33	6	913	H90-1-12/10
		12	12' 4"	13' 6"	6' 6"	8	4	6	1018	H90-1-12/12
		14	14' 4"	15' 6"	6' 6"	8	4	6	1055	H90-1-12/14
		16	16' 4"	17' 6"	6' 6"	10	4.66	6	1224	H90-1-12/16
	14	10	10' 4"	11' 6"	7' 6"	6	3.33	6	977	H90-1-14/10
		12	12' 4"	13' 6"	7' 6"	8	4	6	1082	H90-1-14/12
		14	14' 4"	15' 6"	7' 6"	8	4	6	1119	H90-1-14/14
		16	16' 4"	17' 6"	7' 6"	10	4.66	6	1288	H90-1-14/16
	16	10	10' 4"	11' 6"	7' 6"	6	3.33	6	1081	H90-1-16/10
		12	12' 4"	13' 6"	7' 6"	8	4	6	1186	H90-1-16/12
		14	14' 4"	15' 6"	7' 6"	8	4	6	1223	H90-1-16/14
		16	16' 4"	17' 6"	7' 6"	10	4.66	6	1392	H90-1-16/16

Rated Cap. (Tons)	Height Under Beam (H) in Ft.	Nominal Span (Ft.)	A	B	C	D (in.)	E (in.)	Caster Dia. (in.)	Weight (Lbs.)	Model No.
2	10	10	10' 4"	11' 6"	5' 6"	8	4	8	949	H90-2-10/10
		12	12' 4"	13' 6"	5' 6"	8	4	8	986	H90-2-10/12
		14	14' 4"	15' 6"	5' 6"	10	4.66	8	1131	H90-2-10/14
		16	16' 4"	17' 6"	5' 6"	10	4.66	8	1182	H90-2-10/16
	12	10	10' 4"	11' 6"	6' 6"	8	4	8	1041	H90-2-12/10
		12	12' 4"	13' 6"	6' 6"	8	4	8	1078	H90-2-12/12
		14	14' 4"	15' 6"	6' 6"	10	4.66	8	1223	H90-2-12/14
		16	16' 4"	17' 6"	6' 6"	10	4.66	8	1274	H90-2-12/16
	14	10	10' 4"	11' 6"	7' 6"	8	4	8	1101	H90-2-14/10
		12	12' 4"	13' 6"	7' 6"	8	4	8	1138	H90-2-14/12
		14	14' 4"	15' 6"	7' 6"	10	4.66	8	1283	H90-2-14/14
		16	16' 4"	17' 6"	7' 6"	10	4.66	8	1334	H90-2-14/16
	16	10	10' 4"	11' 6"	7' 6"	8	4	8	1205	H90-2-16/10
		12	12' 4"	13' 6"	7' 6"	8	4	8	1242	H90-2-16/12
		14	14' 4"	15' 6"	7' 6"	10	4.66	8	1387	H90-2-16/14
		16	16' 4"	17' 6"	7' 6"	10	4.66	8	1438	H90-2-16/16
3	10	10	9' 3"	11' 6"	5' 6"	10	4.66	8	1107	H90-3-10/10
		12	11' 3"	13' 6"	5' 6"	10	4.66	8	1157	H90-3-10/12
		14	13' 3"	15' 6"	5' 6"	10	4.66	8	1208	H90-3-10/14
		16	15' 3"	17' 6"	5' 6"	12	5	8	1427	H90-3-10/16
	12	10	9' 3"	11' 6"	6' 6"	10	4.66	8	1229	H90-3-12/10
		12	11' 3"	13' 6"	6' 6"	10	4.66	8	1279	H90-3-12/12
		14	13' 3"	15' 6"	6' 6"	10	4.66	8	1330	H90-3-12/14
		16	15' 3"	17' 6"	6' 6"	12	5	8	1529	H90-3-12/16
	14	10	9' 3"	11' 6"	7' 6"	10	4.66	8	1350	H90-3-14/10
		12	11' 3"	13' 6"	7' 6"	10	4.66	8	1400	H90-3-14/12
		14	13' 3"	15' 6"	7' 6"	10	4.66	8	1451	H90-3-14/14
		16	15' 3"	17' 6"	7' 6"	12	5	8	1670	H90-3-14/16
	16	10	9' 3"	11' 6"	7' 6"	10	4.66	8	1473	H90-3-16/10
		12	11' 3"	13' 6"	7' 6"	10	4.66	8	1523	H90-3-16/12
		14	13' 3"	15' 6"	7' 6"	10	4.66	8	1574	H90-3-16/14
		16	15' 3"	17' 6"	7' 6"	12	5	8	1793	H90-3-16/16
5	10	10	9' 3"	11' 6"	5' 6"	12	5	8	1397	H90-5-10/10
		12	11' 3"	13' 6"	5' 6"	12	5	8	1467	H90-5-10/12
		14	13' 3"	15' 6"	5' 6"	15	5.5	8	1537	H90-5-10/14
		16	15' 3"	17' 6"	5' 6"	15	5.5	8	1992	H90-5-10/16
	12	10	9' 3"	11' 6"	6' 6"	12	5	8	1519	H90-5-12/10
		12	11' 3"	13' 6"	6' 6"	12	5	8	1589	H90-5-12/12
		14	13' 3"	15' 6"	6' 6"	15	5.5	8	1659	H90-5-12/14
		16	15' 3"	17' 6"	6' 6"	15	5.5	8	2114	H90-5-12/16
	14	10	9' 3"	11' 6"	7' 6"	12	5	8	1640	H90-5-14/10
		12	11' 3"	13' 6"	7' 6"	12	5	8	1710	H90-5-14/12
		14	13' 3"	15' 6"	7' 6"	15	5.5	8	1780	H90-5-14/14
		16	15' 3"	17' 6"	7' 6"	15	5.5	8	2235	H90-5-14/16
	16	10	9' 3"	11' 6"	7' 6"	12	5	8	1763	H90-5-16/10
		12	11' 3"	13' 6"	7' 6"	12	5	8	1833	H90-5-16/12
		14	13' 3"	15' 6"	7' 6"	15	5.5	8	1903	H90-5-16/14
		16	15' 3"	17' 6"	7' 6"	15	5.5	8	2358	H90-5-16/16

LiftAll®
PRODUCTS FOR BETTER LIFTING

GANTRY CRANES

Adjustable Steel (K90)



FEATURES

- Balanced design allows for easy rolling, even under load
- Simple bolt together construction
- Includes 4 steel swivel casters
- Easy set-up and maintenance
- Height adjustable in 1 ft. increments
- Conforms to AISC, OSHA and CMAA specifications

Rated Cap. (Tons)	Max.Height Under Beam (H) in Ft.	Nominal Span (Ft.)	A	B	C	D (in.)	E (in.)	Caster Dia. (in.)	Min.Height Under Beam (H)	Weight (Lbs.)	Model No.
1	10	10	10' 4"	11' 6"	5' 6"	6	3.33	6	10' 5"	847	K90-1-10/10
		12	12' 4"	13' 6"	5' 6"	8	4	6	10' 5"	952	K90-1-10/12
		14	14' 4"	15' 6"	5' 6"	8	4	6	10' 5"	989	K90-1-10/14
		16	16' 4"	17' 6"	5' 6"	10	4.66	6	10' 5"	1158	K90-1-10/16
	12	10	10' 4"	11' 6"	6' 6"	6	3.33	6	10' 5"	944	K90-1-12/10
		12	12' 4"	13' 6"	6' 6"	8	4	6	10' 5"	1049	K90-1-12/12
		14	14' 4"	15' 6"	6' 6"	8	4	6	10' 5"	1086	K90-1-12/14
		16	16' 4"	17' 6"	6' 6"	10	4.66	6	10' 5"	1225	K90-1-12/16
	14	10	10' 4"	11' 6"	7' 6"	6	3.33	6	10' 5"	1028	K90-1-14/10
		12	12' 4"	13' 6"	7' 6"	8	4	6	10' 5"	1133	K90-1-14/12
		14	14' 4"	15' 6"	7' 6"	8	4	6	10' 5"	1170	K90-1-14/14
		16	16' 4"	17' 6"	7' 6"	10	4.66	6	10' 5"	1339	K90-1-14/16
	16	10	10' 4"	11' 6"	7' 6"	6	3.33	6	10' 5"	1132	K90-1-16/10
		12	12' 4"	13' 6"	7' 6"	8	4	6	10' 5"	1237	K90-1-16/12
		14	14' 4"	15' 6"	7' 6"	8	4	6	10' 5"	1274	K90-1-16/14
		16	16' 4"	17' 6"	7' 6"	10	4.66	6	10' 5"	1443	K90-1-16/16

Rated Cap. (Tons)	Max.Height Under Beam (H) in Ft.	Nominal Span (Ft.)	A	B	C	D (in.)	E (in.)	Caster Dia. (in.)	Min.Height Under Beam (H)	Weight (Lbs.)	Model No.
2	10	10	10' 4"	11' 6"	5' 6"	8	4	8	6' 8"	971	K90-2-10/10
		12	12' 4"	13' 6"	5' 6"	8	4	8	6' 8"	1008	K90-2-10/12
		14	14' 4"	15' 6"	5' 6"	10	4.66	8	6' 8"	1153	K90-2-10/14
		16	16' 4"	17' 6"	5' 6"	10	4.66	8	6' 8"	1204	K90-2-10/16
	12	10	10' 4"	11' 6"	6' 6"	8	4	8	7' 8"	1068	K90-2-12/10
		12	12' 4"	13' 6"	6' 6"	8	4	8	7' 8"	1105	K90-2-12/12
		14	14' 4"	15' 6"	6' 6"	10	4.66	8	7' 8"	1250	K90-2-12/14
		16	16' 4"	17' 6"	6' 6"	10	4.66	8	7' 8"	1301	K90-2-12/16
	14	10	10' 4"	11' 6"	7' 6"	8	4	8	8' 8"	1152	K90-2-14/10
		12	12' 4"	13' 6"	7' 6"	8	4	8	8' 8"	1189	K90-2-14/12
		14	14' 4"	15' 6"	7' 6"	10	4.66	8	8' 8"	1334	K90-2-14/14
		16	16' 4"	17' 6"	7' 6"	10	4.66	8	8' 8"	1385	K90-2-14/16
	16	10	10' 4"	11' 6"	7' 6"	8	4	8	10' 8"	1256	K90-2-16/10
		12	12' 4"	13' 6"	7' 6"	8	4	8	10' 8"	1293	K90-2-16/12
		14	14' 4"	15' 6"	7' 6"	10	4.66	8	10' 8"	1438	K90-2-16/14
		16	16' 4"	17' 6"	7' 6"	10	4.66	8	10' 8"	1489	K90-2-16/16
3	10	10	9' 3"	11' 6"	5' 6"	10	4.66	8	6' 11"	1165	K90-3-10/10
		12	11' 3"	13' 6"	5' 6"	10	4.66	8	6' 11"	1215	K90-3-10/12
		14	13' 3"	15' 6"	5' 6"	10	4.66	8	6' 11"	1266	K90-3-10/14
		16	15' 3"	17' 6"	5' 6"	12	5	8	6' 11"	1485	K90-3-10/16
	12	10	9' 3"	11' 6"	6' 6"	10	4.66	8	7' 11"	1292	K90-3-12/10
		12	11' 3"	13' 6"	6' 6"	10	4.66	8	7' 11"	1342	K90-3-12/12
		14	13' 3"	15' 6"	6' 6"	10	4.66	8	7' 11"	1393	K90-3-12/14
		16	15' 3"	17' 6"	6' 6"	12	5	8	7' 11"	1612	K90-3-12/16
	14	10	9' 3"	11' 6"	7' 6"	10	4.66	8	8' 11"	1416	K90-3-14/10
		12	11' 3"	13' 6"	7' 6"	10	4.66	8	8' 11"	1466	K90-3-14/12
		14	13' 3"	15' 6"	7' 6"	10	4.66	8	8' 11"	1517	K90-3-14/14
		16	15' 3"	17' 6"	7' 6"	12	5	8	8' 11"	1736	K90-3-14/16
	16	10	9' 3"	11' 6"	7' 6"	10	4.66	8	10' 11"	1543	K90-3-16/10
		12	11' 3"	13' 6"	7' 6"	10	4.66	8	10' 11"	1593	K90-3-16/12
		14	13' 3"	15' 6"	7' 6"	10	4.66	8	10' 11"	1644	K90-3-16/14
		16	15' 3"	17' 6"	7' 6"	12	5	8	10' 11"	1863	K90-3-16/16
5	10	10	9' 3"	11' 6"	5' 6"	12	5	8	7'	1455	K90-5-10/10
		12	11' 3"	13' 6"	5' 6"	12	5	8	7'	1525	K90-5-10/12
		14	13' 3"	15' 6"	5' 6"	15	5.5	8	7'	1595	K90-5-10/14
		16	15' 3"	17' 6"	5' 6"	15	5.5	8	7'	2050	K90-5-10/16
	12	10	9' 3"	11' 6"	6' 6"	12	5	8	8'	1582	K90-5-12/10
		12	11' 3"	13' 6"	6' 6"	12	5	8	8'	1652	K90-5-12/12
		14	13' 3"	15' 6"	6' 6"	15	5.5	8	8'	1722	K90-5-12/14
		16	15' 3"	17' 6"	6' 6"	15	5.5	8	8'	2177	K90-5-12/16
	14	10	9' 3"	11' 6"	7' 6"	12	5	8	9'	1706	K90-5-14/10
		12	11' 3"	13' 6"	7' 6"	12	5	8	9'	1776	K90-5-14/12
		14	13' 3"	15' 6"	7' 6"	15	5.5	8	9'	1846	K90-5-14/14
		16	15' 3"	17' 6"	7' 6"	15	5.5	8	9'	2301	K90-5-14/16
	16	10	9' 3"	11' 6"	7' 6"	12	5	8	11'	1833	K90-5-16/10
		12	11' 3"	13' 6"	7' 6"	12	5	8	11'	1903	K90-5-16/12
		14	13' 3"	15' 6"	7' 6"	15	5.5	8	11'	1973	K90-5-16/14
		16	15' 3"	17' 6"	7' 6"	15	5.5	8	11'	2428	K90-5-16/16

GANTRY CRANES

Fixed Aluminum (HA90)



FEATURES

- Light-weight Aluminum construction
- Balanced design allows for easy rolling, even under load
- Simple bolt together construction
- Includes 4 poly-coated swivel casters
- Easy set-up and maintenance
- Conforms to AISC, OSHA and CMAA specifications

Rated Cap. (Tons)	Height Under Beam (H)	Nominal Span (Ft.)	A	B	C	D (in.)	E (in.)	Caster Dia. (in.)	Weight (Lbs.)	Model No.
1	7' 6 "	6	6' 10"	8' 4"	4'	6	3.33	6	212	HA90-1-7/6
		9	9'	10' 6"	4'	8	4	6	238	HA90-1-7/9
		11	11'	12' 6"	4'	8	4	6	251	HA90-1-7/11
	9' 2"	6	6' 10"	8' 4"	5'	6	3.33	6	234	HA90-1-9/6
		9	9'	10' 6"	5'	8	4	6	260	HA90-1-9/9
		11	11'	12' 6"	5'	8	4	6	273	HA90-1-9/11
	10' 10"	6	6' 10"	8' 4"	6'	6	3.33	6	258	HA90-1-10/6
		9	9'	10' 6"	6'	8	4	6	284	HA90-1-10/9
		11	11'	12' 6"	6'	8	4	6	297	HA90-1-10/11
2	7' 6 "	6	6' 4"	8' 4"	4'	8	4	8	351	HA90-2-7/6
		8	8' 6"	10' 6"	4'	10	4.66	8	408	HA90-2-7/8
		10	10' 6"	12' 6"	4'	10	4.66	8	429	HA90-2-7/10
	9' 2"	6	6' 4"	8' 4"	5'	8	4	8	371	HA90-2-9/6
		8	8' 6"	10' 6"	5'	10	4.66	8	428	HA90-2-9/8
		10	10' 6"	12' 6"	5'	10	4.66	8	449	HA90-2-9/10
	10' 10"	6	6' 4"	8' 4"	6'	8	4	8	401	HA90-2-10/6
		8	8' 6"	10' 6"	6'	10	4.66	8	458	HA90-2-10/8
		10	10' 6"	12' 6"	6'	10	4.66	8	479	HA90-2-10/10

GANTRY CRANES

Adjustable Aluminum (KA90)



FEATURES

- Light-weight Aluminum construction
- Balanced design allows for easy rolling, even under load
- Simple bolt together construction
- Includes 4 poly-coated swivel casters
- Easy set-up and maintenance
- Height adjustable in 6 in. increments
- Conforms to AISC, OSHA and CMAA specifications

Rated Cap. (Tons)	Max.Height Under Beam (H)	Nominal Span (Ft.)	A	B	C	D (in.)	E (in.)	Caster Dia. (in.)	Min.Height Under Beam (H)	Weight (Lbs.)	Model No.
1	7' 6"	6	6' 7"	8' 4"	4'	6	3.44	6	5' 6"	350	KA90-1-7/6
		8	8' 9"	10' 6"	4'	8	4	6	5' 6"	375	KA90-1-7/8
		10	10' 9"	12' 6"	4'	8	4	6	5' 6"	390	KA90-1-7/10
	9' 2"	6	6' 7"	8' 4"	5'	6	3.44	6	6' 2"	360	KA90-1-9/6
		8	8' 9"	10' 6"	5'	8	4	6	6' 2"	385	KA90-1-9/8
		10	10' 9"	12' 6"	5'	8	4	6	6' 2"	400	KA90-1-9/10
	10' 10"	6	6' 7"	8' 4"	6'	6	3.44	6	7' 10"	385	KA90-1-10/6
		8	8' 9"	10' 6"	6'	8	4	6	7' 10"	410	KA90-1-10/8
		10	10' 9"	12' 6"	6'	8	4	6	7' 10"	425	KA90-1-10/10
	12' 6"	6	6' 7"	8' 4"	6' 6"	6	3.44	6	9' 6"	415	KA90-1-12/6
		8	8' 9"	10' 6"	6' 6"	8	4	6	9' 6"	440	KA90-1-12/8
		10	10' 9"	12' 6"	6' 6"	8	4	6	9' 6"	455	KA90-1-12/10
2	7' 6"	6	6'	8' 4"	4'	8	4	8	5' 6"	460	KA90-2-7/6
		8	8' 2"	10' 6"	4'	10	4.66	8	5' 6"	500	KA90-2-7/8
		10	10' 6"	12' 6"	4'	10	4.66	8	5' 6"	525	KA90-2-7/10
	9' 2"	6	6'	8' 4"	5'	8	4	8	6' 2"	485	KA90-2-9/6
		8	8' 2"	10' 6"	5'	10	4.66	8	6' 2"	525	KA90-2-9/8
		10	10' 6"	12' 6"	5'	10	4.66	8	6' 2"	550	KA90-2-9/10
	10' 10"	6	6'	8' 4"	6'	8	4	8	7' 10"	520	KA90-2-10/6
		8	8' 2"	10' 6"	6'	10	4.66	8	7' 10"	560	KA90-2-10/8
		10	10' 6"	12' 6"	6'	10	4.66	8	7' 10"	585	KA90-2-10/10
	12' 6"	6	6'	8' 2"	6' 6"	8	4	8	9' 6"	530	KA90-2-12/6
		8	8' 2"	10' 6"	6' 6"	10	4.66	8	9' 6"	570	KA90-2-12/8
		10	10' 6"	12' 6"	6' 6"	10	4.66	8	9' 6"	595	KA90-2-12/10